

**CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD****REGION 9, SAN DIEGO REGION**

9174 Sky Park Court, Suite 100  
San Diego, CA 92123  
(858) 467-2952 • Fax (858) 571-6972  
<http://www.waterboards.ca.gov>

**TENTATIVE ORDER NO. R9-2008-0048**  
**NPDES NO. CA0109151**

**WASTE DISCHARGE REQUIREMENTS**  
**BAE SYSTEMS SAN DIEGO SHIP REPAIR INC.**  
**DISCHARGE TO THE SAN DIEGO BAY**

The following Discharger is subject to waste discharge requirements as set forth in this Order:

**Table 1. Discharger Information**

<b>Discharger</b>	<b>BAE Systems San Diego Ship Repair Inc.</b>
<b>Name of Facility</b>	<b>BAE Systems San Diego Ship Repair Inc.</b>
<b>Facility Address</b>	<b>2205 East Belt Street</b>
	<b>San Diego, CA 92113</b>
	<b>San Diego County</b>
The U.S. Environmental Protection Agency (USEPA) and the Regional Water Quality Control Board have classified this discharge as a major discharge.	

The discharge by the Owner from the discharge points identified below is subject to waste discharge requirements as set forth in this Order:

**Table 2. Discharge Locations**

<b>Discharge Point</b>	<b>Effluent Description</b>	<b>Discharge Point Latitude</b>	<b>Discharge Point Longitude</b>	<b>Receiving Water</b>
BW-001 (POSD)	Ballast Water	XXXXXX	XXXXXX	San Diego Bay
BW-002 (AFDL)	Ballast Water	XXXXXX	XXXXXX	San Diego Bay
FP-001 (Pier 3)	Fire protection water	32° 41' 25" N	117° 8' 41" W	San Diego Bay
FP-002 (Building 13)	Fire protection water	32° 41' 29" N	117° 8' 39" W	San Diego Bay
PW-001 (Pier 1)	Potable water leaks from hoses	32° 41' 38" N	117° 8' 46" W	San Diego Bay
PW-002 (Pier 3)	Potable water leaks from hoses	32° 41' 29" N	117° 8' 41" W	San Diego Bay
SC-001 (Pier 1)	Steam condensate leaks from hoses	32° 41' 28" N	117° 8' 46" W	San Diego Bay
SC-002 (Pier 3)	Steam condensate leaks from hoses	32° 41' 29" N	117° 8' 41" W	San Diego Bay
WW-001 (Pier 1)	Water weight test bags	32° 41' 28" N	117° 8' 46" W	San Diego Bay

ADMINISTRATIVE DRAFT

Discharge Point	Effluent Description	Discharge Point Latitude	Discharge Point Longitude	Receiving Water
WW-002 (Pier 3)	Water weight test bags	32° 41' 29" N	117° 8' 41" W	San Diego Bay
SW-001	Contact storm water	32° 41' 33" N	117° 8' 43" W	San Diego Bay
SW-002	Contact storm water	32° 41' 32" N	117° 8' 41" W	San Diego Bay
SW-003	Contact storm water	32° 41' 32" N	117° 8' 40" W	San Diego Bay
SW-004	Contact storm water	32° 41' 29" N	117° 8' 36" W	San Diego Bay
SW-005	Contact storm water	32° 41' 30" N	117° 8' 35" W	San Diego Bay
SW-006	Contact storm water	32° 41' 26" N	117° 8' 36" W	San Diego Bay

**Table 3. Administrative Information**

This Order was adopted by the Regional Water Quality Control Board on:	<Adoption Date>
This Order shall become effective on:	<Effective Date>
This Order shall expire on:	<Expiration Date>
The Discharger shall file a Report of Waste Discharge in accordance with title 23, California Code of Regulations, as application for issuance of new waste discharge requirements no later than:	[Choose: <u>180 days prior to the Order expiration date</u> OR <u>&lt;insert date&gt;</u> ]

I, John Robertus, Executive Officer, do hereby certify that this Order with all attachments is a full, true, and correct copy of an Order adopted by the California Regional Water Quality Control Board, San Diego Region, on **<Adoption Date>**.

**TENTATIVE**

\_\_\_\_\_  
John Robertus, Executive Officer

**Table of Contents**

I.	Facility Information .....	5
II.	Findings .....	6
III.	Discharge Prohibitions .....	12
IV.	Effluent Limitations and Discharge Specifications.....	13
	A. Effluent Limitations – Discharge Point Nos. BW-001, BW-002, FP-001, FP-002, PW-001, PW-002, SC-001, SC-002, WW-001, and WW-002.....	13
	B. Land Discharge Specifications – Not Applicable .....	15
	C. Reclamation Specifications – Not Applicable .....	15
V.	Receiving Water Limitations.....	16
	A. Surface Water Limitation .....	16
	B. Groundwater Limitations – Not Applicable.....	18
VI.	Provisions.....	19
	A. Standard Provisions .....	19
	B. Monitoring and Reporting Program (MRP) Requirements.....	20
	C. Special Provisions .....	21
	1. Reopener Provisions .....	21
	2. Special Studies, Technical Reports and Additional Monitoring Requirements .....	22
	3. Best Management Practices and Pollution Prevention.....	22
	4. Construction, Operation and Maintenance Specifications.....	22
	5. Special Provisions for Municipal Facilities (POTWs Only) – Not Applicable.....	22
	6. Other Special Provisions .....	22
	7. Compliance Schedules.....	22
VII.	Compliance Determination.....	23
	A. General.....	23
	B. Multiple Sample Data. ....	23
	C. Average Monthly Effluent Limitation (AMEL).....	24
	D. Average Weekly Effluent Limitation (AWEL) .....	24
	E. Maximum Daily Effluent Limitation (MDEL) .....	24
	F. Instantaneous Minimum Effluent Limitation.....	24
	G. Instantaneous Maximum Effluent Limitation.....	25
	H. Mass Emission Rate.....	25

**List of Tables**

Table 1.	Discharger Information.....	1
Table 2.	Discharge Locations.....	1
Table 3.	Administrative Information.....	2
Table 4.	Facility Information .....	5
Table 5.	Basin Plan Beneficial Uses .....	8
Table 6.	Effluent Limitations For All Discharges.....	13
Table 7.	Summary of Additional Effluent Limitations for Fire Protection Water .....	13
Table 8.	Summary of Additional Effluent Limitations for Steam Condensate .....	14
Table 9.	Summary of Additional Effluent Limitations for Water Weight Bag Effluent.....	14
Table 10.	Interim Effluent Limitations for Fire Protection Water.....	14
Table 11.	Interim Effluent Limitations for Steam Condensate .....	15
Table 12.	Interim Effluent Limitations for Water Weight Bag Effluent.....	15

ADMINISTRATIVE DRAFT

Table 13. Receiving Water Turbidity Objectives.....16

### List of Attachments

Attachment A – Definitions .....	A-1
Attachment B – Map.....	B-2
Attachment C – Flow Schematic .....	C-3
Attachment D – Standard Provisions .....	D-3
Attachment E – Monitoring and Reporting Program.....	E-3
Attachment F – Fact Sheet.....	F-3
Attachment G – Best Management Practices Plan Requirements .....	F-3

ADMINISTRATIVE DRAFT



**I. FACILITY INFORMATION**

The following Discharger is subject to waste discharge requirements as set forth in this Order:

**Table 4. Facility Information**

<b>Discharger</b>	<b>BAE Systems San Diego Ship Repair Inc.</b>
<b>Name of Facility</b>	<b>BAE Systems San Diego Ship Repair Inc.</b>
<b>Facility Address</b>	<b>2205 East Belt Street</b>
	<b>San Diego, CA 92113</b>
	<b>San Diego County</b>
<b>Facility Contact, Title, and Phone</b>	<b>Sandor Halvax, Environmental Engineering, (619) 238-1000 ext. 1060</b>
<b>Mailing Address</b>	<b>SAME</b>
<b>Type of Facility</b>	<b>Shipbuilding and Repair (SIC Code # 3731)</b>
<b>Facility Design Flow</b>	<b>Not Applicable</b>

**ADMINISTRATIVE DRAFT**

## II. FINDINGS

The California Regional Water Quality Control Board, San Diego Region (hereinafter Regional Water Board), finds:

**A. Background.** BAE Systems San Diego Ship Repair Inc. (hereinafter Discharger) is currently discharging pursuant to Order No. R9-2002-0161 and National Pollutant Discharge Elimination System (NPDES) Permit No. CA0109151. The Discharger submitted a Report of Waste Discharge, dated May 11, 2007, and applied for a NPDES permit renewal to discharge drydock ballast water, fire protection water, potable water leaks from hoses, steam condensate leaks from hoses, and water weight test bag effluent, from numerous discharge locations in BAE Systems San Diego Ship Repair Inc., hereinafter Facility. Contact storm water is generally not discharged to San Diego Bay, but is treated on-site and then discharged to a municipal treatment plant for disposal. However, discharges of storm water may occur at the Facility to the San Diego Bay when the on-site holding capacity is exceeded or the storm water collection and treatment system is not operating properly.

For the purposes of this Order, references to the "discharger" or "permittee" in applicable federal and state laws, regulations, plans, or policy are held to be equivalent to references to the Discharger herein.

**B. Facility Description.** The Discharger operates a shipyard. Discharges from the Facility to the San Diego Bay include drydock ballast tank water, fire protection water, drips of potable water and steam condensate from hoses supplying these services to ships, effluent from weight test bags, and storm water. The supply water for the fire protection water, cooling water, dry dock ballast water, and weight test bags is pumped from the San Diego Bay. In the NPDES report of waste discharge (ROWD) submitted to the Regional Water Board, dated May 11, 2007, the Discharger states that the non-contact cooling water discharges from building 13 (for the compressor air system) have been eliminated.

A description of each discharge is provided in section II.A of Attachment F (Fact Sheet) to this Order. Attachment B provides a map of the area around the Facility. Attachment C provides a flow schematic of the facility.

**C. Legal Authorities.** This Order is issued pursuant to section 402 of the federal Clean Water Act (CWA) and implementing regulations adopted by the U.S. Environmental Protection Agency (USEPA) and chapter 5.5, division 7 of the California Water Code (commencing with section 13370). It shall serve as a NPDES permit for point source discharges from this facility to surface waters. This Order also serves as Waste Discharge Requirements (WDRs) pursuant to article 4, chapter 4, division 7 of the Water Code (commencing with section 13260).

**D. Background and Rationale for Requirements.** The Regional Water Board developed the requirements in this Order based on information submitted as part of the application, through monitoring and reporting programs, and other available information. The Fact

ADMINISTRATIVE DRAFT

Sheet (Attachment F), which contains background information and rationale for Order requirements, is hereby incorporated into this Order and constitutes part of the Findings for this Order. Attachments A through E and G are also incorporated into this Order.

- E. California Environmental Quality Act (CEQA).** Under Water Code section 13389, this action to adopt an NPDES permit is exempt from the provisions of CEQA, Public Resources Code sections 21100-21177.
- F. Technology-based Effluent Limitations.** Section 301(b) of the CWA and implementing USEPA permit regulations at section 122.44, title 40 of the Code of Federal Regulations<sup>1</sup>, require that permits include conditions meeting applicable technology-based requirements at a minimum, and any more stringent effluent limitations necessary to meet applicable water quality standards. The discharge authorized by this Order must meet minimum federal technology-based requirements based on Best Professional Judgment (BPJ) in accordance with Part 125, section 125.3. A detailed discussion of the technology-based effluent limitations development is included in the Fact Sheet (Attachment F).
- G. Water Quality-based Effluent Limitations.** Section 301(b) of the CWA and section 122.44(d) require that permits include limitations more stringent than applicable federal technology-based requirements where necessary to achieve applicable water quality standards.

Section 122.44(d)(1)(i) mandates that permits include effluent limitations for all pollutants that are or may be discharged at levels that have the reasonable potential to cause or contribute to an exceedance of a water quality standard, including numeric and narrative objectives within a standard. Where reasonable potential has been established for a pollutant, but there is no numeric criterion or objective for the pollutant, water quality-based effluent limitations (WQBELs) must be established using: (1) USEPA criteria guidance under CWA section 304(a), supplemented where necessary by other relevant information; (2) an indicator parameter for the pollutant of concern; or (3) a calculated numeric water quality criterion, such as a proposed state criterion or policy interpreting the state's narrative criterion, supplemented with other relevant information, as provided in section 122.44(d)(1)(vi).

- H. Water Quality Control Plans.** The Regional Water Board adopted a Water Quality Control Plan for the San Diego Basin (hereinafter Basin Plan) on September 8, 1994, and last amended on April 25, 2007, that designates beneficial uses, establishes water quality objectives, and contains implementation programs and policies to achieve those objectives for all waters addressed through the plan. Beneficial uses applicable to the San Diego Bay are as follows:

---

<sup>1</sup> All further statutory references are to title 40 of the Code of Federal Regulations unless otherwise indicated.

**Table 5. Basin Plan Beneficial Uses**

Discharge Point Nos.	Receiving Water Name	Beneficial Use(s)
BW-001, BW-002; FP-001, FP-002; PW-001, PW-002; SC-001, SC-002; WW-001, WW-002; SW-001 through SW-006	San Diego Bay	<u>Existing:</u> Industrial Service Supply (IND); navigation (NAV); contact water recreation (REC1); non-contact water recreation (REC2); commercial and sport fishing (COMM); preservation of biological habitats of special significance (BIOL); estuarine habitat (EST); wildlife habitat (WILD); preservation of rare, threatened or endangered species (RARE); marine habitat (MAR); migration of aquatic organisms (MIGR); shellfish harvesting (SHELL)

Requirements of this Order implement the Basin Plan.

Under section 303(d) of the 1972 Clean Water Act, states, territories and authorized tribes are required to develop lists of water quality limited segments. The waters on these lists do not meet water quality standards, even after point sources of pollution have installed the minimum required levels of pollution control technology. On November 30, 2006 USEPA gave final approval to California's 2006 section 303(d) List of Water Quality Limited Segments. The San Diego Bay, as a whole, is listed as impaired for polychlorinated biphenyls (PCBs). Additional portions of the San Diego Bay are listed as impaired for applicable parameters. Two portions of the San Diego Bay applicable to the Facility include, "San Diego Bay Shoreline, near Coronado Bridge", "San Diego Bay Shoreline, between Sampson and 28<sup>th</sup> Streets", and "San Diego Bay Shoreline, near Chollas Creek". These portions of the San Diego Bay are listed in the 303(d) list as impaired for: benthic community effects, copper, mercury, polycyclic aromatic hydrocarbons (PAHs), PCBs, sediment toxicity, and zinc.

No applicable TMDL has been adopted by the Regional Water Board and approved by USEPA. A TMDL for sediment toxicity is currently being developed for the "San Diego Bay Shoreline, near Chollas Creek".

The State Water Board adopted the *Water Quality Control Plan for Control of Temperature in the Coastal and Interstate Water and Enclosed Bays and Estuaries of California* (Thermal Plan) on May 18, 1972, and amended this plan on September 18, 1975. This plan contains temperature objectives for surface waters. Requirements of this Order implement the Thermal Plan.

- I. **National Toxics Rule (NTR) and California Toxics Rule (CTR).** USEPA adopted the NTR on December 22, 1992, and later amended it on May 4, 1995 and November 9, 1999. About 40 criteria in the NTR applied in California. On May 18, 2000, USEPA adopted the CTR. The CTR promulgated new toxics criteria for California and, in addition, incorporated the previously adopted NTR criteria that were applicable in the state. The CTR was amended on February 13, 2001. These rules contain water quality criteria for priority pollutants.

ADMINISTRATIVE DRAFT

- J. State Implementation Policy.** On March 2, 2000, the State Water Board adopted the Policy for Implementation of Toxics Standards for Inland Surface Waters, Enclosed Bays, and Estuaries of California (State Implementation Policy or SIP). The SIP became effective on April 28, 2000 with respect to the priority pollutant criteria promulgated for California by the USEPA through the NTR and to the priority pollutant objectives established by the Regional Water Board in the Basin Plan. The SIP became effective on May 18, 2000 with respect to the priority pollutant criteria promulgated by the USEPA through the CTR. The State Water Board adopted amendments to the SIP on February 24, 2005 that became effective on July 13, 2005. The SIP establishes implementation provisions for priority pollutant criteria and objectives and provisions for chronic toxicity control. Requirements of this Order implement the SIP.
- K. Compliance Schedules and Interim Requirements.** Section 2.1 of the SIP provides that, based on a Discharger's request and demonstration that it is infeasible for an existing Discharger to achieve immediate compliance with an effluent limitation derived from a CTR criterion, compliance schedules may be allowed in an NPDES permit. Unless an exception has been granted under section 5.3 of the SIP, a compliance schedule may not exceed 5 years from the date that the permit is issued or reissued, nor may it extend beyond 10 years from the effective date of the SIP (or May 18, 2010) to establish and comply with CTR criterion-based effluent limitations. Where a compliance schedule for a final effluent limitation exceeds 1 year, the Order must include interim numeric limitations for that constituent or parameter. Where allowed by the Basin Plan, compliance schedules and interim effluent limitations or discharge specifications may also be granted to allow time to implement a new or revised water quality objective. This Order does include compliance schedules and interim effluent limitations. A detailed discussion of the basis for the compliance schedule(s) and interim effluent limitation(s) and/or discharge specifications is included in the Fact Sheet.
- L. Alaska Rule.** On March 30, 2000, USEPA revised its regulation that specifies when new and revised state and tribal water quality standards (WQS) become effective for CWA purposes. (40 CFR § 131.21; 65 Fed. Reg. 24641 (April 27, 2000).) Under the revised regulation (also known as the Alaska rule), new and revised standards submitted to USEPA after May 30, 2000, must be approved by USEPA before being used for CWA purposes. The final rule also provides that standards already in effect and submitted to USEPA by May 30, 2000 may be used for CWA purposes, whether or not approved by USEPA.
- M. Stringency of Requirements for Individual Pollutants.** This Order contains both technology-based and water quality-based effluent limitations for individual pollutants. The technology-based effluent limitations consist of restrictions on oil and grease, settleable solids, turbidity, and pH (upper limitation). Restrictions on oil and grease, settleable solids, turbidity, and pH (upper limitation) are discussed in section III.B of the Fact Sheet. This Order's technology-based pollutant restrictions implement the minimum, applicable federal technology-based requirements. In addition to numeric technology-based limitations, this Order requires the implementation of a Best Management Practices (BMP) Plan. To carry out the purpose and intent of the CWA,

the previous Order required the Discharger to develop and implement a BMP Plan, as authorized by CWA section 304(e) and section 402(p), for toxic pollutants and hazardous substances, and for the control of storm water discharges. The continued implementation and updating of this BMP Plan is carried over from the previous Order.

WQBELs have been scientifically derived to implement water quality objectives that protect beneficial uses. Both the beneficial uses and the water quality objectives have been approved pursuant to federal law and are the applicable federal water quality standards. To the extent that toxic pollutant WQBELs were derived from the CTR, the CTR is the applicable standard pursuant to section 131.38. The scientific procedures for calculating the individual WQBELs for priority pollutants are based on the CTR-SIP, which was approved by USEPA on May 18, 2000. All beneficial uses and water quality objectives contained in the Basin Plan were approved under State law and submitted to and approved by USEPA prior to May 30, 2000. Any water quality objectives and beneficial uses submitted to USEPA prior to May 30, 2000, but not approved by USEPA before that date, are nonetheless "applicable water quality standards for purposes of the CWA" pursuant to section 131.21(c)(1). Collectively, this Order's restrictions on individual pollutants are no more stringent than required to implement the requirements of the CWA.

- N. Antidegradation Policy.** Section 131.12 requires that the state water quality standards include an antidegradation policy consistent with the federal policy. The State Water Board established California's antidegradation policy in State Water Board Resolution No. 68-16. Resolution No. 68-16 incorporates the federal antidegradation policy where the federal policy applies under federal law. Resolution No. 68-16 requires that existing quality of waters be maintained unless degradation is justified based on specific findings. The Regional Water Board's Basin Plan implements, and incorporates by reference, both the state and federal antidegradation policies. As discussed in detail in the Fact Sheet the permitted discharge is consistent with the antidegradation provision of section 131.12 and State Water Board Resolution No. 68-16.
- O. Anti-Backsliding Requirements.** Sections 402(o)(2) and 303(d)(4) of the CWA and federal regulations at title 40, Code of Federal Regulations section 122.44(l) prohibit backsliding in NPDES permits. These anti-backsliding provisions require effluent limitations in a reissued permit to be as stringent as those in the previous permit, with some exceptions where limitations may be relaxed. All effluent limitations in this Order are at least as stringent as the effluent limitations in the previous Order.
- P. Endangered Species Act.** This Order does not authorize any act that results in the taking of a threatened or endangered species or any act that is now prohibited, or becomes prohibited in the future, under either the California Endangered Species Act (Fish and Game Code sections 2050 to 2097) or the Federal Endangered Species Act (16 U.S.C.A. sections 1531 to 1544). This Order requires compliance with effluent limits, receiving water limits, and other requirements to protect the beneficial uses of waters of the state. The Discharger is responsible for meeting all requirements of the applicable Endangered Species Act.

- Q. Monitoring and Reporting.** Section 122.48 requires that all NPDES permits specify requirements for recording and reporting monitoring results. Water Code sections 13267 and 13383 authorizes the Regional Water Board to require technical and monitoring reports. The Monitoring and Reporting Program establishes monitoring and reporting requirements to implement federal and State requirements. This Monitoring and Reporting Program is provided in Attachment E.

Sediment monitoring requirements have been carried over from Order No. R9-2002-0161 to determine compliance with receiving water objectives and to determine the impacts of the operation on the surrounding sediment and biota. Storm water monitoring requirements have been carried over from Order No. R9-2002-0161 to determine the effectiveness of the best management practices (BMP) Program and determine compliance with receiving water objectives. Operational monitoring requirements have been carried over from Order No. R9-2002-0161 to determine the effective of the BMP Plan and ensure that appropriate BMPs are properly implemented.

- R. Standard and Special Provisions.** Standard Provisions, which apply to all NPDES permits in accordance with section 122.41, and additional conditions applicable to specified categories of permits in accordance with section 122.42, are provided in Attachment D. The Discharger must comply with all standard provisions and with those additional conditions that are applicable under section 122.42. The Regional Water Board has also included in this Order special provisions applicable to the Discharger. A rationale for the special provisions contained in this Order is provided in the attached Fact Sheet.

Section 13263.3 of the California Water Code states that pollution prevention should be the first step in the hierarchy for reducing pollution and managing wastes. Further, section 13263.3 (d)(1) states that a Regional Water Board may require a discharger to complete and implement a pollution prevention plan if that discharger significantly contributes, or has the potential to significantly contribute, to the creation of toxic hot spots. The results of a reasonable potential analysis detailed in section IV.C.3 of Attachment F to this Order (Fact Sheet) indicate the Discharger has potential to contribute to the creation of toxic hot spots for arsenic, copper, and lead in San Diego Bay. This Order requires the Discharger to develop and implement a pollution prevention plan for arsenic, copper, and lead to help reduce pollutants in the wastewaters to levels below water quality criteria and obtain consistent compliance with effluent limitations.

- S. Provisions and Requirements Implementing State Law.** The provisions/requirements in section VI.C.3.b of this Order are included to implement state law only. These provisions/requirements are not required or authorized under the federal CWA; consequently, violations of these provisions/requirements are not subject to the enforcement remedies that are available for NPDES violations.

- T. Notification of Interested Parties.** The Regional Water Board has notified the Discharger and interested agencies and persons of its intent to prescribe Waste Discharge Requirements for the discharge and has provided them with an opportunity to

submit their written comments and recommendations. Details of notification are provided in the Fact Sheet of this Order.

- U. Consideration of Public Comment.** The Regional Water Board, in a public meeting, heard and considered all comments pertaining to the discharge. Details of the Public Hearing are provided in the Fact Sheet of this Order.

THEREFORE, IT IS HEREBY ORDERED, that this Order supercedes Order No. R9-2002-0161 except for enforcement purposes, and, in order to meet the provisions contained in division 7 of the Water Code (commencing with section 13000) and regulations adopted thereunder, and the provisions of the CWA and regulations and guidelines adopted thereunder, the Discharger shall comply with the requirements in this Order.

### III. DISCHARGE PROHIBITIONS

- A. The Discharger shall comply with all requirements of the Basin Plan Waste Discharge Prohibitions which are hereby included in this Order by reference.
- B. The discharge of sewage, except as noted in the Basin Plan Waste Discharge Prohibitions, to San Diego Bay is prohibited.
- C. The discharge of industrial process water, including hydroblast water, is prohibited.
- D. The discharge of the first flush of storm water runoff from high risk areas is prohibited, except if the pollutants in the discharge are reduced to the extent that compliance with ACUTE TOXICITY LIMIT REFERENCE.
- E. The discharges of municipal and industrial waste sludge and untreated sludge digester supernatant, centrate, or filtrate to San Diego Bay is prohibited.
- F. The discharge of rubbish, refuse, debris, materials of petroleum origin, waste zinc plates, abrasives, primer, paint, paint chips, solvents, and marine fouling organisms, and the deposition of such wastes at any place where they could eventually be discharged is prohibited. This prohibition does not apply to the discharge of marine fouling organisms removed from unpainted, uncoated surfaces by underwater operations and discharges that result from floating booms that were installed for "Force Protection" purposes. Rubbish and refuse include, but are not limited to, any cans, bottles, paper, plastic, vegetable matter, or dead animals deposited or caused to be deposited by man.
- G. The discharge of materials of petroleum origin in sufficient quantities to be visible is prohibited.
- H. The discharge or bypassing of untreated waste to San Diego Bay is prohibited. This prohibition does not apply to non-contact cooling water, miscellaneous low volume water, and fire protection water streams which comply with the requirements of this Order for elevated temperature waste discharges and which do not contain pollutants or waste other than heat.

ADMINISTRATIVE DRAFT



- I. The discharge of polychlorinated biphenyl compounds, such as those used for transformer fluid, is prohibited.
- J. The discharge of wastes and pollutants from underwater operations, such as underwater paint and coating removal and underwater hull cleaning, is prohibited. This prohibition does not apply to the discharge of marine fouling organisms removed from unpainted and uncoated surfaces by underwater operations, or to discharges that result from the cleaning of floating booms that were installed for "Force Protection" purposes.

#### IV. EFFLUENT LIMITATIONS AND DISCHARGE SPECIFICATIONS

##### A. Effluent Limitations – Discharge Point Nos. BW-001, BW-002, FP-001, FP-002, PW-001, PW-002, SC-001, SC-002, WW-001, and WW-002

##### 1. Final Effluent Limitations – Discharge Point Nos. BW-001, BW-002, FP-001, FP-002, PW-001, PW-002, SC-001, SC-002, WW-001, and WW-002

The Discharger shall maintain compliance with the following effluent limitations at Discharge Point Nos. BW-001, BW-002, FP-001, FP-002, PW-001, PW-002, SC-001, SC-002, WW-001, and WW-002, with compliance measured at Monitoring Location Nos. BW-001, BW-002, FP-001, FP-002, PW-001, PW-002, SC-001, SC-002, WW-001, and WW-002 as described in the attached Monitoring and Reporting Program (MRP):

**Table 6. Effluent Limitations For All Discharges**

Parameter	Units	Effluent Limitations		
		Average Monthly	Weekly Average	Instantaneous Maximum
Oil and Grease	mg/L	25	40	75
Settleable Solids	ml/L	1.0	1.5	3.0
Turbidity	NTU	75	100	225
pH	pH units	--	--	<sup>1</sup>
Temperature	°F	--	--	<sup>2</sup>

<sup>1</sup> Within limits of 7.0 – 9.0 at all times.

<sup>2</sup> At no time shall any discharge be greater than 20°F over the natural temperature of the receiving water.

##### 2. Final Effluent Limitations – Discharge Point Nos. FP-001 and FP-002

The Discharger shall maintain compliance with the following effluent limitations at Discharge Point Nos. FP-001 and FP-002, with compliance measured at Monitoring Location Nos. FP-001 and FP-002 as described in the attached MRP:

**Table 7. Summary of Additional Effluent Limitations for Fire Protection Water**

Parameter	Units	Effluent Limitations	
		Average Monthly	Maximum Daily
Arsenic, Total Recoverable	µg/L	29.48	59.14
Copper, Total Recoverable	µg/L	2.88	5.78

**3. Final Effluent Limitations – Discharge Point Nos. SC-001 and SC-002**

The Discharger shall maintain compliance with the following effluent limitations at Discharge Point Nos. SC-001 and SC-002, with compliance measured at Monitoring Location Nos. SC-001 and SC-002 as described in the attached MRP:

**Table 8. Summary of Additional Effluent Limitations for Steam Condensate**

Parameter	Units	Effluent Limitations	
		Average Monthly	Maximum Daily
Copper, Total Recoverable	µg/L	2.88	5.78
Lead, Total Recoverable	µg/L	6.98	14.00

**4. Final Effluent Limitations – Discharge Point Nos. WW-001 and WW-002**

The Discharger shall maintain compliance with the following effluent limitations at Discharge Point Nos. WW-001 and WW-002, with compliance measured at Monitoring Location Nos. WW-001 and WW-002 as described in the attached MRP:

**Table 9. Summary of Additional Effluent Limitations for Water Weight Bag Effluent**

Parameter	Units	Effluent Limitations	
		Average Monthly	Maximum Daily
Arsenic, Total Recoverable	µg/L	29.48	59.14
Copper, Total Recoverable	µg/L	2.88	5.78

**5. Interim Effluent Limitations**

- a. During the period beginning the effective date of this Order and ending on May 18, 2010, the Discharger shall maintain compliance with the following limitations at Discharge Point Nos. FP-001 and FP-002, with compliance measured at Monitoring Location Nos. FP-001 and FP-002 as described in the attached MRP. This interim effluent limitations shall apply in lieu of the corresponding final effluent limitations specified for the same parameters during the time period indicated in this provision.

**Table 10. Interim Effluent Limitations for Fire Protection Water**

Parameter	Units	Maximum Daily
Arsenic, Total Recoverable	µg/L	59.14
Copper, Total Recoverable	µg/L	5.78

- b. During the period beginning the effective date of this Order and ending on May 18, 2010, the Discharger shall maintain compliance with the following limitations at Discharge Point Nos. SC-001 and SC-002 with compliance measured at

Monitoring Location Nos. SC-001 and SC-002 as described in the attached MRP. These interim effluent limitations shall apply in lieu of the corresponding final effluent limitations specified for the same parameters during the time period indicated in this provision.

**Table 11. Interim Effluent Limitations for Steam Condensate**

Parameter	Units	Interim Maximum Daily
Copper, Total Recoverable	µg/L	77.3
Lead, Total Recoverable	µg/L	58

- c. During the period beginning the effective date of this Order and ending on May 18, 2010, the Discharger shall maintain compliance with the following limitations at Discharge Point Nos. WW-001 and WW-002, with compliance measured at Monitoring Location Nos. WW-001 and WW-002 as described in the attached MRP. These interim effluent limitations shall apply in lieu of the corresponding final effluent limitations specified for the same parameters during the time period indicated in this provision.

**Table 12. Interim Effluent Limitations for Water Weight Bag Effluent**

Parameter	Units	Interim Maximum Daily
Copper, Total Recoverable	µg/L	10.9

**B. Land Discharge Specifications – Not Applicable**

**C. Reclamation Specifications – Not Applicable**

ADMINISTRATIVE DRAFT

**V. RECEIVING WATER LIMITATIONS****A. Surface Water Limitation**

Receiving water limitations are based on water quality objectives contained in the Basin Plan and are a required part of this Order. The discharge shall not cause the following in the San Diego Bay.

**1. Physical Characteristics**

- a. Waters shall not contain oils, greases waxes, or other materials in concentrations which result in visible film or coating on the surface of the water or on objects in the water, or which cause nuisance or which otherwise adversely affect beneficial uses.
- b. Waters shall not contain floating material, including solids, liquids, foams, and scum in concentrations which cause nuisance or adversely affect beneficial uses.
- c. The suspended sediment load and suspended sediment discharge rate of surface waters shall not be altered in such a manner as to cause nuisance or adversely affect beneficial uses.
- d. Waters shall not contain suspended and settleable solids in concentrations of solids that cause nuisance or adversely affect beneficial uses.
- e. Waters shall not contain taste or odor producing substances at concentrations, which cause a nuisance or adversely affect beneficial uses.

Waters shall be free of changes in turbidity that cause nuisance or adversely affect beneficial uses. The transparency of the waters in lagoons and estuaries shall not be less than 50 percent of the depth at locations where measurement is made by means of a standard Secchi disk, except where lesser transparency is caused by rainfall runoff from undisturbed natural areas and dredging projects conducted in conformance with waste discharge requirements of the Regional Water Board. With these two exceptions, increases in turbidity attributable to controllable water quality factors shall not exceed the following limits:

**Table 13. Receiving Water Turbidity Objectives**

Natural Turbidity	Maximum Increase
0 – 50 NTU	20% over natural turbidity level
50 – 100 NTU	10 NTU
Greater than 100 NTU	10% over natural turbidity level

**2. Thermal Characteristics**

ADMINISTRATIVE DRAFT

Discharges from the Facility shall not exceed the natural temperature of the receiving waters by more than 20°F.

### 3. Chemical Characteristics

- a. Dissolved oxygen levels shall not be less than 5.0 mg/L in waters of the San Diego Bay. The annual mean dissolved oxygen concentration shall not be less than 7 mg/L.
- b. The pH shall not be changed at any time more than 0.2 units from that which occurs naturally. The pH shall not be depressed below 7.0 nor raised above 9.0.
- c. Waters of the San Diego Bay shall not contain biostimulatory substances in concentrations that promote aquatic growth to the extent that such growths cause nuisance or adversely affect beneficial uses.
- d. The discharge of wastes shall not cause concentrations of un-ionized ammonia ( $\text{NH}_3$ ) to exceed 0.025 mg/L (as N) in the San Diego Bay.
- e. No individual pesticide or combination of pesticides shall be present in the water column, sediments or biota at concentration(s) that adversely affect beneficial uses. Pesticides shall not be present at levels which will bioaccumulate in aquatic organisms to levels which are harmful to human health, wildlife or aquatic organisms.

### 4. Bacteriological Characteristics

- a. In waters designated for contact recreation (REC-1), the fecal coliform concentration based on a minimum of not less than five samples for any 30-day period, shall not exceed a log mean of 200/100 ml, nor shall more than 10 percent of the total samples during any 30-day period exceed 400 per 100 ml.
- b. In waters designated for shell fish harvesting (SHELL), the median total coliform concentration throughout the water column for any 30-day period shall not exceed 70/100 ml nor shall more than 10 percent of the samples collected during any 30-day period exceed 230/100 ml for five-tube decimal dilution test or 330/100 ml when a three-tube decimal dilution test is used.
- c. In waters designated for contact recreation (REC-1), the enterococci concentration shall not exceed 35/100 ml in all areas, 104/100 ml in designated beach areas, 276/100 ml in moderately or lightly used areas, and 500/100 ml in infrequently used areas.

### 5. Biological Characteristics

- a. Marine communities, including vertebrate, invertebrate, and plant species, shall not be degraded.

ADMINISTRATIVE DRAFT

- b. The natural taste, odor, and color of fish, shellfish, or other marine resources used for human consumption shall not be altered.
- c. The concentration of organic materials in fish, shellfish, or other marine resources used for human consumption shall not bioaccumulate to levels that are harmful to human health.

#### **6. Radioactivity**

Radionuclides shall not be present in concentrations that are deleterious to human, plant animal, or aquatic life nor that result in the accumulation of radionuclides in the food web to an extent that presents a hazard to human, plant, animal or aquatic life.

#### **7. Toxicity**

All waters shall be maintained free of toxic substances in concentrations that are toxic to, or that produce detrimental physiological responses in human, plan, animal, or aquatic life. Compliance with this objective will be determined by use of indicator organisms, analyses of species diversity, population density, growth anomalies, bioassays of appropriate duration, or other appropriate methods as specified by the Regional Water Board.

#### **B. Groundwater Limitations – Not Applicable**

ADMINISTRATIVE DRAFT

## VI. PROVISIONS

### A. Standard Provisions

1. **Federal Standard Provisions.** The Discharger shall comply with all Standard Provisions included in Attachment D of this Order.
2. **Regional Water Board Standard Provisions.** The Discharger shall comply with the following provisions:
  - a. The Discharger shall comply with all requirements and conditions of this Order. Any permit non-compliance constitutes a violation of the CWA and/or of the CWC and is grounds for enforcement action, permit termination, revocation and reissuance, or modification, or for denial of an application for permit renewal, modification, or reissuance.
  - b. The Discharger shall comply with all applicable federal, state, and local laws and regulations for handling, transport, treatment, or disposal of waste or the discharge of waste to waters of the State in a manner which causes or threatens to cause a condition of pollution, contamination or nuisance as those terms are defined in CWC 13050.
  - c. The Porter-Cologne Water Quality Control Act provides for civil and criminal penalties comparable to, and in some cases greater than, those provided for under the CWA.
  - d. Any noncompliance with this Order is a violation of the CWC and/or the CWA and is grounds for denial of an application for Order renewal or modification.
  - e. No discharge of waste into waters of the State, whether or not the discharge is made pursuant to WDRs, shall create a vested right to continue the discharge. All discharges of wastes into waters of the State are privileges, not rights.
  - f. For purposes of this Order, the term "permittee" used in parts of 40 CFR incorporated into this Order by reference and/or applicable to this Order shall have the same meaning as the term "Discharger" used elsewhere in this Order.
  - g. This Order expires on **<DATE>**, after which, the terms and conditions of this permit are automatically continued pending issuance of a new Order, provided that all requirements of USEPA's NPDES regulations at 40 CFR 122.6 and the State's regulations at CCR Title 23, section 2235.4 regarding the continuation of expired Orders and waste discharge requirements are met.
  - h. Except as provided for in 40 CFR 122.7, no information or documents submitted in accordance with or in application for this permit will be considered confidential, and all such information and documents shall be available for review by the public at the office of the Regional Water Board.

ADMINISTRATIVE DRAFT

- i. A copy of this Order shall be maintained on-site at the Facility, and shall be available to Regional Water Board, State Water Board, and USEPA personnel and/or their authorized representative at all times.
- j. The Discharger shall comply with any interim limitations established by addendum, enforcement action, or revised waste discharge requirements that have been or may be adopted by the Regional Water Board.
- k. Failure to comply with provisions or requirements of this Order, or violation of other applicable laws or regulations governing discharges from this facility, may subject the Discharger to administrative or civil liabilities, criminal penalties, and/or other enforcement remedies to ensure compliance. Additionally, certain violations may subject the Discharger to civil or criminal enforcement from appropriate local, state, or federal law enforcement entities.
- l. In the event the Discharger does not comply or will be unable to comply for any reason, with any prohibition, effluent limitation, discharge specification, or receiving water limitation of this Order, the Discharger shall notify the Regional Water Board by telephone (858) 467-2952 within 24 hours of having knowledge of such noncompliance, and shall confirm this notification in writing within five days, unless the Regional Water Board waives confirmation. The written notification shall state the nature, time, duration, and cause of noncompliance, and shall describe the measures being taken to remedy the current noncompliance and prevent recurrence including, where applicable, a schedule of implementation. Other noncompliance requires written notification as above at the time of the normal monitoring report.

#### **B. Monitoring and Reporting Program (MRP) Requirements**

1. The Discharger shall comply with the MRP, and future revisions thereto, in Attachment E of this Order.
2. Reports required to be submitted to this Regional Water Board shall be sent to:

Executive Officer  
California Regional Water Quality Control Board  
San Diego Region  
9174 Sky Park Court, Suite 100  
San Diego, CA 92123-4340

Notifications required to be provided to this Regional Water Board shall be made to:

Telephone – (858) 467-2952  
Facsimile – (858) 571-6972

3. After notification by the State or Regional Water Board, the Discharger may be required to electronically submit self-monitoring reports. Until such time as electronic



submission of self-monitoring reports is required, the Discharger shall submit discharge monitoring reports (DMRs) in accordance with the requirements described further below.

DMRs must be signed and certified as required by the standard provisions (Attachment D). The Discharger shall submit the original DMR and one copy to:

State Water Resources Control Board  
Discharge Monitoring Report Processing Center  
Post Office Box 671  
Sacramento, CA 95812

All discharge monitoring results must be reported on the official USEPA pre-printed DMR forms (USEPA Form 3320-1). Forms that are self generated or modified cannot be accepted.

### **C. Special Provisions**

#### **1. Reopener Provisions**

- a. This Order may be reopened and modified in accordance with NPDES regulations at 40 CFR Part 122 and 124, as necessary, to include additional conditions or limitations based on newly available information or to implement any USEPA approved, new, State water quality objective.

This Order may be modified, revoked and reissued, or terminated for cause including, but not limited to, the following:

- 1) Violations of any terms or conditions of this Order.
  - 2) Obtaining this Order by misrepresentation or failure to disclose fully all relevant facts.
  - 3) A change in any condition that requires either a temporary or permanent reduction or elimination of the authorized discharge.
- b. This Order may be re-opened and modified, to incorporate in accordance with the provisions set forth in 40 CFR Parts 122 and 124, to include requirements for the implementation of the watershed management approach.
  - c. This Order may be re-opened and modified, revoked, and reissued or terminated in accordance with the provisions of 40 CFR sections 122.44, 122.62 to 122.64, 125.62, and 125.64. Causes for taking such actions include, but are not limited to, failure to comply with any condition of this Order and permit, and endangerment to human health or the environment resulting from the permitted activity.

ADMINISTRATIVE DRAFT

- d. This Order may be re-opened and modified, to incorporate additional limitations, prohibitions, and requirements, based on the results of additional monitoring required by the MRP.
- e. The filing of a request by the Discharger for modifications, revocation and reissuance, or termination of this Order, or a notification of planned change in or anticipated noncompliance with this Order does not stay any condition of this Order.

## 2. Special Studies, Technical Reports and Additional Monitoring Requirements

This subsection includes any requirements for special studies (i.e., mixing zone or dilution studies, sediment monitoring). These studies may be required by the Order, or may be triggered by exceedance of an effluent limitation or other threshold. In some cases, the studies may be optional (e.g., dilution studies). This subsection also includes any special monitoring requirements outside the requirements of the Monitoring and Reporting Program. For example, additional monitoring may include a study of CTR constituents discharged from a new discharge point that has been added to the facility or participation in Regional monitoring programs. A rationale supporting the need for these special provisions should be included in the Fact Sheet.

### a. Toxicity Reduction Requirements [To Be Added Later]

## 3. Best Management Practices and Pollution Prevention

### a. Best Management Practices Plan

The Discharger shall continue to implement a BMP Plan that prevents the discharge of pollutants into the receiving waters at levels that would contribute to the degradation of the receiving waters or otherwise negatively affect the beneficial uses of the receiving water. At a minimum, the BMP Plan shall be developed and implemented in accordance with Attachment G to prevent, or minimize the potential for, the release of pollutants to waters of the State and waters of the United States.

## 4. Construction, Operation and Maintenance Specifications

The Facility shall be operated and maintained in a manner consistent with the BMP Plan as specified in section VI.C.a of this Order.

## 5. Special Provisions for Municipal Facilities (POTWs Only) – Not Applicable

## 6. Other Special Provisions – Not Applicable

## 7. Compliance Schedules

- a. Compliance Schedules for Final Effluent Limitations for Arsenic, Copper, and Lead

- i. By May 18, 2010, the Discharger shall comply with the final effluent limitations for arsenic, copper, and lead. Data submitted by the Discharger over the term of Order No. R9-2002-0161 indicates that the Discharger can not immediately meet applicable water quality criteria. Because this compliance schedule is greater than 1 year, in accordance with the section 2.2.1 of the SIP, the Discharger shall submit semi-annual progress reports in accordance with the Monitoring and Reporting Program.
- ii. **Pollution Prevention Plan.** The Discharger shall prepare and implement a pollution prevention plan for arsenic, copper, and lead, in accordance with CWC section 13263.3(d)(2). The minimum requirements for the pollution prevention plan are outlined in the Fact Sheet, Attachment F, section VII.B.3.b. A work plan and time schedule for preparation of the pollution prevention plan shall be completed and submitted to the Regional Water Board **within 3 months of the effective date of this Order**. The Pollution Prevention Plan shall be completed and submitted to the Regional Water Board **within nine (9) months of the effective date of this Order**, and progress reports shall be submitted in accordance with the Monitoring and Reporting Program.

## VII. COMPLIANCE DETERMINATION

Compliance with the effluent limitations contained in section IV of this Order will be determined as specified below:

### A. General.

Compliance with effluent limitation shall be determined using sample reporting protocols defined in the MRP and Attachment A of this Order. For purpose of reporting and administrative enforcement by the Regional and State Water Boards, the Discharger shall be deemed out of compliance with effluent limitations if the concentration of the constituent in the monitoring sample is greater than the effluent limitation and greater than or equal to the reporting level (RL) or lowest quantifiable level.

### B. Multiple Sample Data.

When determining compliance with an average monthly effluent limitation (AMEL) or maximum daily effluent limitation (MDEL) and more than one sample result is available, the Discharger shall compute the arithmetic mean unless the data set contains one or more reported determination of "Detected, but Not Quantified" (DNQ) or "Not Detected" (ND). In those cases, the Discharger shall compute the median in place of the arithmetic mean in accordance with the following procedure:

1. The data set shall be ranked from low to high, ranking the reported ND determinations lowest, DNQ determinations next, following by quantified values (if any). The order of individual ND or DNQ determinations is unimportant.

2. The median value of the data set shall be determined. If the data set has an odd number of data points, then the median is the middle value. If the data set has an even number of data points, then the median is the average of the two values around the middle unless one or both of the points are ND or DNQ, in which case the median value shall be the lower of the two data points where DNQ is lower than a value and ND is lower than DNQ.

### **C. Average Monthly Effluent Limitation (AMEL).**

If the average (or when applicable, the median determined by subsection B above for multiple sample data) of daily discharges over a calendar month exceeds the AMEL for a given parameter, this will represent a single violation, though the Discharger will be considered out of compliance for each day of that month for that parameter (e.g., resulting in 31 days of non-compliance in a 31-day month). If only a single sample is taken during the calendar month and the analytical result for that sample exceeds the AMEL, the Discharger will be considered out of compliance for days when the discharge occurs. For any one calendar month during which no sample (daily discharge) is taken, no compliance determination can be made for that calendar month.

### **D. Average Weekly Effluent Limitation (AWEL)**

If the average (or when applicable, the median determined by subsection B above for multiple sample data) of daily discharges over a calendar week exceeds the AWEL for a given parameter, this will represent a single violation, though the Discharger will be considered out of compliance for each day of that week for that parameter, resulting in 7 days of non-compliance. If only a single sample is taken during the calendar week and the analytical result for that sample exceeds the AWEL, the Discharger will be considered out of compliance for that calendar week. The Discharger Will only be considered out of compliance for days when the discharge occurs. For any on calendar week during which no sample (daily discharge) is taken, no compliance determination can be made for that calendar week.

### **E. Maximum Daily Effluent Limitation (MDEL)**

If a daily discharge (or when applicable, the median determined by subsection B above for multiple sample data of a daily discharge) exceeds the MDEL for a given parameter, the Discharger will be considered out of compliance for that parameter for that 1 day only within the reporting period. For any 1 day during which no sample is taken, no compliance determination can be made for that day.

### **F. Instantaneous Minimum Effluent Limitation.**

If the analytical result of a single grab sample is lower than the instantaneous minimum effluent limitation for a parameter, the Discharger will be considered out of compliance for that parameter for that single sample. Non-compliance for each sample will be considered separately (e.g., the results of two grab samples taken within a calendar day that both are lower than the instantaneous minimum effluent limitation would result in two instances of non-compliance with the instantaneous minimum effluent limitation).

### G. Instantaneous Maximum Effluent Limitation.

If the analytical result of a single grab sample is higher than the instantaneous maximum effluent limitation for a parameter, the Discharger will be considered out of compliance for that parameter for that single sample. Non-compliance for each sample will be considered separately (e.g., the results of two grab samples taken within a calendar day that both exceed the instantaneous maximum effluent limitation would result in two instances of non-compliance with the instantaneous maximum effluent limitation).

### H. Mass Emission Rate.

1. When applicable, the mass emission rate (MER), in pounds per day, shall be obtained from the following calculation for any calendar day:

$$\text{Mass Emission Rate (lbs/day)} = 8.34 \times Q \times C$$

In which Q and C are the appropriate flow rate in MGD and the constituent concentration in mg/L (i.e., either calendar monthly average or daily value), respectively, and 8.34 is a conversion factor. If a composite sample is taken, then C is the concentration measured in the composite sample and Q is the average flow rate occurring during the period over which the samples are composited.

2. When the concentration of a constituent in an effluent sample is determined to be "ND" or "DNQ", the corresponding MER determined from that sample concentration shall also be reported as "ND" or "DNQ".

## ATTACHMENT A – DEFINITIONS

### Arithmetic Mean ( $\mu$ )

Also called the average, is the sum of measured values divided by the number of samples. For ambient water concentrations, the arithmetic mean is calculated as follows:

Arithmetic mean =  $\mu = \Sigma x / n$       where:  $\Sigma x$  is the sum of the measured ambient water concentrations, and  $n$  is the number of samples.

### Average Monthly Effluent Limitation (AMEL)

The highest allowable average of daily discharges over a calendar month, calculated as the sum of all daily discharges measured during a calendar month divided by the number of daily discharges measured during that month.

### Average Weekly Effluent Limitation (AWEL)

The highest allowable average of daily discharges over a calendar week (Sunday through Saturday), calculated as the sum of all daily discharges measured during a calendar week divided by the number of daily discharges measured during that week.

### Bioaccumulative

Those substances taken up by an organism from its surrounding medium through gill membranes, epithelial tissue, or from food and subsequently concentrated and retained in the body of the organism.

### Carcinogenic

Pollutants are substances that are known to cause cancer in living organisms.

### Coefficient of Variation (CV)

CV is a measure of the data variability and is calculated as the estimated standard deviation divided by the arithmetic mean of the observed values.

### Daily Discharge

Daily Discharge is defined as either: (1) the total mass of the constituent discharged over the calendar day (12:00 am through 11:59 pm) or any 24-hour period that reasonably represents a calendar day for purposes of sampling (as specified in the permit), for a constituent with limitations expressed in units of mass or; (2) the unweighted arithmetic mean measurement of the constituent over the day for a constituent with limitations expressed in other units of measurement (e.g., concentration).

The daily discharge may be determined by the analytical results of a composite sample taken over the course of one day (a calendar day or other 24-hour period defined as a day) or by the arithmetic mean of analytical results from one or more grab samples taken over the course of the day.

For composite sampling, if 1 day is defined as a 24-hour period other than a calendar day, the analytical result for the 24-hour period will be considered as the result for the calendar day in which the 24-hour period ends.

### **Detected, but Not Quantified (DNQ)**

DNQ are those sample results less than the RL, but greater than or equal to the laboratory's MDL.

### **Dilution Credit**

Dilution Credit is the amount of dilution granted to a discharge in the calculation of a water quality-based effluent limitation, based on the allowance of a specified mixing zone. It is calculated from the dilution ratio or determined through conducting a mixing zone study or modeling of the discharge and receiving water.

### **Effluent Concentration Allowance (ECA)**

ECA is a value derived from the water quality criterion/objective, dilution credit, and ambient background concentration that is used, in conjunction with the coefficient of variation for the effluent monitoring data, to calculate a long-term average (LTA) discharge concentration. The ECA has the same meaning as waste load allocation (WLA) as used in USEPA guidance (Technical Support Document For Water Quality-based Toxics Control, March 1991, second printing, EPA/505/2-90-001).

### **Enclosed Bays**

Enclosed Bays means indentations along the coast that enclose an area of oceanic water within distinct headlands or harbor works. Enclosed bays include all bays where the narrowest distance between the headlands or outermost harbor works is less than 75 percent of the greatest dimension of the enclosed portion of the bay. Enclosed bays include, but are not limited to, Humboldt Bay, Bodega Harbor, Tomales Bay, Drake's Estero, San Francisco Bay, Morro Bay, Los Angeles-Long Beach Harbor, Upper and Lower Newport Bay, Mission Bay, and San Diego Bay. Enclosed bays do not include inland surface waters or ocean waters.

### **Estimated Chemical Concentration**

The estimated chemical concentration that results from the confirmed detection of the substance by the analytical method below the ML value.

### **Estuaries**

Estuaries means waters, including coastal lagoons, located at the mouths of streams that serve as areas of mixing for fresh and ocean waters. Coastal lagoons and mouths of streams that are temporarily separated from the ocean by sandbars shall be considered estuaries. Estuarine waters shall be considered to extend from a bay or the open ocean to a point upstream where there is no significant mixing of fresh water and seawater. Estuarine waters included, but are not limited to, the Sacramento-San Joaquin Delta, as defined in Water Code section 12220, Suisun Bay, Carquinez Strait downstream to the Carquinez Bridge, and appropriate areas of the Smith, Mad, Eel, Noyo, Russian, Klamath, San Diego, and Otay rivers. Estuaries do not include inland surface waters or ocean waters.

### **First Flush**

Storm water runoff that occurs between the time a storm event begins and when a minimum of 1 inch of precipitation has been collected in a rain gauge or equivalent measurement device at a location on the site which is representative of precipitation at the site. A storm event is a period of rainfall that is preceded by at least seven days without rainfall.

### High Risk Areas

Areas where wastes or pollutants from ship construction, modification, repair, and maintenance activities (including abrasive blast grit material, primer, paint, paint chips, solvents, oils, fuels, sludges, detergents, cleansers, hazardous substances, toxic pollutants, non-conventional pollutants, materials of petroleum origin, or other substances of water quality significance) are subject to precipitation, run-on, and/or runoff.

### Inland Surface Waters

All surface waters of the State that do not include the ocean, enclosed bays, or estuaries.

### Instantaneous Maximum Effluent Limitation

The highest allowable value for any single grab sample or aliquot (i.e., each grab sample or aliquot is independently compared to the instantaneous maximum limitation).

### Instantaneous Minimum Effluent Limitation

The lowest allowable value for any single grab sample or aliquot (i.e., each grab sample or aliquot is independently compared to the instantaneous minimum limitation).

### Maximum Daily Effluent Limitation (MDEL)

The highest allowable daily discharge of a pollutant, over a calendar day (or 24-hour period). For pollutants with limitations expressed in units of mass, the daily discharge is calculated as the total mass of the pollutant discharged over the day. For pollutants with limitations expressed in other units of measurement, the daily discharge is calculated as the arithmetic mean measurement of the pollutant over the day.

### Median

The middle measurement in a set of data. The median of a set of data is found by first arranging the measurements in order of magnitude (either increasing or decreasing order). If the number of measurements ( $n$ ) is odd, then the median =  $X_{(n+1)/2}$ . If  $n$  is even, then the median =  $(X_{n/2} + X_{(n/2)+1})/2$  (i.e., the midpoint between the  $n/2$  and  $n/2+1$ ).

### Method Detection Limit (MDL)

MDL is the minimum concentration of a substance that can be measured and reported with 99 percent confidence that the analyte concentration is greater than zero, as defined in title 40 of the Code of Federal Regulations, Part 136, Attachment B, revised as of July 3, 1999.

### Minimum Level (ML)

ML is the concentration at which the entire analytical system must give a recognizable signal and acceptable calibration point. The ML is the concentration in a sample that is equivalent to the concentration of the lowest calibration standard analyzed by a specific analytical procedure, assuming that all the method specified sample weights, volumes, and processing steps have been followed.

### Mixing Zone

Mixing Zone is a limited volume of receiving water that is allocated for mixing with a wastewater discharge where water quality criteria can be exceeded without causing adverse effects to the overall water body.



### **Not Detected (ND)**

Sample results which are less than the laboratory's MDL.

### **Ocean Waters**

The territorial marine waters of the State as defined by California law to the extent these waters are outside of enclosed bays, estuaries, and coastal lagoons. Discharges to ocean waters are regulated in accordance with the State Water Board's California Ocean Plan.

### **Persistent Pollutants**

Persistent pollutants are substances for which degradation or decomposition in the environment is nonexistent or very slow.

### **Pollutant Minimization Program (PMP)**

PMP means waste minimization and pollution prevention actions that include, but are not limited to, product substitution, waste stream recycling, alternative waste management methods, and education of the public and businesses. The goal of the PMP shall be to reduce all potential sources of a priority pollutant(s) through pollutant minimization (control) strategies, including pollution prevention measures as appropriate, to maintain the effluent concentration at or below the water quality-based effluent limitation. Pollution prevention measures may be particularly appropriate for persistent bioaccumulative priority pollutants where there is evidence that beneficial uses are being impacted. The Regional Water Board may consider cost effectiveness when establishing the requirements of a PMP. The completion and implementation of a Pollution Prevention Plan, if required pursuant to Water Code section 13263.3(d), shall be considered to fulfill the PMP requirements.

### **Pollution Prevention**

Pollution Prevention means any action that causes a net reduction in the use or generation of a hazardous substance or other pollutant that is discharged into water and includes, but is not limited to, input change, operational improvement, production process change, and product reformulation (as defined in Water Code section 13263.3). Pollution prevention does not include actions that merely shift a pollutant in wastewater from one environmental medium to another environmental medium, unless clear environmental benefits of such an approach are identified to the satisfaction of the State or Regional Water Board.

### **Reporting Level (RL)**

RL is the ML (and its associated analytical method) chosen by the Discharger for reporting and compliance determination from the MLs included in this Order. The MLs included in this Order correspond to approved analytical methods for reporting a sample result that are selected by the Regional Water Board either from Appendix 4 of the SIP in accordance with section 2.4.2 of the SIP or established in accordance with section 2.4.3 of the SIP. The ML is based on the proper application of method-based analytical procedures for sample preparation and the absence of any matrix interferences. Other factors may be applied to the ML depending on the specific sample preparation steps employed. For example, the treatment typically applied in cases where there are matrix-effects is to dilute the sample or sample aliquot by a factor of ten. In such cases, this additional factor must be applied to the ML in the computation of the RL.

### **Satellite Collection System**

ADMINISTRATIVE DRAFT

The portion, if any, of a sanitary sewer system owned or operated by a different public agency than the agency that owns and operates the wastewater treatment facility that a sanitary sewer system is tributary to.

### **Significant Materials**

Raw materials; fuels; materials such as solvents, detergents, and plastic pellets; finished materials such as metallic products; raw materials used in food processing or production; hazardous substances designated under section 101 (14) of Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA); and chemical the facility is required to report pursuant to section 313 of Title III of Superfund Amendments and Reauthorization Act (SARA); fertilizers; pesticides; and waste products such as ashes, slag, and sludge that have the potential to be discharged.

### **Significant Quantities**

Volumes, concentrations, or masses of pollutants that can cause or threaten to cause pollution, contamination, or nuisance; adversely impact human health or the environment; and/or cause or contribute to a violation of any applicable water quality standard for the receiving water or any receiving water limitation.

### **Source of Drinking Water**

Any water designated as municipal or domestic supply (MUN) in a Regional Water Board Basin Plan.

### **Standard Deviation ( $\sigma$ )**

Standard Deviation is a measure of variability that is calculated as follows:

$$\sigma = (\sum[(x - \mu)^2]/(n - 1))^{0.5}$$

where:

x is the observed value;

$\mu$  is the arithmetic mean of the observed values; and


n is the number of samples.

### **Toxicity Reduction Evaluation (TRE)**

TRE is a study conducted in a step-wise process designed to identify the causative agents of effluent or ambient toxicity, isolate the sources of toxicity, evaluate the effectiveness of toxicity control options, and then confirm the reduction in toxicity. The first steps of the TRE consist of the collection of data relevant to the toxicity, including additional toxicity testing, and an evaluation of facility operations and maintenance practices, and best management practices. A Toxicity Identification Evaluation (TIE) may be required as part of the TRE, if appropriate. (A TIE is a set of procedures to identify the specific chemical(s) responsible for toxicity. These procedures are performed in three phases (characterization, identification, and confirmation) using aquatic organism toxicity tests.)

**ADMINISTRATIVE DRAFT**

## ATTACHMENT B.1 – TOPOGRAPHIC MAP




# ADMINISTRATIVE DRAFT

Drawing Reference:  
POINT LOMA (CA)  
U.S.G.S TOPOGRAPHIC MAP  
7.5 MINUTE QUADRANGLE  
*Photorevised 1975*  
*Not to scale*

## SITE LOCATION MAP

BAE SYSTEMS, SAN DIEGO

SAN DIEGO COUNTY



## ATTACHMENT B.2 – SITE MAP

ADMINISTRATIVE DRAFT


# ADMINISTRATIVE DRAFT

THOMAS R. COORD: 1289 C6  
BUSINESS MEJ BAE Systems  
San Diego Ship Repair  
BUSINESS ADDRESS: 2205 E. BELT ST.

SITE MAP: PAGE 1 OF 1  
DATE: 09-06-08  
ZIP CODE: 92113


UPFP#: HK07-109689

REVIEWED BY:  
DATE:




# ATTACHMENT C – FLOW SCHEMATIC

ADMINISTRATIVE DRAFT



# STORM WATER TREATMENT FLOW DIAGRAM



## Note:

There are three (3) outfalls where treatment systems are installed. These treatment systems are still experimental as achievement of the NPDES Toxicity Monitoring Provision cannot be consistently met. Therefore, all storm water is still discharged to sanitary sewer. Additional treatment technologies will be employed in the future in an attempt to economically achieve the toxicity discharge monitoring requirement. One of the main difficulties in testing these systems are that the typical rain event is less than 0.25 inches, making it difficult to flow sufficient water through the systems. Ultraviolet filtration tested with no beneficial effect on toxicity of storm water.

ADMINISTRATIVE DRAFT



## ATTACHMENT D – STANDARD PROVISIONS

### I. STANDARD PROVISIONS – PERMIT COMPLIANCE

#### A. Duty to Comply

3. The Discharger must comply with all of the conditions of this Order. Any noncompliance constitutes a violation of the Clean Water Act (CWA) and the California Water Code and is grounds for enforcement action, for permit termination, revocation and reissuance, or modification; or denial of a permit renewal application. (40 CFR § 122.41(a).)
4. The Discharger shall comply with effluent standards or prohibitions established under section 307(a) of the CWA for toxic pollutants and with standards for sewage sludge use or disposal established under section 405(d) of the CWA within the time provided in the regulations that establish these standards or prohibitions, even if this Order has not yet been modified to incorporate the requirement. (40 CFR § 122.41(a)(1).)

#### B. Need to Halt or Reduce Activity Not a Defense

It shall not be a defense for a Discharger in an enforcement action that it would have been necessary to halt or reduce the permitted activity in order to maintain compliance with the conditions of this Order. (40 CFR § 122.41(c).)

#### C. Duty to Mitigate

The Discharger shall take all reasonable steps to minimize or prevent any discharge or sludge use or disposal in violation of this Order that has a reasonable likelihood of adversely affecting human health or the environment. (40 CFR § 122.41(d).)

#### D. Proper Operation and Maintenance

The Discharger shall at all times properly operate and maintain all facilities and systems of treatment and control (and related appurtenances) which are installed or used by the Discharger to achieve compliance with the conditions of this Order. Proper operation and maintenance also includes adequate laboratory controls and appropriate quality assurance procedures. This provision requires the operation of backup or auxiliary facilities or similar systems that are installed by a Discharger only when necessary to achieve compliance with the conditions of this Order. (40 CFR § 122.41(e).)

#### E. Property Rights

5. This Order does not convey any property rights of any sort or any exclusive privileges. (40 CFR § 122.41(g).)

6. The issuance of this Order does not authorize any injury to persons or property or invasion of other private rights, or any infringement of state or local law or regulations. (40 CFR § 122.5(c).)

#### **F. Inspection and Entry**

The Discharger shall allow the Regional Water Board, State Water Board, United States Environmental Protection Agency (USEPA), and/or their authorized representatives (including an authorized contractor acting as their representative), upon the presentation of credentials and other documents, as may be required by law, to (40 CFR § 122.41(i); Wat. Code, § 13383):

7. Enter upon the Discharger's premises where a regulated facility or activity is located or conducted, or where records are kept under the conditions of this Order (40 CFR § 122.41(i)(1));
8. Have access to and copy, at reasonable times, any records that must be kept under the conditions of this Order (40 CFR § 122.41(i)(2));
9. Inspect and photograph, at reasonable times, any facilities, equipment (including monitoring and control equipment), practices, or operations regulated or required under this Order (40 CFR § 122.41(i)(3)); and
10. Sample or monitor, at reasonable times, for the purposes of assuring Order compliance or as otherwise authorized by the CWA or the Water Code, any substances or parameters at any location. (40 CFR § 122.41(i)(4).)

#### **G. Bypass**

##### **11. Definitions**

- a. "Bypass" means the intentional diversion of waste streams from any portion of a treatment facility. (40 CFR § 122.41(m)(1)(i).)
- b. "Severe property damage" means substantial physical damage to property, damage to the treatment facilities, which causes them to become inoperable, or substantial and permanent loss of natural resources that can reasonably be expected to occur in the absence of a bypass. Severe property damage does not mean economic loss caused by delays in production. (40 CFR § 122.41(m)(1)(ii).)

12. Bypass not exceeding limitations. The Discharger may allow any bypass to occur which does not cause exceedances of effluent limitations, but only if it is for essential maintenance to assure efficient operation. These bypasses are not subject to the provisions listed in Standard Provisions – Permit Compliance I.G.3, I.G.4, and I.G.5 below. (40 CFR § 122.41(m)(2).)

ADMINISTRATIVE DRAFT

**13. Prohibition of bypass.** Bypass is prohibited, and the Regional Water Board may take enforcement action against a Discharger for bypass, unless (40 CFR § 122.41(m)(4)(i)):

- b. Bypass was unavoidable to prevent loss of life, personal injury, or severe property damage (40 CFR § 122.41(m)(4)(i)(A));
- c. There were no feasible alternatives to the bypass, such as the use of auxiliary treatment facilities, retention of untreated wastes, or maintenance during normal periods of equipment downtime. This condition is not satisfied if adequate back-up equipment should have been installed in the exercise of reasonable engineering judgment to prevent a bypass that occurred during normal periods of equipment downtime or preventive maintenance (40 CFR § 122.41(m)(4)(i)(B)); and
- d. The Discharger submitted notice to the Regional Water Board as required under Standard Provisions – Permit Compliance I.G.5 below. (40 CFR § 122.41(m)(4)(i)(C).)

**14.** The Regional Water Board may approve an anticipated bypass, after considering its adverse effects, if the Regional Water Board determines that it will meet the three conditions listed in Standard Provisions – Permit Compliance I.G.3 above. (40 CFR § 122.41(m)(4)(ii).)

**15. Notice**

- e. Anticipated bypass. If the Discharger knows in advance of the need for a bypass, it shall submit a notice, if possible at least 10 days before the date of the bypass. (40 CFR § 122.41(m)(3)(i).)
- f. Unanticipated bypass. The Discharger shall submit notice of an unanticipated bypass as required in Standard Provisions - Reporting V.E below (24-hour notice). (40 CFR § 122.41(m)(3)(ii).)

**H. Upset**

Upset means an exceptional incident in which there is unintentional and temporary noncompliance with technology based permit effluent limitations because of factors beyond the reasonable control of the Discharger. An upset does not include noncompliance to the extent caused by operational error, improperly designed treatment facilities, inadequate treatment facilities, lack of preventive maintenance, or careless or improper operation. (40 CFR § 122.41(n)(1).)

**16. Effect of an upset.** An upset constitutes an affirmative defense to an action brought for noncompliance with such technology based permit effluent limitations if the requirements of Standard Provisions – Permit Compliance I.H.2 below are met. No determination made during administrative review of claims that noncompliance was

caused by upset, and before an action for noncompliance, is final administrative action subject to judicial review. (40 CFR § 122.41(n)(2).)

**17. Conditions necessary for a demonstration of upset.** A Discharger who wishes to establish the affirmative defense of upset shall demonstrate, through properly signed, contemporaneous operating logs or other relevant evidence that (40 CFR § 122.41(n)(3)):

- g. An upset occurred and that the Discharger can identify the cause(s) of the upset (40 CFR § 122.41(n)(3)(i));
- h. The permitted facility was, at the time, being properly operated (40 CFR § 122.41(n)(3)(ii));
- i. The Discharger submitted notice of the upset as required in Standard Provisions – Reporting V.E.2.b below (24-hour notice) (40 CFR § 122.41(n)(3)(iii)); and
- j. The Discharger complied with any remedial measures required under Standard Provisions – Permit Compliance I.C above. (40 CFR § 122.41(n)(3)(iv).)

**18. Burden of proof.** In any enforcement proceeding, the Discharger seeking to establish the occurrence of an upset has the burden of proof. (40 CFR § 122.41(n)(4).)

## **II. STANDARD PROVISIONS – PERMIT ACTION**

### **A. General**

This Order may be modified, revoked and reissued, or terminated for cause. The filing of a request by the Discharger for modification, revocation and reissuance, or termination, or a notification of planned changes or anticipated noncompliance does not stay any Order condition. (40 CFR § 122.41(f).)

### **B. Duty to Reapply**

If the Discharger wishes to continue an activity regulated by this Order after the expiration date of this Order, the Discharger must apply for and obtain a new permit. (40 CFR § 122.41(b).)

### **C. Transfers**

This Order is not transferable to any person except after notice to the Regional Water Board. The Regional Water Board may require modification or revocation and reissuance of the Order to change the name of the Discharger and incorporate such other requirements as may be necessary under the CWA and the Water Code. (40 CFR § 122.41(l)(3); § 122.61.)

ADMINISTRATIVE DRAFT

### III. STANDARD PROVISIONS – MONITORING

- A. Samples and measurements taken for the purpose of monitoring shall be representative of the monitored activity. (40 CFR § 122.41(j)(1).)
- B. Monitoring results must be conducted according to test procedures under Part 136 or, in the case of sludge use or disposal, approved under Part 136 unless otherwise specified in Part 503 unless other test procedures have been specified in this Order. (40 CFR § 122.41(j)(4); § 122.44(i)(1)(iv).)

### IV. STANDARD PROVISIONS – RECORDS

- A. Except for records of monitoring information required by this Order related to the Discharger's sewage sludge use and disposal activities, which shall be retained for a period of at least five years (or longer as required by Part 503), the Discharger shall retain records of all monitoring information, including all calibration and maintenance records and all original strip chart recordings for continuous monitoring instrumentation, copies of all reports required by this Order, and records of all data used to complete the application for this Order, for a period of at least three (3) years from the date of the sample, measurement, report or application. This period may be extended by request of the Regional Water Board Executive Officer at any time. (40 CFR § 122.41(j)(2).)
- B. Records of monitoring information shall include:
  - 19. The date, exact place, and time of sampling or measurements (40 CFR § 122.41(j)(3)(i));
  - 20. The individual(s) who performed the sampling or measurements (40 CFR § 122.41(j)(3)(ii));
  - 21. The date(s) analyses were performed (40 CFR § 122.41(j)(3)(iii));
  - 22. The individual(s) who performed the analyses (40 CFR § 122.41(j)(3)(iv));
  - 23. The analytical techniques or methods used (40 CFR § 122.41(j)(3)(v)); and
  - 24. The results of such analyses. (40 CFR § 122.41(j)(3)(vi).)
- C. Claims of confidentiality for the following information will be denied (40 CFR § 122.7(b)):
  - 25. The name and address of any permit applicant or Discharger (40 CFR § 122.7(b)(1)); and
  - 26. Permit applications and attachments, permits and effluent data. (40 CFR § 122.7(b)(2).)

## V. STANDARD PROVISIONS – REPORTING

### B. Duty to Provide Information

The Discharger shall furnish to the Regional Water Board, State Water Board, or USEPA within a reasonable time, any information which the Regional Water Board, State Water Board, or USEPA may request to determine whether cause exists for modifying, revoking and reissuing, or terminating this Order or to determine compliance with this Order. Upon request, the Discharger shall also furnish to the Regional Water Board, State Water Board, or USEPA copies of records required to be kept by this Order. (40 CFR § 122.41(h); Wat. Code, § 13267.)

### B. Signatory and Certification Requirements

27. All applications, reports, or information submitted to the Regional Water Board, State Water Board, and/or USEPA shall be signed and certified in accordance with Standard Provisions – Reporting V.B.2, V.B.3, V.B.4, and V.B.5 below. (40 CFR § 122.41(k).)
2. All permit applications shall be signed by a responsible corporate officer. For the purpose of this section, a responsible corporate officer means: (i) A president, secretary, treasurer, or vice-president of the corporation in charge of a principal business function, or any other person who performs similar policy- or decision-making functions for the corporation, or (ii) the manager of one or more manufacturing, production, or operating facilities, provided, the manager is authorized to make management decisions which govern the operation of the regulated facility including having the explicit or implicit duty of making major capital investment recommendations, and initiating and directing other comprehensive measures to assure long term environmental compliance with environmental laws and regulations; the manager can ensure that the necessary systems are established or actions taken to gather complete and accurate information for permit application requirements; and where authority to sign documents has been assigned or delegated to the manager in accordance with corporate procedures. (40 CFR § 122.22(a)(1).)
3. All reports required by this Order and other information requested by the Regional Water Board, State Water Board, or USEPA shall be signed by a person described in Standard Provisions – Reporting V.B.2 above, or by a duly authorized representative of that person. A person is a duly authorized representative only if:
  - k. The authorization is made in writing by a person described in Standard Provisions – Reporting V.B.2 above (40 CFR § 122.22(b)(1));
  - l. The authorization specifies either an individual or a position having responsibility for the overall operation of the regulated facility or activity such as the position of plant manager, operator of a well or a well field, superintendent, position of equivalent responsibility, or an individual or position having overall responsibility

ADMINISTRATIVE DRAFT

for environmental matters for the company. (A duly authorized representative may thus be either a named individual or any individual occupying a named position.) (40 CFR § 122.22(b)(2)); and

m. The written authorization is submitted to the Regional Water Board and State Water Board. (40 CFR § 122.22(b)(3).)

4. If an authorization under Standard Provisions – Reporting V.B.3 above is no longer accurate because a different individual or position has responsibility for the overall operation of the facility, a new authorization satisfying the requirements of Standard Provisions – Reporting V.B.3 above must be submitted to the Regional Water Board and State Water Board prior to or together with any reports, information, or applications, to be signed by an authorized representative. (40 CFR § 122.22(c).)
5. Any person signing a document under Standard Provisions – Reporting V.B.2 or V.B.3 above shall make the following certification:

“I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.” (40 CFR § 122.22(d).)

### **C. Monitoring Reports**

28. Monitoring results shall be reported at the intervals specified in the Monitoring and Reporting Program (Attachment E) in this Order. (40 CFR § 122.22(l)(4).)
29. Monitoring results must be reported on a Discharge Monitoring Report (DMR) form or forms provided or specified by the Regional Water Board or State Water Board for reporting results of monitoring of sludge use or disposal practices. (40 CFR § 122.41(l)(4)(i).)
30. If the Discharger monitors any pollutant more frequently than required by this Order using test procedures approved under Part 136 or, in the case of sludge use or disposal, approved under Part 136 unless otherwise specified in Part 503, or as specified in this Order, the results of this monitoring shall be included in the calculation and reporting of the data submitted in the DMR or sludge reporting form specified by the Regional Water Board. (40 CFR § 122.41(l)(4)(ii).)
31. Calculations for all limitations, which require averaging of measurements, shall utilize an arithmetic mean unless otherwise specified in this Order. (40 CFR § 122.41(l)(4)(iii).)

### **D. Compliance Schedules**

ADMINISTRATIVE DRAFT

Reports of compliance or noncompliance with, or any progress reports on, interim and final requirements contained in any compliance schedule of this Order, shall be submitted no later than 14 days following each schedule date. (40 CFR § 122.41(l)(5).)

#### **E. Twenty-Four Hour Reporting**

**32.** The Discharger shall report any noncompliance that may endanger health or the environment. Any information shall be provided orally within 24 hours from the time the Discharger becomes aware of the circumstances. A written submission shall also be provided within five (5) days of the time the Discharger becomes aware of the circumstances. The written submission shall contain a description of the noncompliance and its cause; the period of noncompliance, including exact dates and times, and if the noncompliance has not been corrected, the anticipated time it is expected to continue; and steps taken or planned to reduce, eliminate, and prevent reoccurrence of the noncompliance. (40 CFR § 122.41(l)(6)(i).)

**33.** The following shall be included as information that must be reported within 24 hours under this paragraph (40 CFR § 122.41(l)(6)(ii)):

n. Any unanticipated bypass that exceeds any effluent limitation in this Order. (40 CFR § 122.41(l)(6)(ii)(A).)

o. Any upset that exceeds any effluent limitation in this Order. (40 CFR § 122.41(l)(6)(ii)(B).)

**34.** The Regional Water Board may waive the above-required written report under this provision on a case-by-case basis if an oral report has been received within 24 hours. (40 CFR § 122.41(l)(6)(iii).)

#### **F. Planned Changes**

The Discharger shall give notice to the Regional Water Board as soon as possible of any planned physical alterations or additions to the permitted facility. Notice is required under this provision only when (40 CFR § 122.41(l)(1)):

**35.** The alteration or addition to a permitted facility may meet one of the criteria for determining whether a facility is a new source in section 122.29(b) (40 CFR § 122.41(l)(1)(i)); or

**36.** The alteration or addition could significantly change the nature or increase the quantity of pollutants discharged. This notification applies to pollutants that are not subject to effluent limitations in this Order. (40 CFR § 122.41(l)(1)(ii).)

**37.** The alteration or addition results in a significant change in the Discharger's sludge use or disposal practices, and such alteration, addition, or change may justify the application of permit conditions that are different from or absent in the existing

ADMINISTRATIVE DRAFT



permit, including notification of additional use or disposal sites not reported during the permit application process or not reported pursuant to an approved land application plan. (40 CFR § 122.41(l)(1)(iii).)

#### **G. Anticipated Noncompliance**

The Discharger shall give advance notice to the Regional Water Board or State Water Board of any planned changes in the permitted facility or activity that may result in noncompliance with General Order requirements. (40 CFR § 122.41(l)(2).)

#### **H. Other Noncompliance**

The Discharger shall report all instances of noncompliance not reported under Standard Provisions – Reporting V.C, V.D, and V.E above at the time monitoring reports are submitted. The reports shall contain the information listed in Standard Provision – Reporting V.E above. (40 CFR § 122.41(l)(7).)

#### **I. Other Information**

When the Discharger becomes aware that it failed to submit any relevant facts in a permit application, or submitted incorrect information in a permit application or in any report to the Regional Water Board, State Water Board, or USEPA, the Discharger shall promptly submit such facts or information. (40 CFR § 122.41(l)(8).)

### **VI. STANDARD PROVISIONS – ENFORCEMENT**

- C.** The Regional Water Board is authorized to enforce the terms of this permit under several provisions of the Water Code, including, but not limited to, sections 13385, 13386, and 13387

### **VII. ADDITIONAL PROVISIONS – NOTIFICATION LEVELS**

#### **D. Non-Municipal Facilities**

Existing manufacturing, commercial, mining, and silvicultural Dischargers shall notify the Regional Water Board as soon as they know or have reason to believe (40 CFR § 122.42(a)):

- 38.** That any activity has occurred or will occur that would result in the discharge, on a routine or frequent basis, of any toxic pollutant that is not limited in this Order, if that discharge will exceed the highest of the following "notification levels" (40 CFR § 122.42(a)(1)):

- p. 100 micrograms per liter (µg/L) (40 CFR § 122.42(a)(1)(i));
- q. 200 µg/L for acrolein and acrylonitrile; 500 µg/L for 2,4-dinitrophenol and 2-methyl-4,6-dinitrophenol; and 1 milligram per liter (mg/L) for antimony (40 CFR § 122.42(a)(1)(ii));

ADMINISTRATIVE DRAFT

- r. Five (5) times the maximum concentration value reported for that pollutant in the Report of Waste Discharge (40 CFR § 122.42(a)(1)(iii)); or
  - s. The level established by the Regional Water Board in accordance with section 122.44(f). (40 CFR § 122.42(a)(1)(iv).)
- 39.** That any activity has occurred or will occur that would result in the discharge, on a non-routine or infrequent basis, of any toxic pollutant that is not limited in this Order, if that discharge will exceed the highest of the following "notification levels" (40 CFR § 122.42(a)(2)):
- t. 500 micrograms per liter (µg/L) (40 CFR § 122.42(a)(2)(i));
  - u. 1 milligram per liter (mg/L) for antimony (40 CFR § 122.42(a)(2)(ii));
  - v. Ten (10) times the maximum concentration value reported for that pollutant in the Report of Waste Discharge (40 CFR § 122.42(a)(2)(iii)); or
  - w. The level established by the Regional Water Board in accordance with section 122.44(f). (40 CFR § 122.42(a)(2)(iv).)

ADMINISTRATIVE DRAFT

**ATTACHMENT E – MONITORING AND REPORTING PROGRAM****Table of Contents**

I.	General Monitoring Provisions .....	E-3
II.	Monitoring Locations .....	E-3
III.	Influent Monitoring Requirements .....	E-3
IV.	Effluent Monitoring Requirements .....	E-3
	A. Monitoring Locations BW-001 and BW-002.....	E-3
	B. Monitoring Locations PW-001 and PW-002.....	E-3
	C. Monitoring Locations FP-001, FP-002, WW-001, and WW-002 .....	E-3
	D. Monitoring Locations SC-001 and SC-002 .....	E-3
V.	Whole Effluent Toxicity Testing Requirements.....	E-3
VI.	Land Discharge Monitoring Requirements – Not Applicable .....	E-3
VII.	Reclamation Monitoring Requirements – Not Applicable .....	E-3
VIII.	Receiving Water Monitoring Requirements – Surface Water .....	E-3
	A. Monitoring Location RW-001 .....	E-3
IX.	Other Monitoring Requirements .....	E-3
	A. Floating Drydock Submergence/Emergence Water Discharge, Shipbuilding Ways Flood Water Discharge, and Graving Dock Flood Water Discharge.....	E-3
	B. Floating Drydock Ballast Tank.....	E-3
	C. Floating Boom Cleaning .....	E-3
	D. Storm Water .....	E-3
	E. Spill and Illicit Discharge Log.....	E-3
	F. Chemical Utilization Audit.....	E-3
	G. Waste Hauling Log .....	E-3
	H. Sediment Chemistry Monitoring .....	E-3
X.	Reporting Requirements .....	E-3
	A. General Monitoring and Reporting Requirements .....	E-3
	B. Self Monitoring Reports (SMRs).....	E-3
	C. Discharge Monitoring Reports (DMRs).....	E-3
	D. Other Reports.....	E-3

**List of Tables**

Table E-1.	Monitoring Station Locations .....	E-3
Table E-2.	Fire Protection Intake Monitoring .....	E-3
Table E-3.	Effluent Monitoring for Ballast Water .....	E-3
Table E-4.	Effluent Monitoring for Potable Water Leaks From Hoses .....	E-3
Table E-5.	Effluent Monitoring for Fire Protection Water and Water Weight Bag Effluent.....	E-3
Table E-6.	Effluent Monitoring for Steam Condensate Leaks .....	E-3
Table E-7.	Receiving Water Monitoring Requirements .....	E-3
Table E-8.	Monitoring Requirements for Industrial Storm Water Discharges. ....	E-3
Table E-9.	Station Location General Guidelines. ....	E-3
Table E-10.	Sediment Chemistry Methods and Detection Limits. ....	E-3
Table E-11.	Sediment Sampling Site Coordinates (Lambert/California Coordinates) .....	E-3
Table E-12.	Reference Station Sampling Site Coordinates (Lambert/California Coordinates). ....	E-3

**ADMINISTRATIVE DRAFT**

Table E-13. Monitoring Periods and Reporting Schedule .....	E-3
Table E-14. Reporting Requirements for Special Provisions Progress Reports.....	E-3

ADMINISTRATIVE DRAFT

**ATTACHMENT E – MONITORING AND REPORTING PROGRAM (MRP)**

The Code of Federal Regulations section 122.48 requires that all NPDES permits specify monitoring and reporting requirements. Water Code sections 13267 and 13383 also authorize the Regional Water Quality Control Board (Regional Water Board) to require technical and monitoring reports. This MRP establishes monitoring and reporting requirements, which implement the federal and California regulations.

**I. GENERAL MONITORING PROVISIONS**

- A.** Samples and measurements taken as required herein shall be representative of the volume and nature of the monitored discharge. All samples shall be taken at the monitoring locations specified below and, unless otherwise specified, before the monitoring flow joins or is diluted by any other waste stream, body of water, or substance. Monitoring locations shall not be changed without notification to and the approval of this Regional Water Board.
- B.** Monitoring must be conducted according to USEPA test procedures approved at 40 CFR 136, Guidelines Establishing Test Procedures for the Analysis of Pollutants under the Clean Water Act as amended, unless other test procedures are specified in TENTATIVE ORDER NO. R9-2008-0048 and/or this MRP and/or this Regional Water Board
- C.** A copy of the monitoring and reports signed, and certified as required by Attachment D, Standard Provisions V.B, of TENTATIVE ORDER NO. R9-2008-0048, shall be submitted to the Regional Water Board at the address listed in section X.B.7.c this MRP.
- D.** The Discharger shall retain records of all monitoring information, including all calibration and maintenance records and all original strip chart recordings for continuous monitoring, instrumentation, copies of all reports required by TENTATIVE ORDER NO. R9-2008-0048 and this MRP, and records of all data used to complete the application for TENTATIVE ORDER NO. R9-2008-0048. Records shall be maintained for a minimum of five years from the date of sample, measurement, report, or application. This period may be extended by request of this Regional Water Board or by the USEPA at any time.
- E.** All analyses shall be performed in a laboratory certified to perform such analyses by the California Department of Health Services or by a laboratory approved by the Regional Water Board.
- F.** The Discharger shall report in its cover letter all instances of noncompliance not reported under Attachment D, section V.C of TENTATIVE ORDER NO. R9-2008-0048 at the time monitoring reports are submitted. The reports shall contain the information listed in Attachment D, section IV.B of TENTATIVE ORDER NO. R9-2008-0048.
- G.** All monitoring instruments and devices used by the Discharger to fulfill the prescribed monitoring program shall be properly maintained and calibrated as necessary to ensure

ADMINISTRATIVE DRAFT

their continued accuracy. All flow measurement devices shall be calibrated at least once per year to ensure continued accuracy of the devices.

H. Monitoring results shall be reported at intervals and in a manner specified in TENTATIVE ORDER NO. R9-2008-0048 or in this Monitoring and Reporting Program.

I. This Monitoring and Reporting Program may be modified by this Regional Water Board as appropriate.

## II. MONITORING LOCATIONS

The Discharger shall establish the following monitoring locations to demonstrate compliance with the effluent limitations, discharge specifications, and other requirements in this Order:

**Table E-1. Monitoring Station Locations**

Discharge Location No.	Monitoring Location Name	Monitoring Location Description
INF-001	INF-001	A location where a representative sample of the receiving water entering the Fire Water Protection System intake can be obtained.
BW-001	BW-001	A location where a representative sample of the ballast water can be obtained just prior to, or during the discharge into the Bay by the POSD Drydock.
BW-002	BW-002	A location where a representative sample of the ballast water can be obtained just prior to, or during the discharge into the Bay by the AFDL Drydock.
FP-001	FP-001	A location where a representative sample of the fire protection system from Pier 3 can be obtained: 32° 41' 24" N; 117° 8' 41" W
FP-002	FP-002	A location where a representative sample of the fire protection system from Building 13 can be obtained: 32° 41' 29" N; 117° 8' 39" W
PW-001	PW-001	A location where a representative sample of the potable water leaks from hoses from Pier 1 can be obtained: 32° 41' 38" N; 117° 8' 46" W
PW-002	PW-002	A location where a representative sample of the potable water leaks from hoses from Pier 3 can be obtained: 32° 41' 29" N; 117° 8' 41" W
SC-001	SC-001	A location where a representative sample of the steam condensate leaks from hoses from Pier 1 can be obtained: 32° 41' 38" N; 117° 8' 46" W
SC-002	SC-002	A location where a representative sample of the steam condensate leaks from hoses from Pier 3 can be obtained: 32° 41' 29" N; 117° 8' 41" W
WW-001	WW-001	A location where a representative sample of the water weight bag effluent from Pier 1 can be obtained: 32° 41' 38" N; 117° 8' 46" W
WW-002	WW-002	A location where a representative sample of the water weight bag effluent from Pier 3 can be obtained: 32° 41' 29" N; 117° 8' 41" W
RW-001	RW-001	A location where a representative sample of the receiving water can be obtained, outside the influence of ALL Facility discharges.

## III. INFLUENT MONITORING REQUIREMENTS

A. Monitoring Location INF-001

ADMINISTRATIVE DRAFT

1. The Discharger shall monitoring the intake of San Diego Bay water for use in the fire protection system at Monitoring Location INF-001 as follows:

**Table E-2. Fire Protection Intake Monitoring**

Parameter	Units	Sample Type	Minimum Sampling Frequency	Required Analytical Test Method
pH	standard units	Grab	1/month	1
Copper, Total Recoverable	µg/L	Grab	1/month	1,2
Arsenic, Total Recoverable	µg/L	Grab	1/month	1
Total Suspended Solids	mg/L	Grab	1/year	1
Turbidity	NTU	Grab	1/year	1
Remaining CTR Priority Pollutants	µg/L	Grab	1/year	1

<sup>1</sup> As specified in 40 CFR 126.

<sup>2</sup> Influent and effluent samples shall be analyzed for copper according to method 1638 or 1640. The commonly used methods 6010B (Inorganics by ICP-Atomic Emission Spectroscopy) and 200.7 (Trace Elements-ICP) have been found to give inaccurate copper readings in saline-matrix samples due to interference with the sodium-argon complex, which has a molecular weight similar to copper. Method 1638 (ICP/MS) or 1640 (On-Line Chelation) will eliminate the sodium-argon complex before the sample is tested for copper. No inaccurate readings for other metals in a saline-matrix sample is analyzed by methods 6010B or 200.7 are known.

#### IV. EFFLUENT MONITORING REQUIREMENTS

##### A. Monitoring Locations BW-001 and BW-002

1. The Discharger shall monitor the discharge of ballast water at Monitoring Location Nos. BW-001 and BW-002 as follows:

ADMINISTRATIVE DRAFT

**Table E-3. Effluent Monitoring for Ballast Water**

Parameter	Units	Sample Type	Minimum Sampling Frequency	Required Analytical Test Method and (Minimum Level, units), respectively
Flow	GPD	Grab	1/day	Estimate
pH	standard units	Grab	1/month	1
Temperature	°F	Grab	1/month	1
Arsenic, Total Recoverable	µg/L	Grab	1/quarter	1
Copper, Total Recoverable	µg/L	Grab	1/quarter	1,2
Settleable Solids	ml/L	Grab	1/year	1
Turbidity	NTU	Grab	1/year	1
Total Suspended Solids	mg/L	Grab	1/year	1
Oil and Grease	mg/L	Grab	1/year	1
Total Petroleum Hydrocarbons (TPH)	mg/L	Grab	1/year	1
Polynuclear Aromatic Hydrocarbons (PAH) <sup>3</sup>	µg/L	Grab	1/year	1
Tributyltin (TBT)	µg/L	Grab	1/year	1
Acute Toxicity		Grab	1/year	1
Chronic Toxicity		Grab	1/year	1
Total Residual Chlorine	µg/L	Grab	1/year	1
Remaining CTR Priority Pollutants	µg/L	Grab	1/year	1

ADMINISTRATIVE DRAFT

<sup>1</sup> As specified in 40 CFR 136.<sup>2</sup> Influent and effluent samples shall be analyzed for copper according to method 1638 or 1640. The commonly used methods 6010B (Inorganics by ICP-Atomic Emission Spectroscopy) and 200.7 (Trace Elements-ICP) have been found to give inaccurate copper readings in saline-matrix samples due to interference with the sodium-argon complex, which has a molecular weight similar to copper. Method 1638 (ICP/MS) or 1640 (On-Line Chelation) will eliminate the sodium-argon complex before the sample is tested for copper. No inaccurate readings for other metals in a saline-matrix sample is analyzed by methods 6010B or 200.7 are known.<sup>3</sup> PAHs shall mean the sum of acenaphthylene; anthracene; 1,2-benzanthracene; 3,4-benzofluoranthene; benzo(k)fluoranthene; 1,12-benzoperylene; benzo(a)pyrene; chrysene; dibenzo(a,h)anthracene; fluorene; indeno(1,2,3-cd)pyrene; phenanthrene; and pyrene.**B. Monitoring Locations PW-001 and PW-002**

1. The Discharger shall monitor the discharge of potable water leaks from hoses at Monitoring location Nos. PW-001 and PW-002 as follows:



**Table E-4. Effluent Monitoring for Potable Water Leaks From Hoses**

Parameter	Units	Sample Type	Minimum Sampling Frequency	Required Analytical Test Method and (Minimum Level, units), respectively
Flow	GPD	Grab	1/day	Estimate
pH	standard units	Grab	1/month	1
Temperature	°F	Grab	1/month	1
Settleable Solids	ml/L	Grab	1/year	1
Turbidity	NTU	Grab	1/year	1
Total Suspended Solids	mg/L	Grab	1/year	1
Oil and Grease	mg/L	Grab	1/year	1
Total Petroleum Hydrocarbons (TPH)	mg/L	Grab	1/year	1
Polynuclear Aromatic Hydrocarbons (PAH) <sup>3</sup>	µg/L	Grab	1/year	1
Tributyltin (TBT)	µg/L	Grab	1/year	1
Acute Toxicity		Grab	1/year	1
Chronic Toxicity		Grab	1/year	1
Total Residual Chlorine	µg/L	Grab	1/year	1
Remaining CTR Priority Pollutants	µg/L	Grab	1/year	1

<sup>1</sup> As specified in 40 CFR 136.<sup>2</sup> Influent and effluent samples shall be analyzed for copper according to method 1638 or 1640. The commonly used methods 6010B (Inorganics by ICP-Atomic Emission Spectroscopy) and 200.7 (Trace Elements-ICP) have been found to give inaccurate copper readings in saline-matrix samples due to interference with the sodium-argon complex, which has a molecular weight similar to copper. Method 1638 (ICP/MS) or 1640 (On-Line Chelation) will eliminate the sodium-argon complex before the sample is tested for copper. No inaccurate readings for other metals in a saline-matrix sample is analyzed by methods 6010B or 200.7 are known.<sup>3</sup> PAHs shall mean the sum of acenaphthylene; anthracene; 1,2-benzanthracene; 3,4-benzofluoranthene; benzo(k)fluoranthene; 1,12-benzoperylene; benzo(a)pyrene; chrysene; dibenzo(a,h)anthracene; fluorene; indeno(1,2,3-cd)pyrene; phenanthrene; and pyrene.**C. Monitoring Locations FP-001, FP-002, WW-001, and WW-002**

6. The Discharger shall monitor fire protection test water at Monitoring Location Nos. FP-001 and FP-002, and water weight bag effluent at Monitoring Location Nos. WW-001 and WW-002 as follows:

ADMINISTRATIVE DRAFT

**Table E-5. Effluent Monitoring for Fire Protection Water and Water Weight Bag Effluent**

Parameter	Units	Sample Type	Minimum Sampling Frequency	Required Analytical Test Method and (Minimum Level, units), respectively
Flow	GPD	Grab	1/day	Meter <sup>4</sup>
pH	standard units	Grab	1/month	1
Temperature	°F	Grab	1/month	1
Arsenic, Total Recoverable	µg/L	Grab	1/month	1
Copper, Total Recoverable	µg/L	Grab	1/month	1,2
Settleable Solids	ml/L	Grab	1/year	1
Turbidity	NTU	Grab	1/year	1
Total Suspended Solids	mg/L	Grab	1/year	1
Oil and Grease	mg/L	Grab	1/year	1
Total Petroleum Hydrocarbons (TPH)	mg/L	Grab	1/year	1
Polynuclear Aromatic Hydrocarbons (PAH) <sup>3</sup>	µg/L	Grab	1/year	1
Tributyltin (TBT)	µg/L	Grab	1/year	1
Acute Toxicity		Grab	1/year	1
Chronic Toxicity		Grab	1/year	1
Total Residual Chlorine	µg/L	Grab	1/year	1
Remaining CTR Priority Pollutants	µg/L	Grab	1/year	1

<sup>1</sup> As specified in 40 CFR 136.<sup>2</sup> Influent and effluent samples shall be analyzed for copper according to method 1638 or 1640. The commonly used methods 6010B (Inorganics by ICP-Atomic Emission Spectroscopy) and 200.7 (Trace Elements-ICP) have been found to give inaccurate copper readings in saline-matrix samples due to interference with the sodium-argon complex, which has a molecular weight similar to copper. Method 1638 (ICP/MS) or 1640 (On-Line Chelation) will eliminate the sodium-argon complex before the sample is tested for copper. No inaccurate readings for other metals in a saline-matrix sample is analyzed by methods 6010B or 200.7 are known.<sup>3</sup> PAHs shall mean the sum of acenaphthylene; anthracene; 1,2-benzanthracene; 3,4-benzofluoranthene; benzo(k)fluoranthene; 1,12-benzoperylene; benzo(a)pyrene; chrysene; dibenzo(a,h)anthracene; fluorene; indeno(1,2,3-cd)pyrene; phenanthrene; and pyrene.<sup>4</sup> Effluent flow for water weight bag effluent can be estimated.**D. Monitoring Locations SC-001 and SC-002**

1. The Discharger shall monitor steam condensate leaks from hoses at Monitoring Location Nos. SC-001 and SC-002 as follows:

**Table E-6. Effluent Monitoring for Steam Condensate Leaks**

Parameter	Units	Sample Type	Minimum Sampling Frequency	Required Analytical Test Method and (Minimum Level, units), respectively
Flow	GPD	Grab	1/day	Estimated
pH	standard units	Grab	1/month	1
Temperature	°F	Grab	1/month	1
Copper, Total Recoverable	µg/L	Grab	1/month	1,2
Lead, Total Recoverable	µg/L	Grab	1/month	1
Settleable Solids	ml/L	Grab	1/year	1
Turbidity	NTU	Grab	1/year	1
Total Suspended Solids	mg/L	Grab	1/year	1
Oil & Grease	mg/L	Grab	1/year	1
Total Petroleum Hydrocarbons (TPH)	mg/L	Grab	1/year	1
Polynuclear Aromatic Hydrocarbons (PAH) <sup>3</sup>	µg/L	Grab	1/year	1
Tributyltin (TBT)	µg/L	Grab	1/year	1
Acute Toxicity		Grab	1/year	1
Chronic Toxicity		Grab	1/year	1
Total Residual Chlorine	µg/L	Grab	1/year	1
Remaining CTR Priority Pollutants	µg/L	Grab	1/year	1

ADMINISTRATIVE DRAFT

<sup>1</sup> As specified in 40 CFR 136.

<sup>2</sup> Influent and effluent samples shall be analyzed for copper according to method 1638 or 1640. The commonly used methods 6010B (Inorganics by ICP-Atomic Emission Spectroscopy) and 200.7 (Trace Elements-ICP) have been found to give inaccurate copper readings in saline-matrix samples due to interference with the sodium-argon complex, which has a molecular weight similar to copper. Method 1638 (ICP/MS) or 1640 (On-Line Chelation) will eliminate the sodium-argon complex before the sample is tested for copper. No inaccurate readings for other metals in a saline-matrix sample is analyzed by methods 6010B or 200.7 are known.

<sup>3</sup> PAHs shall mean the sum of acenaphthylene; anthracene; 1,2-benzanthracene; 3,4-benzofluoranthene; benzo(k)fluoranthene; 1,12-benzoperylene; benzo(a)pyrene; chrysene; dibenzo(a,h)anthracene; fluorene; indeno(1,2,3-cd)pyrene; phenanthrene; and pyrene.

## V. WHOLE EFFLUENT TOXICITY TESTING REQUIREMENTS

This section includes detailed whole effluent toxicity (WET) testing requirements, including test species effect, test duration, and test method. The requirement to conduct WET testing at a specific monitoring location must be listed under section IV, Effluent Monitoring Requirements, above. This section must include details on how to conduct acute and chronic toxicity tests and may include the following:

- Acute Toxicity Testing Requirements
- Chronic Toxicity Testing Requirements
- Quality Assurance
- Accelerated Monitoring Requirements
- Steps in the TIE/TRE Process

**VI. LAND DISCHARGE MONITORING REQUIREMENTS – NOT APPLICABLE****VII. RECLAMATION MONITORING REQUIREMENTS – NOT APPLICABLE****VIII. RECEIVING WATER MONITORING REQUIREMENTS – SURFACE WATER****A. Monitoring Location RW-001**

1. The Discharger shall monitor the San Diego Bay at RW-001 as follows:

**Table E-7. Receiving Water Monitoring Requirements**

Parameter	Units	Sample Type	Minimum Sampling Frequency	Required Analytical Test Method
Arsenic, Total Recoverable	µg/L	Grab	1/quarter	1
Copper, Total Recoverable	µg/L	Grab	1/quarter	1,2
Lead, Total Recoverable	µg/L	Grab	1/quarter	1
Remaining CTR Priority Pollutants <sup>2</sup>	µg/L	Grab	1/year	1

<sup>1</sup> As specified in 40 CFR 136.3

<sup>2</sup> Influent and effluent samples shall be analyzed for copper according to method 1638 or 1640. The commonly used methods 6010B (Inorganics by ICP-Atomic Emission Spectroscopy) and 200.7 (Trace Elements-ICP) have been found to give inaccurate copper readings in saline-matrix samples due to interference with the sodium-argon complex, which has a molecular weight similar to copper. Method 1638 (ICP/MS) or 1640 (On-Line Chelation) will eliminate the sodium-argon complex before the sample is tested for copper. No inaccurate readings for other metals in a saline-matrix sample is analyzed by methods 6010B or 200.7 are known.

**IX. OTHER MONITORING REQUIREMENTS****A. Floating Drydock Submergence/Emergence Water Discharge, Shipbuilding Ways Flood Water Discharge, and Graving Dock Flood Water Discharge**

The Discharger shall provide written notification to the Regional Water Board 48 hours prior to flooding of its floating drydock, shipbuilding ways, and graving dock. If a facility has to be flooded on a short notice and the 48 hour notification time can not be met, the Discharger shall notify the Regional Water Board as early as possible and include information on why the notification time could not be met.

The Discharger shall document the condition of its facilities prior to each flooding. The conditions can be documented either by VHS videotape or by digital photographs that show date and time on each picture. VHS tapes or digital photographs shall document conditions at the initial flooding of the facilities. If flooding is to occur at night, VHS tapes or digital photographs shall be taken during daylight hours as close to the flooding event as possible.

ADMINISTRATIVE DRAFT

The Discharger shall submit documentation on the facility conditions quarterly to the Regional Water Board in accordance with Table E-13.

If a floating drydock was not flooded during the quarter, the Discharger shall document in the quarterly effluent monitoring report that no flooding occurred during that period.

### **B. Floating Drydock Ballast Tank**

The Discharger shall submit U.S. Navy and ASTM reports certifying the integrity of the Floating Drydock ballast tank water annually, in accordance with Table E-13.

### **C. Floating Boom Cleaning**

Annually, the Discharger shall submit a log of floating boom cleaning activity including the duration of cleaning activity, the personnel-in-charge of the cleaning, the quantity of the discharge, the date, a summary of any potential impacts to receiving water quality, and a summary regarding the description and location of any boom removed from San Diego Bay to be cleaned because of oil or other pollutants. The annual log shall be submitted with the annual report in accordance with Table E-13.

### **D. Storm Water**

#### **1. Non-Storm Water Discharge Visual Observations**

- a. The Discharger shall visually observe all drainage areas within its facility for the presence of unauthorized non-storm water discharges.
- b. Visual observations shall document the presence of any discoloration, stains, odors, floating materials, etc., as well as the source of any discharge (if known). Records shall be maintained of the visual observation dates, locations observed, observations, and response taken to eliminate unauthorized non-storm water discharges and to reduce or prevent pollutants from contacting non-storm water discharges. The BMP Plan Manual shall be revised, as necessary, and implemented in accordance with Order No. R9-2008-0048.
- c. The visual observations required above shall be conducted as follows:

For High Risk Areas (defined in Attachment A), the Discharger shall conduct monthly visual observations, during daylight scheduled facility operating hours<sup>1</sup>, on days with no discharges of storm water runoff associated with industrial activities.

For all other areas, the Discharger shall conduct quarterly visual observations during daylight scheduled facility operating hours, on days with no discharges of storm water runoff associated with industrial activities. Quarterly visual observations shall be conducted in each of the following periods: January-March, April-June, July-September,

<sup>1</sup> "Scheduled facility operating hours" are the time periods when the facility is staffed to conduct any function related to industrial activity, but excluding time periods where only routine maintenance, emergency response, security, and/or janitorial services are performed.

and October-December. The Discharger shall conduct quarterly visual observations within 6-18 weeks of each other.

## 2. Storm Water Discharge Visual Observations

- a. Visual observations are required of all discharges of storm water associated with industrial activity occurring during daylight hours that are preceded by at least 7 days without a storm water discharge.
- b. Visual observations of storm water runoff associated with industrial activity shall document the presence of any floating and suspended material, oil and grease, discoloration, turbidity, odor, and source of any pollutants. Records shall be maintained of observation dates, locations, observations, and response taken to reduce or prevent pollutants in discharges. The BMP Plan Manual shall be revised, as necessary, and implemented in accordance with Attachment G.
- c. Storm water discharge visual observations shall be conducted as follows:
  - i. For high risk areas, the Discharger shall conduct visual observations of discharges of storm water runoff associated with industrial activity from high risk areas, during each storm event. These visual observations shall occur during the first hour of discharge and at all discharge locations. Visual observations of stored or contained storm water shall occur at the time of release.
  - ii. For all other areas, the Discharger shall conduct visual observations of discharges of storm water runoff associated with industrial activity from all other areas during one storm event per month during the wet season (October 1-May 30). These visual observations shall occur during the first hour of discharge and at all discharge locations. Visual observations of stored or contained storm water shall occur at the time of release.

## 3. Sampling and Analysis

- a. The Discharger shall collect storm water samples during the first hour of discharge from:
  - i. the first storm event of the wet season that produces discharges, and
  - ii. at least one other storm event in the wet season that produces discharges.

All storm water discharge locations shall be sampled. Sampling of stored or contained storm water shall occur at the time the stored or contained storm water is released. If a sample is not collected from the first storm of the wet season that produces discharges, the Discharger is still required to collect samples from two other storms of the wet season that produce discharges. The Discharger shall explain in the Storm Water Annual Report why the first storm that produces discharges was not sampled. If a sample cannot be taken during the first hour of a discharge, the Discharger shall explain why the samples could not be taken

ADMINISTRATIVE DRAFT

during this period of time.

- b. Samples shall be collected from discharges of storm water that are preceded by at least 7 days without storm water discharge.
- c. The samples shall be analyzed according to Table E-8. Monitoring Requirements for Industrial Storm Water Discharge.

**Table E-8. Monitoring Requirements for Industrial Storm Water Discharges**

Parameter	Unit	Sample Type	Minimum Frequency	Required Analytical Test Method
Discharge Volume	gallons	Estimate <sup>1</sup>	2 storms per year	Estimate
Total Petroleum Hydrocarbons (TPH)	mg/L	Grab	2 storms per year	<sup>2</sup>
Total Suspended Solids	mg/L	Grab	2 storms per year	<sup>2</sup>
Settleable Solids	ml/L	Grab	2 storms per year	<sup>2</sup>
pH	pH Units	Grab	2 storms per year	<sup>2</sup>
Arsenic, Total Recoverable	µg/L	Grab	2 storms per year	<sup>2</sup>
Cadmium, Total Recoverable	µg/L	Grab	2 storms per year	<sup>2</sup>
Chromium, Total Recoverable	µg/L	Grab	2 storms per year	<sup>2</sup>
Copper, Total Recoverable	µg/L	Grab	2 storms per year	<sup>2,4</sup>
Lead, Total Recoverable	µg/L	Grab	2 storms per year	<sup>2</sup>
Mercury, Total Recoverable	µg/L	Grab	2 storms per year	<sup>2</sup>
Nickel, Total Recoverable	µg/L	Grab	2 storms per year	<sup>2</sup>
Silver, Total Recoverable	µg/L	Grab	2 storms per year	<sup>2</sup>
Zinc, Total Recoverable	µg/L	Grab	2 storms per year	<sup>2</sup>
Chemical Oxygen Demand (COD)	mg/L	Grab	2 storms per year	<sup>2</sup>
Tributyltin (TBT)	µg/L	Grab	2 storms per year	<sup>2</sup>
Acute Toxicity <sup>2</sup>	% survival	Grab	1 storm per year	<sup>2</sup>
Oil and Grease	mg/L	Grab	2 storms per year	<sup>2</sup>
Total Organic Carbon (TOC)	mg/L	Grab	2 storms per year	<sup>2</sup>
Specific Conductance	µmho/cm	Measurement	2 storms per year	<sup>2</sup>

<sup>1</sup> The volume of storm water discharge can be estimated by multiplying: amount of rainfall in feet × square feet of surface area × impervious factor. There are 7.5 gallons per cubic foot.

<sup>2</sup> As specified in 40 CFR 136.3.

<sup>3</sup> The presence of acute toxicity in the storm water shall be determined as specified in *Methods for Measuring the Acute Toxicity of Effluents to Freshwater and Marine Organisms* (EPA 600/4-90-027F, August 1993 or subsequent editions). Dischargers shall conduct an annual acute toxicity test on a sample of storm water. Dischargers shall conduct a 96-hour static-renewal test with the vertebrate *Menidia beryllina*, or the invertebrate *Mysidopsis bahia*. The acute toxicity testing shall be a 96-hour static renewal test conducted on a sample of 100% storm water and a laboratory control. Use of two laboratory controls, a receiving water

ADMINISTRATIVE DRAFT

control, and a synthetic laboratory seawater control, is highly recommended. The salinity of the sample should be adjusted to the salinity level typical of the receiving water using dry sea salt. The adjusted salinity level shall be reported. The storm water tests shall be conducted with concurrent reference toxicant tests. Both the reference toxicant and the storm water test shall meet all test acceptability criteria as specified in the above named manual. If the test acceptability criteria are not achieved, the Discharger shall re-sample and re-test by the next storm.

4. Influent and effluent samples shall be analyzed for copper according to method 1638 or 1640. The commonly used methods 6010B (Inorganics by ICP-Atomic Emission Spectroscopy) and 200.7 (Trace Elements-ICP) have been found to give inaccurate copper readings in saline-matrix samples due to interference with the sodium-argon complex, which has a molecular weight similar to copper. Method 1638 (ICP/MS) or 1640 (On-Line Chelation) will eliminate the sodium-argon complex before the sample is tested for copper. No inaccurate readings for other metals in a saline-matrix sample is analyzed by methods 6010B or 200.7 are known.

#### 4. Storm Water Discharge Sample Locations

- a. The Discharger shall visually observe and collect samples of storm water discharges from all drainage areas that represent the quality and quantity of the facility's storm water discharges from the storm event. Monitoring stations shall be established at each point of discharge from areas where industrial activities occur or have occurred during the previous year. Monitoring stations shall be positioned at points where the storm water flow has not commingled with any flow of water from a non-industrial area, and where samples representative of the discharge of storm water runoff associated with industrial activity in the drainage area can be obtained.

Monitoring locations shall be identified in the BMP Plan Manual, depicted on a site map, and shall not be changed without notice to and the approval of this Regional Water Board. The installation of automatic or mechanical storm water samplers at the monitoring station is recommended.

- b. With the exception of high risk areas, Dischargers that determine that the industrial activities and BMPs within two or more drainage areas are substantially identical may either: (a) collect samples from a reduced number of substantially identical drainage areas, or (b) collect samples from each substantially identical drainage area and analyze a combined sample from each substantially identical drainage area. The Discharger must document such a determination in the annual report.

#### 5. Visual Observation and Sample Collection Exceptions

The Discharger is required to be prepared to collect samples and conduct visual observations at the beginning of the wet season (October 1) and throughout the wet season until the minimum requirements of sections IX.D.2 and IX.D.3. of this MRP are completed with the following exception:

- a. The Discharger is not required to collect a sample (in accordance with section IX.D.3) and conduct visual observations (in accordance with section IX.D.2) due to dangerous weather conditions, such as flooding, electrical storm, etc. Non-storm water visual observations are only required during daylight scheduled

ADMINISTRATIVE DRAFT



facility operating hours. Storm water visual observation are only required during daylight hours. Dischargers that do not collect the required samples or visual observations during a wet season due to this exception shall include an explanation in the Storm Water Annual Report why the sampling or visual observations could not be conducted.

#### 6. Storm Water Annual Report

The Discharger shall submit a Storm Water Annual Report by September 1 of each year to this Regional Water Board. The report shall include the following:

- a. summary of visual observations and sampling and analysis results;
- b. evaluation of the visual observation and sampling and analysis results;
- c. laboratory reports;
- d. Annual Comprehensive Site Compliance Evaluation Report required by TENTATIVE ORDER NO. R9-2008-0048;
- e. explanation of why the facility did not implement any activities required by TENTATIVE ORDER NO. R9-2008-0048 (if not included in the Evaluation Report); and
- f. records specified in section IX.D of this MRP.

The Discharger shall prepare and submit the Storm Water Annual Report using the annual report forms provided by the State Water Board or Regional Water Board or shall submit their information on a form that contains equivalent information.

#### E. Spill and Illicit Discharge Log

The Discharger shall log and report all spills and illicit discharges within and from NASSCO each month, including spills and illicit discharges from vessels that are in the yard for service. The spill / illicit discharge reports shall identify:

1. the time and date of the spill or illicit discharge;
2. the cause of the spill or illicit discharge;
3. the materials or wastes involved in the spill or illicit discharge,
4. the estimated volume of the spill or illicit discharges;
5. the specific location where the spill or illicit discharge originated;
6. the fate of the spill or illicit discharge (e.g., San Diego Bay, floating drydock, etc.);
7. the physical extent or size of the area(s) affected by the spill;

8. whether the spill or illicit discharge contained pollutants;
9. the public agencies notified;
10. the corrective actions taken; and
11. the means to prevent or minimize future spills or illicit discharges.

The reports shall be submitted quarterly to the Regional Water Board in accordance with Table E-13 of this MRP.

The Discharger shall include in its annual effluent report, a summary of the spills and illicit discharges that occurred in or on its leasehold. The spill/illicit discharge summary report shall indicate the total number of spills and illicit discharges for the year, categorize the spills and illicit discharges, and provide the percentages of each type of spill or illicit discharge in a graphical representation. The summary report shall also indicate the efforts the Discharger used in the year to prevent or minimize spills.

#### **F. Chemical Utilization Audit**

The Discharger shall submit a complete Chemical Utilization Audit form to summarize the use of hazardous materials and wastes generated. The form shall be submitted annually to the Regional Water Board in accordance with Table E-13 of this MRP.

#### **G. Waste Hauling Log**

The Discharger shall submit a log showing the volume, type, disposition, and date of disposal for all wastes originating from the Facility during each month. The log shall be submitted semi-annually to the Regional Water Board in accordance with Table E-13 of this Monitoring and Reporting Program.

#### **H. Sediment Chemistry Monitoring**

1. Sediment monitoring, as specified in this MRP, will not be required until the sediment cleanup at BAE is successfully completed. The sediment cleanup analysis results will be used in lieu of this sediment monitoring. The first set of samples from the BAE sampling stations and reference stations, outlined in this MRP are required to be taken concurrently with the last post cleanup sediment sampling. This will establish a baseline set of data after cleanup that can be used to compare the annual sediment monitoring data submitted thereafter to establish if or how concentrations in the sediment change over time.

2. Sample Collection

- a. The sediment sampling program shall consist entirely of surficial sediment samples, and shall be conducted by the Discharger at the stations within its leasehold, as specified in Table E-11 of this MRP.

b. A minimum of one sample shall be collected and analyzed from each designated station on an annual basis. The samples shall not be discarded after analysis. All samples shall be frozen and retained for a period of not less than 45 days from the date on which the Regional Water Board receives the corresponding analytical results. The Regional Water Board shall notify the Discharger when the samples can be discarded.

c. If more than one sample is collected from a sampling station, each sample shall be analyzed separately and shall not be composited.

d. Samples shall be collected in accordance with the current *Sample Collection Plan* that was submitted and approved under the General Shipyard Permit by the Regional Water Board. This Plan addresses all collection protocol including station positioning method, sampling equipment, containers, preservation, transportation, etc.

Any proposed future changes to the *Sample Collection Plan* shall be submitted to this Regional Water Board for review at least 60 days prior to when the changes are proposed to take effect.

If the Discharger proposes a new Sample Collection Plan, the following items have to be included in the plan:

- i. Narrative Descriptions: A detailed narrative description of each station location, including distances from permanent key landmarks, shall be developed and confirmed in the field.
- ii. Photographs: Each station shall be marked (if feasible) and photographed. A minimum of two photos shall be taken to show the location of each station relative to the key landmarks that will be used to relocate it (e.g., storm drain outlet, corner of dry dock, etc).
- iii. Station Coordinates: The Discharger shall convert the station coordinates from the Lambert coordinate grid system (i.e., Easting and Northing) into Latitude and Longitude coordinates. All station coordinates shall be confirmed in the field and corrected if necessary.
- iv. Facility and Reference Station Maps: Accurate Facility and reference station maps shall be developed and confirmed in the field. All maps shall be drawn to a scale of 1"=50' or 1"=100' overlain on a Latitude/Longitude coordinate grid system. In addition to the monitoring stations, the maps shall show only pertinent details such as structures, storm drains, and work areas. A mylar master is recommended, photocopies may be submitted.

The final Sample Collection Plan shall remain unchanged from station to station and year to year.

e. If over the course of the monitoring program conditions at a particular station are encountered which render collection of grab samples dangerous or impractical, the Discharger may use in its place another of the approved methods/samplers (e.g., Ekman

or diver). If possible, substitutions should be approved in advance by the Regional Water Board.

When substitutions are necessary, the corresponding Discharge Monitoring Reports shall specify the station(s) involved and the substitute method/sampler employed.

### 3. Sampling Stations and Analysis

- a. The guidelines listed in Table E-9 regarding station location/sample collection shall apply, unless otherwise specified in this Monitoring and Reporting Program.

**Table E-9. Station Location General Guidelines**

Stations Adjacent To:	Sample Collection:
Piers, Floats, Docks, Drydocks, and Quay Walls	<p>Samples shall be taken immediately below the edge of a pier float, dock, dry dock, or quay wall and shall be collected by 0.1 m<sup>2</sup> modified van Veen dredge deployed from a boat or the side of the pier float, dock, dry dock, or quay wall.</p> <p>When a float and quay wall or pier are present side-by-side, samples should be taken below the outside (or bay-side) edge of the float (rather than between the float and quay wall or under the float).</p>
Rip Rap	Samples should be collected 5 feet further from shore than where the rip rap first meets the soft bottom sediment. (In some cases, 10 feet may be specified.)
Storm Drains	Storm drain samples of bay sediment should be collected at a point approximately 10 feet from the mouth of the drain and in line with the centerline of the drain unless otherwise specified in this Monitoring and Reporting Program.
Beach	The narrative descriptions will indicate the distance that a station is located relative to a stationary landmark, such as a pier or other nearby structure.
Dock/Rip Rap Intersection	Follow guidelines for rip rap station.
Dock/Beach Intersection	Follow guidelines for beach station.

- b. The three remote reference stations identified in Table E-12 of this Monitoring and Reporting Program are common to reference stations for other shipyards discharging to San Diego Bay. The Discharger may fulfill its sampling requirements for the remote reference stations by submitting results from samples collected at these stations by other entities during the sampling/reporting period. Reference station locations are specified in Sediment Monitoring Station Locations section of this MRP.

It is the Discharger's responsibility to request and obtain permission from the appropriate party or parties prior to sample collection at each of the three reference stations.

## 4. Analysis Parameters and Detection Limits

Sample analyses shall be conducted using approved laboratory methods capable of meeting the detection limits shown in Table E-10. Sediment Chemistry Methods and Detection Limits. Surficial sediment samples shall be analyzed for the parameters and to the detection limits indicated in Table E-10.

**Table E-10. Sediment Chemistry Methods and Detection Limits**

Parameter	Method Number	Detection Limit (dry weight)
Grain size	--	NA
Cadmium, Chromium, Copper, Nickel, Silver <sup>1</sup>	6010	0.5 mg/kg
Mercury <sup>1</sup>	7471	0.1 mg/kg
Arsenic <sup>1</sup>	7060 or 7061	0.5 mg/kg
Lead <sup>1</sup>	7421	0.5 mg/kg
Zinc <sup>1</sup>	6010	2.0 mg/kg
Tributyltin (TBT) <sup>2</sup>	See Footnote 2	1.0 µg/kg
Total Petroleum Hydrocarbons (TPH) <sup>3</sup>	Modified 8015 or DHS	500. µg/kg
Polychlorinated biphenyls/ Polychlorinated terphenyls (PCBs/PCTs) <sup>4</sup>	8080	20.0 µg/kg
PAH <sup>5</sup>	8270	100. µg/kg

<sup>1</sup> Trace metal analysis shall include the individual concentrations of arsenic, cadmium, chromium, copper, lead, mercury, nickel, silver, and zinc. Method 3050 shall be used in preparation for all metal analyses except mercury. Preparation procedures for mercury are included in method 7471.

<sup>2</sup> Concentrations of tributyltin shall be analyzed using protocol approved by the Regional Water Board or as described in:

Stephenson, M.D., and D.R. Smith. 1988. Determination of Tributyltin in Tissues and Sediments by Graphite Furnace Atomic Absorption Spectrometry. Analytical Chemistry, Vol. 60, No. 7. pp 696-698; or

Stallard M.O., and S.Y. Cola. 1989. Optimization of Butyltin Measurements for Seawater, Tissue, and Marine Sediment Samples. Applied Organometallic Chemistry 3:105-114; or

Unger, M.A. et al. 1986. GC Determination of Butyltin in Natural Waters by Flame Photometric Detection of Hexyl Derivatives with Mass Spectrometric Confirmation. Chemosphere, Volume 15, Number 4. p 461.

<sup>3</sup> Using gas chromatography, analyze for the medium molecular weight hydrocarbons, boiling point range nC<sub>12</sub> - nC<sub>32</sub>. Separate the two resulting fractions, specifying the concentrations of (1) saturated aliphatic hydrocarbons; (2) unsaturated aromatic hydrocarbons; and (3) their sum, the total petroleum hydrocarbons. The concentrations of the remaining monitored contaminants, PCBs, PCTs, and PAHs, can be determined by further analysis of these two fractions.

**TOTAL PETROLEUM HYDROCARBONS**

Aliphatic	Aromatic
PCBs/PCTs	PAHs

ADMINISTRATIVE DRAFT

- <sup>4</sup> Analyze the saturated aliphatic fraction for PCBs and PCTs, both of which can be measured in a single procedure. Run the PCB analysis as usual but include one additional standard for Aroclor 5460. At approximately 40 minutes, increase the temperature to 285 degrees celsius. PCTs elute later than PCBs and the entire procedure will take approximately 90 minutes.

Report the concentration of total PCBs, indicating the name and degradation status of the predominant aroclor (e.g., Aroclor 1260, undegraded). The name and status of a secondary PCB aroclor shall also be reported, if present. Similarly, specify the concentration of total PCTs assumed to be Aroclor 5460. Report the presence of any unidentified mixture of chlorinated hydrocarbons detected by electron capture gas chromatography. Additional PCB/PCT information, such as the concentrations of individual congeners, should also be provided if available without additional analytical costs.

- <sup>5</sup> The concentrations of the individual PAHs can be determined by further analysis of the unsaturated aromatic fraction. The concentrations of the following eight PAHs shall be reported: phenanthrene, 1-methyl phenanthrene, 2-methyl phenanthrene, benzo(a)pyrene, chrysene, fluoranthene, pyrene, and anthracene.

Additional information, such as the concentration of other PAHs, should also be provided if available without additional analytical costs.

- <sup>6</sup> Although not initially required, composited sediment from each sample shall be retained for possible future total organic carbon (TOC) analysis. All samples shall be frozen and retained for a period of no less than 45 days from the date on which Regional Water Board staff received the corresponding analytical results. At that time, the Regional Water Board shall be notified and approval to discard the samples shall be obtained, before the samples are discarded.

## 5. Sediment Monitoring Results and Reports

### a. Discharge Monitoring Reports

The sediment monitoring results shall be submitted to the Regional Water Board in hard copy form and on a compact disc in Microsoft Word 2000 or older format.

The sediment monitoring results shall contain all required sampling results in the following three forms:

#### i. Tables:

Current, as well as historical, monitoring data shall be provided in tabular form. Historical monitoring data is defined as sample results from all previous reporting periods collected as a part of this MRP. All concentrations shall be reported in both dry and wet weights. Tabular data shall be submitted in hard copy and on a compact disk in IBM Microsoft Excel 2000 or older format.

#### ii. Graphs:

The specific type of graph(s) to be generated (e.g., histogram) is not specified, but left to the discretion of the Discharger's consultant who should determine the most effective way of presenting the data. Graphical data shall be submitted in hard copy and on a compact disk in Microsoft Excel 2000 or older format.

#### iii. Facility and Reference Station Maps:

The facility and reference station maps developed for the final Sample Collection Plan and confirmed during the "pre-sampling field effort" shall be used to present the monitoring data. A separate Facility and reference station map shall be developed for each monitored contaminant or contaminant group indicating the measured concentrations at each station (rather than concentration contours).

iv. Paint Chip Analysis:

In addition to tables, graphs, and maps, shipyard Discharge Monitoring Reports must also include the results of the annual paint chip analyses required in Tables E-11 and E-12 of this MRP.

b. Trend Curves and Statistical Analysis

The Discharger shall submit annual "trend curves" for each monitored constituent, in which concentrations are plotted as a function of time. The Discharger shall also determine if a statistically significant change (increase or decrease) in sediment concentrations has occurred over time for each contaminant, relative to reference concentrations.

In making this determination, the Discharger shall employ a statistical method that is best suited for the data available (parametric vs. non-parametric test).

In all cases, the Discharger shall report as soon as possible the cause(s) or suspected cause(s) of any increase in contaminant concentrations, if they are known.

Monitoring results shall be compared against the following three sets of reference data:

- i. The Discharger's own historical baseline data (historical data is defined as sample results from all previous sampling/reporting periods collected as a part of the Sediment Monitoring and Reporting Program);
- ii. Concentrations measured at the three remote reference sites; and
- iii. Concentrations measured at nearby city storm drain(s), if present.

6. Sediment Monitoring Station Locations

- a. The Discharger shall collect surficial sediment samples in accordance with Table E-11. BAE Facilities Sampling Site Coordinates.

**Table E-11. Sediment Sampling Site Coordinates (Lambert/California Coordinates)**

Station Number	Easting	Northing	Indicators Only <sup>1</sup>	Full Analysis <sup>2</sup>	Paint Chips
SWM-001	1724820	172460	X		

Station Number	Easting	Northing	Indicators Only <sup>1</sup>	Full Analysis <sup>2</sup>	Paint Chips
SWM-002	1724750	192320		X	X
SWM-003	1724720	192220	X		
SWM-004	1724915	197400		X	X
SWM-005	1724975	192400	X		
SWM-006	1724960	192290		X	X
SWM-007	1725000	192240	X		
SWM-008	1725060	192210	X		
SWM-009	1724925	191975	X		
SWM-010	1725100	192020	X		
SWM-011	1725160	191820	X		
SWM-012	1725460	192115	X		
SWM-013	1725475	192000	X		
SWM-014	1725380	191760	X		
SWM-015	1725385	191680	X		
STD-SWM-01	1725400	192150		X	X

<sup>1</sup> Indicators Only Analysis

Grain Size  
Trace Metals  
Tributyltin (TBT)

<sup>2</sup> Full Analysis

Grain Size  
Trace Metals  
Tributyltin (TBT)  
Total Petroleum Hydrocarbons (TPH)  
Polychlorinated Biphenyls/Terphenyls (PCBs/PCTs)  
Polynuclear Aromatic Hydrocarbons (PAHs)

<sup>3</sup> Paint Chip Analysis

For each analysis, paint chips shall be extracted from a total of approximately 9 liters of sediment; 3 liters from each of the three sampling sites.

In the laboratory, the sediment shall be sieved using a screen size just large enough to allow the sediment to pass but not the paint chips. Do not exceed a maximum screen size of 16 openings per inch (openings are approximately 1/16th of an inch). The remaining debris shall then be sorted by hand to remove paint chips. After removal, the paint chips shall be photographed, quantified, and analyzed for metals and TBT.

If paint chips are present, three separate analyses shall be conducted annually. Each analysis will be conducted on paint chips extracted from three stations or replicates; the first analysis will use paint chips extracted from stations SWM-02, SWM-04, and SWM-06. The second analysis shall use paint chips from the three reference stations listed in *Table E-12* of this MRP. The third analysis shall be conducted on three replicates taken from storm drain station STD-SWM-01.

ADMINISTRATIVE DRAFT



- b. The Discharger shall collect surficial samples from the three reference stations in accordance with Table E-12. Reference Station Sampling Site Coordinates.

**Table E-12. Reference Station Sampling Site Coordinates (Lambert/California Coordinates).**

Station Number	Easting	Northing	Indicators Only <sup>1</sup>	Full Analysis <sup>2</sup>	Paint Chips <sup>3</sup>
REF-01	1697300	196600		X	X
REF-02	1706085	204810		X	X
REF-03	1715225	201110		X	X

<sup>1</sup>. Indicators Only Analysis (see Table E-11 above)

<sup>2</sup>. Full Analysis (see Table E-11 above)

<sup>3</sup>. Paint Chip Analysis (see Table E-11 above)

## X. REPORTING REQUIREMENTS

### A. General Monitoring and Reporting Requirements

1. The Discharger shall comply with all Standard Provisions (Attachment D) related to monitoring, reporting, and recordkeeping.

### B. Self Monitoring Reports (SMRs)

1. At any time during the term of this permit, the State or Regional Water Board may notify the Discharger to electronically submit Self-Monitoring Reports (SMRs) using the State Water Board's California Integrated Water Quality System (CIWQS) Program Web site (<http://www.waterboards.ca.gov/ciwqs/index.html>). Until such notification is given, the Discharger shall submit hard copy SMRs. The CIWQS Web site will provide additional directions for SMR submittal in the event there will be service interruption for electronic submittal.
2. The Discharger shall report in the SMR the results for all monitoring specified in this MRP under sections III through IX. The Discharger shall submit monthly SMRs including the results of all required monitoring using USEPA-approved test methods or other test methods specified in this Order. If the Discharger monitors any pollutant more frequently than required by this Order, the results of this monitoring shall be included in the calculations and reporting of the data submitted in the SMR.
3. Monitoring periods and reporting for all required monitoring shall be completed according to the following schedule:

**Table E-13. Monitoring Periods and Reporting Schedule**

Sampling Frequency	Monitoring Period Begins On...	Monitoring Period	SMR Due Date
Continuous	Permit Effective Date	All	Submit with monthly SMR

Daily	Permit Effective Date	(Midnight through 11:59 PM) or any 24-hour period that reasonably represents a calendar day for purposes of sampling.	Submit with monthly SMR
Weekly	Sunday following permit effective date or on permit effective date if on a Sunday	Sunday through Saturday	Submit with monthly SMR
Monthly	First day of calendar month following permit effective date or on permit effective date if that date is first day of the month	1 <sup>st</sup> day of calendar month through last day of calendar month	30 days following the end of the monitoring period
Quarterly	Closest of January 1, April 1, July 1, or October 1 following (or on) permit effective date	January 1 through March 31 April 1 through June 30 July 1 through September 30 October 1 through December 31	30 days following the end of the monitoring period
Semiannually	Closest of January 1 or July 1 following (or on) permit effective date	January 1 through June 30 July 1 through December 31	30 days following the end of the monitoring period
Annually	January 1 following permit effective date	January 1 through December 31	60 days following the end of the monitoring period
Annual Storm Water Report (IX.D.6 of this MRP)	First day of calendar month following permit effective date or on permit effective date if that date is first day of the month	July 1 through June 30	September 1

- 4. Reporting Protocols.** The Discharger shall report with each sample result the applicable reported Minimum Level (ML) and the current Method Detection Limit (MDL), as determined by the procedure in Part 136.

The Discharger shall report the results of analytical determinations for the presence of chemical constituents in a sample using the following reporting protocols:

- Sample results greater than or equal to the reported ML shall be reported as measured by the laboratory (i.e., the measured chemical concentration in the sample).
- Sample results less than the RL, but greater than or equal to the laboratory's MDL, shall be reported as "Detected, but Not Quantified," or DNQ. The estimated chemical concentration of the sample shall also be reported.

For the purposes of data collection, the laboratory shall write the estimated chemical concentration next to DNQ as well as the words "Estimated Concentration" (may be shortened to "Est. Conc."). The laboratory may, if such information is available, include numerical estimates of the data quality for the reported result. Numerical estimates of data quality may be percent accuracy (+

a percentage of the reported value), numerical ranges (low to high), or any other means considered appropriate by the laboratory.

- c. Sample results less than the laboratory's MDL shall be reported as "Not Detected," or ND.
  - d. Dischargers are to instruct laboratories to establish calibration standards so that the ML value (or its equivalent if there is differential treatment of samples relative to calibration standards) is the lowest calibration standard. At no time is the Discharger to use analytical data derived from extrapolation beyond the lowest point of the calibration curve.
5. Compliance Determination. Compliance with effluent limitations for priority pollutants shall be determined using sample reporting protocols defined above and Attachment A of this Order. For purposes of reporting and administrative enforcement by the Regional and State Water Boards, the Discharger shall be deemed out of compliance with effluent limitations if the concentration of the priority pollutant in the monitoring sample is greater than the effluent limitation and greater than or equal to the reporting level (RL).
  6. Multiple Sample Data. When determining compliance with an AMEL or MDEL for priority pollutants and more than one sample result is available, the Discharger shall compute the arithmetic mean unless the data set contains one or more reported determinations of "Detected, but Not Quantified" (DNQ) or "Not Detected" (ND). In those cases, the Discharger shall compute the median in place of the arithmetic mean in accordance with the following procedure:
    - a. The data set shall be ranked from low to high, ranking the reported ND determinations lowest, DNQ determinations next, followed by quantified values (if any). The order of the individual ND or DNQ determinations is unimportant.
    - b. The median value of the data set shall be determined. If the data set has an odd number of data points, then the median is the middle value. If the data set has an even number of data points, then the median is the average of the two values around the middle unless one or both of the points are ND or DNQ, in which case the median value shall be the lower of the two data points where DNQ is lower than a value and ND is lower than DNQ.
  7. The Discharger shall submit SMRs in accordance with the following requirements:
    - a. The Discharger shall arrange all reported data in a tabular format. The data shall be summarized to clearly illustrate whether the facility is operating in compliance with interim and/or final effluent limitations. The Discharger is not required to duplicate the submittal of data that is entered in a tabular format within CIWQS. When electronic submittal of data is required and CIWQS does not provide for entry into a tabular format within the system, the Discharger shall electronically submit the data in a tabular format as an attachment.

- b. The Discharger shall attach a cover letter to the SMR. The information contained in the cover letter shall clearly identify violations of the WDRs; discuss corrective actions taken or planned; and the proposed time schedule for corrective actions. Identified violations must include a description of the requirement that was violated and a description of the violation.
- c. SMRs must be submitted to the Regional Water Board, signed and certified as required by the Standard Provisions (Attachment D), to the address listed below:

**Regional Water Quality Control Board, San Diego Region**  
**9174 Sky Park Court, Suite 100**  
**San Diego, CA 92123**

### **C. Discharge Monitoring Reports (DMRs)**

1. As described in section X.B.1 above, at any time during the term of this permit, the State or Regional Water Board may notify the Discharger to electronically submit SMRs that will satisfy federal requirements for submittal of Discharge Monitoring Reports (DMRs). Until such notification is given, the Discharger shall submit DMRs in accordance with the requirements described below.
2. DMRs must be signed and certified as required by the standard provisions (Attachment D). The Discharger shall submit the original DMR and one copy of the DMR to the address listed below:

<b>STANDARD MAIL</b>	<b>FEDEX/UPS/ OTHER PRIVATE CARRIERS</b>
State Water Resources Control Board Division of Water Quality c/o DMR Processing Center PO Box 100 Sacramento, CA 95812-1000	State Water Resources Control Board Division of Water Quality c/o DMR Processing Center 1001 I Street, 15 <sup>th</sup> Floor Sacramento, CA 95814

All discharge monitoring results must be reported on the official USEPA pre-printed DMR forms (EPA Form 3320-1). Forms that are self-generated will not be accepted unless they follow the exact same format of USEPA Form 3320-1.

### **D. Other Reports**

1. **Progress Reports.** As specified in the compliance time schedules required in Special Provisions VI, progress reports shall be submitted in accordance with the following reporting requirements. At minimum, the progress reports shall include a discussion of the status of final compliance, whether the Discharger is on schedule to meet the final compliance date, and the remaining tasks to meet the final compliance date.

**Table E-14. Reporting Requirements for Special Provisions Progress Reports**

**ADMINISTRATIVE DRAFT**

Special Provision	Reporting Requirements
Order, Provision VI.C.7.a.i – Semi-annual progress reports for meeting the final effluent limitations for arsenic, copper, and lead, as specified in section IV of the Order.	January 30 <sup>th</sup> and July 30 <sup>th</sup> , until May 18, 2010
Order, Provision VI.C.7.a.ii – Work plan and time schedule for preparation of the pollution prevention plan for arsenic, copper, and lead.	Within 3 months after the adoption of this Order.
Order, Provision VI.C.7.a.ii – Final pollution prevention plan for arsenic, copper, and lead	Within 9 months after the adoption of this Order
Attachment G, Provision IX – Annual BMP Site Evaluation	February 28

2. Toxicity - The Discharger shall report the results of any <special studies, acute and chronic toxicity testing, TRE/TIE, PMP, and Pollution Prevention Plan> required by Special Provisions – VI.C.<list> of this Order. The Discharger shall report the progress in satisfaction of compliance schedule dates specified in Special Provisions – VI.C.7 of this Order. The Discharger shall submit reports <with the first monthly SMR scheduled to be submitted on or immediately following the report due date> <in compliance with SMR reporting requirements described in subsection X.B.5 above>. – wait till we get toxicity requirements.

ADMINISTRATIVE DRAFT

**ATTACHMENT F – FACT SHEET****Table of Contents**

I.	Permit Information.....	F-3
II.	Facility Description.....	F-3
	A. Description of Wastewater.....	F-3
	B. Discharge Points and Receiving Waters .....	F-3
	C. Summary of Existing Requirements and Self-Monitoring Report (SMR) Data .....	F-3
	D. Compliance Summary .....	F-3
	E. Planned Changes – Not Applicable.....	F-3
III.	Applicable Plans, Policies, and Regulations .....	F-3
	A. Legal Authorities.....	F-3
	B. California Environmental Quality Act (CEQA).....	F-3
	C. State and Federal Regulations, Policies, and Plans.....	F-3
	D. Impaired Water Bodies on CWA 303(d) List.....	F-3
	E. Other Plans, Policies and Regulations .....	F-3
IV.	Rationale For Effluent Limitations and Discharge Specifications .....	F-3
	A. Discharge Prohibitions.....	F-3
	B. Technology-Based Effluent Limitations .....	F-3
	1. Scope and Authority .....	F-3
	2. Applicable Technology-Based Effluent Limitations.....	F-3
	C. Water Quality-Based Effluent Limitations (WQBELs).....	F-3
	1. Scope and Authority .....	F-3
	2. Applicable Beneficial Uses and Water Quality Criteria and Objectives .....	F-3
	3. Determining the Need for WQBELs.....	F-3
	4. WQBEL Calculations.....	F-3
	5. Whole Effluent Toxicity (WET).....	F-3
	D. Final Effluent Limitations .....	F-3
	4. Satisfaction of Anti-Backsliding Requirements .....	F-3
	5. Satisfaction of Antidegradation Policy .....	F-3
	6. Stringency of Requirements for Individual Pollutants .....	F-3
	E. Interim Effluent Limitations .....	F-3
	F. Land Discharge Specifications – Not Applicable .....	F-3
	G. Reclamation Specifications – Not Applicable .....	F-3
V.	Rationale for Receiving Water Limitations .....	F-3
	A. Surface Water .....	F-3
	B. Groundwater – Not Applicable.....	F-3
VI.	Rationale for Monitoring and Reporting Requirements .....	F-3
	A. Influent Monitoring.....	F-3
	B. Effluent Monitoring .....	F-3
	C. Whole Effluent Toxicity Testing Requirements.....	F-3
	D. Receiving Water Monitoring .....	F-3
	1. Surface Water .....	F-3
	2. Groundwater – Not Applicable.....	F-3
	E. Other Monitoring Requirements .....	F-3
VII.	Rationale for Provisions .....	F-3

ADMINISTRATIVE DRAFT

A. Standard Provisions .....	F-3
B. Special Provisions .....	F-3
1. Reopener Provisions .....	F-3
2. Special Studies and Additional Monitoring Requirements .....	F-3
3. Best Management Practices and Pollution Prevention .....	F-3
4. Construction, Operation, and Maintenance Specifications – Not Applicable .....	F-3
5. Special Provisions for Municipal Facilities (POTWs Only) – Not Applicable .....	F-3
6. Other Special Provisions – Not Applicable .....	F-3
7. Compliance Schedules .....	F-3
VIII. Public Participation .....	F-3
A. Notification of Interested Parties .....	F-3
B. Written Comments .....	F-3
C. Public Hearing .....	F-3
D. Waste Discharge Requirements Petitions .....	F-3
E. Information and Copying .....	F-3
F. Register of Interested Persons .....	F-3
G. Additional Information .....	F-3

### List of Tables

Table F-1. Facility Information .....	F-3
Table F-2. Discharge Locations .....	F-3
Table F-3. Numeric Effluent Limitations .....	F-3
Table F-4. Discharge Data Summary .....	F-3
Table F-5. Basin Plan Beneficial Uses .....	F-3
Table F-6. Ocean Plan Table A Effluent Limitations .....	F-3
Table F-7. Numeric Technology-based Effluent Limitations .....	F-3
Table F-8. Applicable Water Quality Criteria .....	F-3
Table F-9. Summary of RPA Results .....	F-3
Table F-10. WQBEL Calculations for Arsenic .....	F-3
Table F-11. WQBEL Calculations for Copper .....	F-3
Table F-12. WQBEL Calculations for Lead .....	F-3
Table F-13. Summary of CTR Water Quality-based Effluent Limitations .....	F-3
Table F-14. Effluent Limitations For All Discharges .....	F-3
Table F-15. Summary of Final Effluent Limitations By Discharge Location .....	F-3
Table F-16. Interim Effluent Limitations .....	F-3

ADMINISTRATIVE DRAFT

**ATTACHMENT F – FACT SHEET**

As described in section II of this Order, this Fact Sheet includes the legal requirements and technical rationale that serve as the basis for the requirements of this Order.

This Order has been prepared under a standardized format to accommodate a broad range of discharge requirements for Dischargers in California. Only those sections or subsections of this Order that are specifically identified as “not applicable” have been determined not to apply to this Discharger. Sections or subsections of this Order not specifically identified as “not applicable” are fully applicable to this Discharger.

**I. PERMIT INFORMATION**

The following table summarizes administrative information related to the facility.

**Table F-1. Facility Information**

WDID	
Discharger	BAE Systems San Diego Ship Repair Inc.
Name of Facility	BAE Systems San Diego Ship Repair Inc.
Facility Address	2205 East Belt Street
	San Diego CA 92113
	San Diego County
Facility Contact, Title and Phone	Sandor Halvax, Environmental Engineering, (619) 238-1000 ext. 1060
Authorized Person to Sign and Submit Reports	Sandor Halvax, Environmental Engineering, (619) 238-1000 ext. 1060
Mailing Address	PO BOX 13308, San Diego CA 92170
Billing Address	PO BOX 13308, San Diego CA 92170
Type of Facility	Shipbuilding and Repair (SIC Code # 3731)
Major or Minor Facility	Major
Threat to Water Quality	
Complexity	
Pretreatment Program	NA
Reclamation Requirements	NA
Facility Permitted Flow	NA
Facility Design Flow	NA
Watershed	San Diego Bay
Receiving Water	San Diego Bay
Receiving Water Type	Enclosed Bay

- A. BAE Systems San Diego Ship Repair Inc. (BAE) (hereinafter Discharger) is the owner and operator of BAE Systems San Diego Ship Repair Inc. (hereinafter Facility), a shipyard for the construction, conversion, and repair of U.S. Navy and commercial customers.

ADMINISTRATIVE DRAFT



For the purposes of this Order, references to the “discharger” or “permittee” in applicable federal and state laws, regulations, plans, or policy are held to be equivalent to references to the Discharger herein.

- B. The Facility discharges wastewater to the San Diego Bay, a water of the United States, and is currently regulated by Order No. R9-2002-0161, which was adopted on November 13, 2002 and expired on November 13, 2007. The terms and conditions of the current Order have been automatically continued and remain in effect until new Waste Discharge Requirements (WDRs) and National Pollutant Discharge ~~Elimination~~Elimination System (NPDES) permit are adopted pursuant to this Order.

In addition, the Regional Water Quality Control Board (hereinafter Regional Water Board) is currently undergoing proceedings for the issuance of a Cleanup and Abatement Order for discharges of metals and other pollutant wastes to San Diego Bay marine sediment and waters located within and adjacent to BAE Systems San Diego Ship Repair (formerly called Southwest Marine Inc.) and National Steel and Shipbuilding Company (NASSCO) leaseholds. The Discharger (along with NASSCO; Continental Maritime; City of San Diego; Marine Construction and Design Company and Campbell Industries, Inc.; Chevron; BP Atlantic Richfield Company; San Diego Gas and Electric; and the U.S. Navy) is currently being considered for coverage under the tentative Cleanup and Abatement Order No. R9-2005-0126 to address elevated levels of metals and organics in the sediment.

- C. The Discharger filed a report of waste discharge and submitted an application for renewal of its WDRs and NPDES permit on May 11, 2007. A site visit was conducted on December 6, 2007 to observe operations and collect additional data to develop permit limitations and conditions.

## II. FACILITY DESCRIPTION

The Facility is a full service ship repair facility and occupies approximately 10.39 acres of land and 16.64 acres of water on the eastern waterfront of central San Diego Bay. The San Diego Unified Port District is the lessor to BAE. The Facility consists of five piers ranging in length from 257 feet to 700 feet and two floating dry docks. The auxiliary floating dry dock (AFDL) has a lifting capacity of 4,000 tons and is located on the south side of pier 4. The Pride of San Diego (POSD) dry dock has a lifting capacity of 22,000 tons and is located south of pier 2.

The piers and wharves moor and support berthed vessels that are undergoing repair operations, as well as berthing barges used to house vessel crews while ship repairs are being conducted. A concrete wharf is utilized to access the POSD dry dock. Wastes staged and transported across piers may include spent abrasives, paint, petroleum products, sanitary waste, and general refuse and debris.

The dry docks are used to conduct repair and maintenance activity which cannot normally be conducted while the vessel is waterborne. These activities generally include exterior: hull repair; abrasive blasting; hydroblasting; painting; the repair or replacement of shafts, propellers, and rudders; and the repair or replacement of valves and fittings below the

ADMINISTRATIVE DRAFT

waterline. Ship launching and recovery is accomplished by means of integral ballast tanks, which take in and discharge seawater used to raise and lower the dry docks. Wastes generated during ship repair include spent abrasives, paint, rust, petroleum products, marine growth and general refuse and debris. Both dry docks are contained to prevent storm water and wash water from entering the receiving water.

On-shore facilities include a painting and abrasive blasting area located at the foot of pier number 3, and a paint booth located on the southeast section of the facility. On the north end of the facility is an area used for steam cleaning/pressure washing of vehicles and equipment, which includes a sump where effluents are collected and drained to a three-stage clarifier and discharged to the POTW. Manufacturing, storage areas, and material staging areas are also located on-site to support ship repair operations.

The perimeter of the Facility, including piers and dry docks is bermed to prevent the discharge of contact storm water. Storm water is collected via three storm water diversion systems, which includes 31 catch basins/drains, associated piping, 20 holding tanks, and three treatment systems.

#### **A. Description of Wastewater**

Discharges from the Facility to the San Diego Bay include fire protection water, dry dock ballast tank water, drips of potable water and steam condensate from hoses supplying these services to ships, and effluent from weight test bags. The supply water for the fire protection water, cooling water, dry dock ballast water, and weight test bags is pumped from the San Diego Bay. In the NPDES report of waste discharge (ROWD) submitted to the Regional Water Board, dated May 11, 2007, the Discharger states that the non-contact cooling water discharges from building 13 (for the compressor air system) have been eliminated.

Contact storm water is generally not discharged to the San Diego Bay, but is treated on-site and then discharged to a municipal treatment plant for disposal. However, discharges of storm water may occur to the San Diego Bay when the holding capacity is exceeded or the storm water collection and treatment system is not operating properly.

Descriptions of the current discharge types from the Facility are provided in the subsections below.

- 1. Floating Drydock Ballast Water.** Sinking and floating of POSD and AFDL is accomplished by flooding or ballasting the ballast tanks of the floating drydocks. Ballast water from the POSD and AFDL is discharged through DD-001 and DD-002, respectively. The estimated discharge of ballast water is up to 9 million gallons and 4.488 million gallons per lift for the POSD and the AFDL, respectively.
- 2. Fire Protection Water.** Fire protection water is discharged at Pier 3 and Building 13 at approximately 50 gallons per minute (gpm), seven days a week, 6 months a year, for each location (0.072 mgd for 6 months a year per location). Bay water is collected through a series of pumps to pressurize the fire protection system, and the over pressure from the system is discharged to San Diego Bay. The discharge of fire protection water from Pier 1 has been eliminated since the adoption of Order No. R9-2002-0161.

3. **Potable Water Leaks and Steam Condensate Leaks.** Potable water and steam are pumped through hoses to the ships for domestic use (cooking, cleaning, sanitary) and heating. Potable water leaks and steam condensate leaks occur from the hoses supplying the fresh water and steam to ships at Piers 1 and 3 for on-ship use. The discharge of potable water leaks and steam condensate is estimated to occur at less than 1 gpd for each discharge of potable water leaks and steam condensate, and consists of drips from the hoses and piping from the pier to the ship.
4. **Water Weight Test Bags.** Effluent is periodically discharged from water bags used for load test weights for vessels at Piers 1 and 3. Source water for the water weight test bags is directly from the San Diego Bay. Discharge events occur approximately 4 days a year, at approximately 40,000 gpd.
5. **Storm Water.** The perimeter of the Facility, including piers and dry docks is bermed to prevent surface runoff of contact storm water. Storm water is collected via three storm water diversion systems which consists of 31 catch basins/drains and associated piping, holding tanks, and three separate treatment systems. The storm water is pumped from the collection systems to above ground storm water holding tanks. The total on-site holding capacity is approximately 500,000 gallons and consists of approximately 20 holding tanks. The commingled storm water and industrial wastewater from the above ground holding tanks is processed through one of three treatment systems which each consist of a micron filter, and two granular activated carbon chambers arranged in series. Process flow is approximately 100 to 120 gallons per minute (gpm) for each system. Effluent from the on-site treatment systems is directed to a municipal wastewater treatment plant for final disposal. Storm water discharges may occur at the Facility through six discharge locations if the storm water holding capacity is exceeded or there if the storm water diversion system is not operating correctly.
  - a. Discharge Point No. SW-001. Industrial activity associated with this discharge location is limited to material storage and handling.
  - b. Discharge Point No. SW-002. Storm water discharges from this discharge location are exclusively roof runoff from buildings 5, 6, 7, and 75.
  - c. Discharge Point No. SW-003. Industrial activity associated with this discharge location is limited to material storage and handling for POSD drydock activities.
  - d. Discharge Point No. SW-004. Industrial activity associated with this discharge location includes material storage and handling and structural fabrication (i.e., welding, grinding, and cutting).
  - e. Discharge Point No. SW-005. Industrial activity associated with this discharge location is limited to material storage and handling.
  - f. Discharge Point No. SW-006. Industrial activity associated with this discharge location includes material storage and handling, fire hose hydrostatic testing, staging of abrasive blasting equipment (has independent secondary containment), and tank cleaning (has independent secondary containment).

The discharge of commingled storm water and industrial waste water is not authorized under this Order.

### B. Discharge Points and Receiving Waters

1. The Facility is located in Section \_\_, T \_\_, R \_\_, MDB&M, as shown in Attachment B, a part of this Order.
2. Wastewater and contact storm water is discharged into the San Diego Bay as summarized below:

**Table F-2. Discharge Locations**

Discharge Point	Effluent Description	Discharge Point Latitude	Discharge Point Longitude	Receiving Water
BW-001 (POSD)	Ballast Water			San Diego Bay
BW-002 (AFDL)	Ballast Water			San Diego Bay
FP-001 (Pier 3)	Fire protection water	32° 41' 25" N	117° 8' 41" W	San Diego Bay
FP-002 (Building 13)	Fire protection water	32° 41' 29" N	117° 8' 39" W	San Diego Bay
PW-001 (Pier 1)	Potable water leaks from hoses	32° 41' 38" N	117° 8' 46" W	San Diego Bay
PW-002 (Pier 3)	Potable water leaks from hoses	32° 41' 29" N	117° 8' 41" W	San Diego Bay
SC-001 (Pier 1)	Steam condensate leaks from hoses	32° 41' 28" N	117° 8' 46" W	San Diego Bay
SC-002 (Pier 3)	Steam condensate leaks from hoses	32° 41' 29" N	117° 8' 41" W	San Diego Bay
WW-001 (Pier 1)	Water weight test bags	32° 41' 28" N	117° 8' 46" W	San Diego Bay
WW-002 (Pier 3)	Water weight test bags	32° 41' 29" N	117° 8' 41" W	San Diego Bay
SW-001	Contact storm water	32° 41' 33" N	117° 8' 43" W	San Diego Bay
SW-002	Contact storm water	32° 41' 32" N	117° 8' 41" W	San Diego Bay
SW-003	Contact storm water	32° 41' 32" N	117° 8' 40" W	San Diego Bay
SW-004	Contact storm water	32° 41' 29" N	117° 8' 36" W	San Diego Bay
SW-005	Contact storm water	32° 41' 30" N	117° 8' 35" W	San Diego Bay
SW-006	Contact storm water	32° 41' 26" N	117° 8' 36" W	San Diego Bay

ADMINISTRATIVE DRAFT

3. In February 1998, the Regional Water Board designated 30 acres of the San Diego Bay's eastern shoreline near the Coronado Bridge as an impaired water body and included this area in the CWA section 303(d) list (currently the 303(d) listed shipyard sediment area consists of approximately 55 acres). The elevated levels of metals in the sediment led the Regional Water Board to issue Resolution No. 2001-03 on February 21, 2001 which directed the Executive Officer to issue a Water Code section 13267 letter to Southwest Marina (currently BAE Systems) and NASSCO requiring each shipyard to submit the results of a site-specific study to develop sediment cleanup levels and identify sediment cleanup alternatives by June 21, 2001.

NASSCO and BAE Systems conducted a detailed sediment investigation within the Shipyard Sediment Site adjacent to the NASSCO and BAE Systems lease holds. The results of the investigation are provided in the *Exponent report NASSCO and Southwest Marine Detailed Sediment Investigation, September 2003*. The Shipyard Report aided in the development of acceptable cleanup levels for the Shipyard Sediment Site.

Currently the Regional Water Board is working on Cleanup and Abatement Order No. R9-2005-0126, which the Discharger is expected to be regulated under. Cleanup and Abatement Order No. R9-2005-0126 is expected to require all the applicable dischargers to take all corrective actions necessary to cleanup contaminated marine bay sediment at the Shipyard Sediment Site.

### **C. Summary of Existing Requirements and Self-Monitoring Report (SMR) Data**

1. Discharge prohibitions for all authorized discharges contained in Order No. R9-2002-0161 include:
  - a. The Discharger shall comply with all requirements of the Basin Plan Waste Discharge Prohibitions which are hereby included in this Order.
  - b. The discharge of sewage, except as noted in the Basin Plan Waste Discharge Prohibitions, to San Diego Bay is prohibited.
  - c. The discharge of industrial process water other than non-contact cooling water and miscellaneous low volume water, is prohibited.
  - d. The discharge of the first flush of storm water runoff from high risk areas is prohibited, except if the pollutants in the discharge were reduced to the extent that compliance with the requirements of Discharge Specification [B.4 of Order No. R9-2002-0161 (acute toxicity limit summarized in Table F-3 of this Fact Sheet)] is achieved.
  - e. The discharge of municipal and industrial waste sludge and untreated sludge digester supernatant, centrate, or filtrate to San Diego Bay is prohibited.
  - f. The discharge of rubbish, refuse, debris, materials of petroleum origin, waste zinc plates, abrasives, primer, paint, paint chips, solvents, and marine fouling organisms, and the deposition of such wastes at any place where they could eventually be discharged is prohibited. This prohibition does not apply to the discharge of marine fouling organisms

removed from unpainted, uncoated surfaces by underwater operations and discharges that result from floating booms that were installed for "Force Protection" purposes.

g. The discharge of materials of petroleum origin in sufficient quantities to be visible is prohibited.

h. The discharge or bypassing of untreated waste to San Diego Bay is prohibited. (This prohibition does not apply to non-contact cooling water, miscellaneous low volume water, and fire protection water streams which comply with the requirements of this Order for elevated temperature waste discharges and which do not contain pollutants or waste other than heat.)

i. The discharge of polychlorinated biphenyl compounds, such as those used for transformer fluid, is prohibited.

j. The discharge of wastes and pollutants from underwater operations, (such as underwater paint and/or coating removal and underwater hull cleaning (e.g. "scamping")), is prohibited. This prohibition does not apply to the discharge of marine fouling organisms removed from unpainted and uncoated surfaces by underwater operations, or to discharges that result from the cleaning of floating booms that were installed for "Force Protection" purposes.

2. Discharge effluent limitations and specifications for fire protection water; miscellaneous low volume water (i.e, steam condensate and potable water leaks), and non-contact cooling water were contained in the previous Order. Effluent limitations contained in the previous Order are summarized in Table F-3.

**Table F-3. Numeric Effluent Limitations**

Parameter	Units	Instantaneous Maximum Effluent Limitation
Oil and Grease	mg/L	25
Settleable Solids	ml/L	1.0
Turbidity	NTU	75
pH	S.U.	Within limits of 6.0 – 9.0 at all times.
Temperature	Not more than 20°F greater than natural temperature of receiving waters.	
Acute Toxicity	1,2	
Chronic Toxicity	3,4	

<sup>1</sup> For miscellaneous low volume water and storm water, undiluted discharges to the San Diego Bay shall not produce less than 90% survival, 50% of the time, and not less than 70% survival, 10% of the time.

<sup>2</sup> For non-contact cooling water, fire protection water, and floating drydock ballast water, undiluted discharges to the San Diego Bay shall not produce less than 90% survival, 50% of the time, and not less than 70% survival, 10% of the time, except where the percent survival in San Diego Bay Water at the intake location is less than these levels. Where the percent survival in undiluted discharges to San Diego Bay which consist of water taken from San Diego Bay shall not be less than the percent survival in San Diego Bay water at the intake location. In the absence of test results demonstrating otherwise, it will be assumed that the percent survival in San Diego Bay water at the intake location is not less than these levels.

<sup>3</sup> For miscellaneous discharges, undiluted discharges to San Diego Bay shall not exceed 1 Toxicity Unit Chronic (TUc).

<sup>4</sup> For non-contact cooling water, fire protection water, and floating drydock ballast water, undiluted discharges to San Diego Bay which consist of water taken from San Diego Bay shall not exceed 1 Toxicity Unit Chronic (TUc), except where the chronic toxicity of San Diego Bay water at the intake location exceeds 1 TUc. Where the chronic toxicity of San Diego Bay water at the intake location exceeds 1 TUc, the chronic toxicity of undiluted discharges to San Diego Bay which consists of water taken from San Diego Bay shall not exceed the chronic toxicity of San Diego Bay water at the intake location. In the absence of test results demonstrating otherwise, it will be assumed that the chronic toxicity in San Diego Bay water at the intake location does not exceed 1 TUc.

3. All discharges regulated under Order No. R9-2002-0161 were prohibited from containing a hazardous substance equal to or in excess of a reportable quantity listed in Title 40 of the Code of Federal Regulations (40 CFR), Part 117 and/or 40 CFR 302.
4. In addition to numeric effluent limitations, the Discharger was required to reduce or prevent the discharge of pollutants through the implementation of best available technology (BAT) economically achievable for toxic, non-conventional, pollutants and Best Conventional Pollution Control Technology (BCT) for conventional pollutants through the development and implementation of a BMP Plan.
5. Waste discharges shall be discharged in a manner so as to achieve the most rapid initial dilution practicable to minimize concentrations of substances not removed by source control or treatment.
6. Waste management systems (e.g., wastewater treatment systems and waste storage facilities) shall be designed, constructed, operated, and maintained so as to prevent the discharge of pollutants and maintain indigenous marine life and a healthy and diverse marine community.
7. Waste discharges shall be essentially free of:
  - a. Material that is floatable or will become floatable upon discharge.
  - b. Settleable material or substances that may form sediments which will degrade benthic communities or other aquatic life.
  - c. Substances which will accumulate to toxic levels in marine waters, sediment, or biota.
  - d. Materials the result in aesthetically undesirable discoloration of receiving waters.
  - e. Substances that significantly decrease the natural light to benthic communities and other marine life.

8. A summary of the available monthly monitoring data for regulated parameters for fire protection (Piers 1, 3, and Building 13), Building 13 cooling water, water weight bag effluent, and steam condensate are summarized below:

**Table F-4. Discharge Data Summary**

Parameter	Unit	Highest Reported Value			
		Fire Protection	Building 13 Cooling Water	Water Weight Bag Effluent	Steam Condensate
Oil and Grease	mg/L	<1	<1	7	<1
Settleable Solids	m/L	<0.2	<0.2	<0.2	<0.2
Turbidity	NTU	2.96	2.01	24.4	0.36
pH	su	7.9	7.8	8.6	8.6
Temperature	°F	NA	NA	NA	NA
Acute Toxicity <sup>1</sup>	% survival	90	95	95	95
Chronic Toxicity	TU <sub>c</sub>	1	0.41	0.41	>1

NA – Not Available

<sup>1</sup> Lowest survival percentage.

9. Acute toxicity survival percentages for storm water for eight sampling events between December 7, 2004 through March 22, 2006, in which treated storm water was discharged to the San Diego Bay ranged from 90 to 100 percent. The Facility has not discharged storm water to the Bay since April 6, 2006, on which no toxicity sampling was conducted.

DRAFT



#### **D. Compliance Summary**

No effluent limitation exceedances were identified during the permit term.

On December 6, 2007, the Facility was inspected by a USEPA contractor to determine compliance with Order No. R9-2002-0161. Major findings reported from that inspection include:

1. "Regional Water Board Order No. R9-2002-0161, Attachment B – Best Management Practices Program Requirements, Provision 4.a, requires the Discharger to include a site map in the Best Management Practices (BMP) Manual indicating the direction of flow and outlet point of each drainage area. The site maps included in the BMP Plan Manual did not describe the direction of flow of each drainage area."

#### **E. Planned Changes – Not Applicable**

### **III. APPLICABLE PLANS, POLICIES, AND REGULATIONS**

The requirements contained in the proposed Order are based on the requirements and authorities described in this section.

#### **A. Legal Authorities**

This Order is issued pursuant to section 402 of the federal Clean Water Act (CWA) and implementing regulations adopted by the USEPA and chapter 5.5, division 7 of the California Water Code (commencing with section 13370). It shall serve as a NPDES permit for point source discharges from this facility to surface waters. This Order also serves as WDRs pursuant to article 4, chapter 4, division 7 of the Water Code (commencing with section 13260).

#### **B. California Environmental Quality Act (CEQA)**

Under Water Code section 13389, this action to adopt an NPDES permit is exempt from the provisions of CEQA, Public Resources Code sections 21100 through 21177.

#### **C. State and Federal Regulations, Policies, and Plans**

1. **Water Quality Control Plans.** The Regional Water Quality Control Board (Regional Water Board) adopted a Water Quality Control Plan for the San Diego Basin (hereinafter Basin Plan) on September 8, 1994, and last amended on April 25, 2007. The Basin Plan was subsequently approved by the State Water Resources Control Board (State Water Board) on December 13, 1994. Subsequent revisions to the Basin Plan have also been adopted by the Regional Water Board and approved by the State Water Board. The Basin Plan designates beneficial uses, establishes water quality objectives, and contains implementation programs and policies to achieve those objectives for all waters addressed through the plan. In addition, the Basin Plan implements State Water Board Resolution No. 88-63, which established State policy that all waters, with certain exceptions, should be considered suitable or

potentially suitable for municipal or domestic supply. Requirements of this Order implement the Basin Plan. Beneficial uses applicable to San Diego Bay are as follows:

**Table F-5. Basin Plan Beneficial Uses**

Discharge Point	Receiving Water Name	Beneficial Use(s)
FP-001, FP-002; PW-001, PW-002; SC-001, SC-002; WW-001, WW-002; SW-001 through SW-006	San Diego Bay	<u>Existing:</u> Industrial Service Supply (IND); navigation (NAV); contact water recreation (REC1); non-contact water recreation (REC2); commercial and sport fishing (COMM); preservation of biological habitats of special significance (BIOL); estuarine habitat (EST); wildlife habitat (WILD); preservation of rare, threatened or endangered species (RARE); marine habitat (MAR); migration of aquatic organisms (MIGR); shellfish harvesting (SHELL)

Requirements of this Order implement the Basin Plan.

2. **Thermal Plan.** The State Water Board adopted a *Water Quality Control Plan for Control of Temperature in the Coastal and Interstate Water and Enclosed Bays and Estuaries of California* (Thermal Plan) on 18 May 1972, and amended this plan on 18 September 1975. This plan contains temperature objectives for surface waters. Requirements of this Order implement the Thermal Plan.
3. **National Toxics Rule (NTR) and California Toxics Rule (CTR).** USEPA adopted the NTR on December 22, 1992, and later amended it on May 4, 1995 and November 9, 1999. About 40 criteria in the NTR applied in California. On May 18, 2000, USEPA adopted the CTR. The CTR promulgated new toxics criteria for California and, in addition, incorporated the previously adopted NTR criteria that were applicable in the state. The CTR was amended on February 13, 2001. These rules contain water quality criteria for priority pollutants.
4. **State Implementation Policy.** On March 2, 2000, the State Water Board adopted the *Policy for Implementation of Toxics Standards for Inland Surface Waters, Enclosed Bays, and Estuaries of California* (State Implementation Policy or SIP). The SIP became effective on April 28, 2000 with respect to the priority pollutant criteria promulgated for California by the USEPA through the NTR and to the priority pollutant objectives established by the Regional Water Board in the Basin Plan. The SIP became effective on May 18, 2000 with respect to the priority pollutant criteria promulgated by the USEPA through the CTR. The State Water Board adopted amendments to the SIP on February 24, 2005 that became effective on July 13, 2005. The SIP establishes implementation provisions for priority pollutant criteria and objectives and provisions for chronic toxicity control. Requirements of this Order implement the SIP.
5. **Alaska Rule.** On March 30, 2000, USEPA revised its regulation that specifies when new and revised state and tribal water quality standards (WQS) become effective for CWA purposes (40 CFR § 131.21, 65 Fed. Reg. 24641 (April 27, 2000)). Under the revised regulation (also known as the Alaska rule), new and revised standards

submitted to USEPA after May 30, 2000, must be approved by USEPA before being used for CWA purposes. The final rule also provides that standards already in effect and submitted to USEPA by May 30, 2000, may be used for CWA purposes, whether or not approved by USEPA.

- 6. Antidegradation Policy.** Section 131.12 requires that the state water quality standards include an antidegradation policy consistent with the federal policy. The State Water Board established California's antidegradation policy in State Water Board Resolution No. 68-16. Resolution No. 68-16 incorporates the federal antidegradation policy where the federal policy applies under federal law. Resolution No. 68-16 requires that existing water quality be maintained unless degradation is justified based on specific findings. The Regional Water Board's Basin Plan implements, and incorporates by reference, both the State and federal antidegradation policies. The permitted discharge must be consistent with the antidegradation provision of section 131.12 and State Water Board Resolution No. 68-16.
- 7. Anti-Backsliding Requirements.** Sections 402(o)(2) and 303(d)(4) of the CWA and federal regulations at title 40, Code of Federal Regulations<sup>1</sup> section 122.44(l) prohibit backsliding in NPDES permits. These anti-backsliding provisions require that effluent limitations in a reissued permit must be as stringent as those in the previous permit, with some exceptions in which limitations may be relaxed.

#### **D. Impaired Water Bodies on CWA 303(d) List**

Under section 303(d) of the 1972 Clean Water Act, states, territories and authorized tribes are required to develop lists of water quality limited segments. The waters on these lists do not meet water quality standards, even after point sources of pollution have installed the minimum required levels of pollution control technology. On November 30, 2006 USEPA gave final approval to California's 2006 section 303(d) List of Water Quality Limited Segments. The San Diego Bay, as a whole, is listed as impaired for polychlorinated biphenyls (PCBs). Additional portions of the San Diego Bay are listed as impaired for additional parameters. Portions of the San Diego Bay applicable to the Facility include, "San Diego Bay Shoreline, near Coronado Bridge", "San Diego Bay Shoreline, between Sampson and 28<sup>th</sup> Streets", and "San Diego Bay Shoreline, near Chollas Creek". These portions of the San Diego Bay are listed in the 303(d) list as impaired for: benthic community effects, copper, mercury, polycyclic aromatic hydrocarbons (PAHs), PCBs, sediment toxicity, and zinc.

An applicable Total Maximum Daily Load (TMDL) has not yet been adopted by the Regional Water Board and approved by USEPA. A TMDL for sediment toxicity is currently being developed for the "San Diego Bay Shoreline, near Chollas Creek". In the event that this TMDL is finalized during the term of this Order, the Regional Water Board reserves the right to reopen and revise this Order as necessary to comply with the applicable TMDL.

<sup>1</sup> All further statutory references are to title 40 of the Code of Federal Regulations unless otherwise indicated.

## E. Other Plans, Policies and Regulations

1. Bays and Estuaries Policy. The State Water Board adopted a Water Quality Control Policy for Enclosed Bays and Estuaries of California (Bays and Estuaries Policy) on May 16, 1974 (last amended in 1995). The Bays and Estuary Policy establishes principles for management of water quality, quality requirements for waste discharges, discharge prohibitions, and general provisions to prevent water quality degradation and to protect the beneficial uses of waters of enclosed bays and estuaries. These principles, requirements, prohibitions and provisions have been incorporated into this Order.

- a. The Bays and Estuaries Policy contains the following principle for management of water quality in enclosed bays and estuaries, which includes the San Diego Bay:

- 1) The discharge of municipal wastewaters and industrial process waters (exclusive of cooling water discharges) to enclosed bays and estuaries shall be phased out at the earliest practicable date. Exceptions to this provision may be granted by a Regional Water Board only when the Regional Water Board finds that the wastewater in question would consistently be treated and discharged in such a manner that it would enhance the quality of receiving waters above that which would occur in the absence of the discharge. For the purpose of this policy, treated ballast waters and innocuous non-municipal wastewater such as clear brines, washwater, and pool drains are not necessarily considered industrial process wastes, and may be allowed by Regional Water Boards under discharge requirements that provide protection to the beneficial uses of the receiving water.
- 2) The Bays and Estuaries Policy also prohibits the discharge or by-passing of untreated wastes. This Order prohibits the discharge and by-passing of untreated waste except for non-contact fire protection system water, hydrostatic relief water, and flood water. For the purpose of the Bays and Estuaries Policy and this TENTATIVE ORDER NO. R9-2008-0048, the discharges of fire protection water; potable water leaks from hoses; steam condensate leaks from hoses; and water weight test bag effluent will be considered innocuous non-municipal wastewaters and, as such, will not be considered industrial process wastes.

- b. The following Principles for the Management of Water Quality in Enclosed Bays and Estuaries, as stated in the Bays and Estuaries Policy, apply to all of California's enclosed bays and estuaries including San Diego Bay:

- 1) Persistent or cumulative toxic substances shall be removed from the waste to the maximum extent practicable through source control or adequate treatment prior to discharge.
- 2) Bay or estuarine outfall and diffuser systems shall be designed to achieve the most rapid initial dilution practicable to minimize concentrations of substances not removed by source control or treatment.

- 3) Wastes shall not be discharged into or adjacent to areas where the protection of beneficial uses requires spatial separation from waste fields.
- 4) Waste discharges shall not cause a blockage of zones of passage required for the migration of anadromous fish.
- 5) Non-point sources of pollutants shall be controlled to the maximum practicable extent.

This Regional Water Board has considered the Principle for the Management of Water Quality in Enclosed Bays in Estuaries, in adopting this Order. The terms and conditions of this Order are consistent with the Principles for the Management of Water Quality in Enclosed Bays and Estuaries.

#### IV. RATIONALE FOR EFFLUENT LIMITATIONS AND DISCHARGE SPECIFICATIONS

The CWA requires point source dischargers to control the amount of conventional, non-conventional, and toxic pollutants that are discharged into the waters of the United States. The control of pollutants discharged is established through effluent limitations and other requirements in NPDES permits. There are two principal bases for effluent limitations in the Code of Federal Regulations: section 122.44(a) requires that permits include applicable technology-based limitations and standards; and section 122.44(d) requires that permits include WQBELs to attain and maintain applicable numeric and narrative water quality criteria to protect the beneficial uses of the receiving water.

##### A. Discharge Prohibitions

1. California Water Code section 13243 provides that the Regional Water Board, in a water quality control plan, may specify certain conditions where the discharge of wastes or certain types of wastes that could affect the quality of waters of the state is prohibited. The Basin Plan prohibitions are incorporated by reference in the Order. Prohibition III.A and III.B are carried over from the previous Order and require the Discharger to comply with the Basin Plan prohibitions.
  2. Discharge Prohibitions III.C, III.E, III.F, III.G, and III.H are based on the requirements of the Enclosed Bays and Estuaries Policy and are carried over from the previous Order.
  3. Discharge Prohibition III.D is based on the toxicity requirements contained in the Basin Plan.
  4. Discharge Prohibition III.I, which prohibits the discharge of PCBs, is carried over from the previous Order based on the 303(d) listing for these compounds for San Diego Bay.
  5. Discharge Prohibition III.J prohibits the discharge of waste and pollutants from underwater operations, and has been carried over from the previous Order.

## B. Technology-Based Effluent Limitations

### 1. Scope and Authority

Section 301(b) of the CWA and implementing USEPA permit regulations at section 122.44, title 40 of the Code of Federal Regulations, require that permits include conditions meeting applicable technology-based requirements at a minimum, and any more stringent effluent limitations necessary to meet applicable water quality standards. The discharges authorized by this Order must meet minimum federal technology-based requirements based on Best Professional Judgment (BPJ) in accordance with 40 CFR section 125.3.

The CWA requires that technology-based effluent limitations be established based on several levels of controls:

- a. Best practicable treatment control technology (BPT) represents the average of the best performance by plants within an industrial category or subcategory. BPT standards apply to toxic, conventional, and non-conventional pollutants.
- b. Best available technology economically achievable (BAT) represents the best existing performance of treatment technologies that are economically achievable within an industrial point source category. BAT standards apply to toxic and non-conventional pollutants.
- c. Best conventional pollutant control technology (BCT) represents the control from existing industrial point sources of conventional pollutants including BOD, TSS, fecal coliform, pH, and oil and grease. The BCT standard is established after considering the "cost reasonableness" of the relationship between the cost of attaining a reduction in effluent discharge and the benefits that would result, and also the cost effectiveness of additional industrial treatment beyond BPT.
- d. New source performance standards (NSPS) represent the best available demonstrated control technology standards. The intent of NSPS guidelines is to set limitations that represent state-of-the-art treatment technology for new sources.

The CWA requires USEPA to develop effluent limitations, guidelines and standards (ELGs) representing application of BPT, BAT, BCT, and NSPS. Section 402(a)(1) of the CWA and section 125.3 of the Code of Federal Regulations authorize the use of BPJ to derive technology-based effluent limitations on a case-by-case basis where ELGs are not available for certain industrial categories and/or pollutants of concern. Where BPJ is used, the permit writer must consider specific factors outlined in section 125.3.

ADMINISTRATIVE DRAFT

## 2. Applicable Technology-Based Effluent Limitations

- a. The State Water Board adopted a revised Water Quality Control Plan for Ocean Waters of California (Ocean Plan) on April 21, 2005, which became effective on February 14, 2006. Although the Ocean Plan is not directly applicable to enclosed bays, such as San Diego Bay, the salinity and beneficial uses of San Diego Bay are similar to those of the ocean waters of the State. Therefore, in order to protect the beneficial uses of San Diego Bay, the previous Order used the Ocean Plan as a reference for developing discharge specifications, receiving water prohibitions, and narrative limitations and to supplement the provisions contained in the CTR, the SIP, and the Bays and Estuaries Policy.

The Ocean Plan establishes water quality objectives, general requirements for management of waste discharged to the ocean, effluent quality requirements for waste discharges, discharge prohibitions, and general provisions. Further, Table A of the Ocean Plan establishes technology-based effluent limitations for discharges for which ELGs have not been established pursuant to sections 301, 302, 304, or 306 of the federal CWA.

Based on Table A of the Ocean Plan, Board Order No. R9-2002-0161 established numeric effluent limitations for non-contact cooling water, miscellaneous low volume water, and fire protection water.

The effluent limitations contained in Table A of the Ocean Plan are summarized below:

**Table F-6. Ocean Plan Table A Effluent Limitations**

Parameter	Units	Table A Effluent Limitations		
		Average Monthly	Weekly Average	Instantaneous Maximum
Oil and Grease	mg/L	25	40	75
Settleable Solids	ml/L	1.0	1.5	3.0
Turbidity	NTU	75	100	225
pH	pH units	--	--	<sup>1</sup>

<sup>1</sup> Within limits of 6.0 – 9.0 at all times.

The numeric effluent limitations contained in Order No. R9-2002-0161, based on Table A of the Ocean Plan are summarized below:

**Table F-7. Numeric Technology-based Effluent Limitations**

Parameter	Unit	Average Monthly
Oil and Grease	mg/L	25
Settleable Solids	ml/L	1.0
Turbidity	NTU	75
pH	pH units	--

<sup>1</sup> Within limits of 6.0 – 9.0 at all times.

- b. In addition to numeric technology-based limitations, and in accordance with 40 CFR 122.44(k), the previous Order determined that the implementation of BMPs for the discharge of industrial wastes associated with ship construction, repair and maintenance activities were appropriate. To carry out the purpose and intent of the CWA, the previous Order required the Discharger to develop and implement a BMP plan, as authorized by CWA section 304(e) and section 402(p), for toxic pollutants and hazardous substances, and for the control of storm water discharges at Discharge Point Nos. SW-001 through SW-002.

The requirement to implement an appropriate BMP plan are carried over from Order No. R9-2002-0161. Further, the previous Order established only the average monthly effluent limitations in Table A of the Ocean Plan. This Order establishes the weekly average and instantaneous maximum limitations contained in the Ocean Plan, consistent with current requirements for similar facilities in the Region, and in accordance with footnote 1 to Table A, which states, "Table A effluent limitations apply only to publicly owned treatment works and industrial discharges for which Effluent Limitations Guidelines have not been established pursuant to sections 301, 302, 304, or 306 of the Federal Clean Water Act."

In addition, and consistent with the current requirements for a similar facility in the Region (NPDES No. CA0109134 – NASSCO) the numeric technology-based effluent limitations are applied to the discharge of ballast water from the floating drydocks at Discharge Point Nos. BW-001 and BW-002.

ADMINISTRATIVE DRAFT



## C. Water Quality-Based Effluent Limitations (WQBELs)

### 1. Scope and Authority

Section 301(b) of the CWA and section 122.44(d) require that permits include limitations more stringent than applicable federal technology-based requirements where necessary to achieve applicable water quality standards.

Section 122.44(d)(1)(i) mandates that permits include effluent limitations for all pollutants that are or may be discharged at levels that have the reasonable potential to cause or contribute to an exceedance of a water quality standard, including numeric and narrative objectives within a standard. Where reasonable potential has been established for a pollutant, but there is no numeric criterion or objective for the pollutant, WQBELs must be established using: (1) USEPA criteria guidance under CWA section 304(a), supplemented where necessary by other relevant information; (2) an indicator parameter for the pollutant of concern; or (3) a calculated numeric water quality criterion, such as a proposed state criterion or policy interpreting the state's narrative criterion, supplemented with other relevant information, as provided in section 122.44(d)(1)(vi).

The process for determining reasonable potential and calculating WQBELs when necessary is intended to protect the designated uses of the receiving water as specified in the Basin Plan, and achieve applicable water quality objectives and criteria that are contained in other state plans and policies, or any applicable water quality criteria contained in the CTR and NTR.

### 2. Applicable Beneficial Uses and Water Quality Criteria and Objectives

The Basin Plan designates beneficial uses, establishes water quality objectives, and contains implementation programs and policies to achieve those objectives for all waters addressed through the Basin Plan. The beneficial uses applicable to the San Diego Bay are summarized in section III.C.1 of this Fact Sheet. The Basin Plan includes both narrative and numeric water quality objectives applicable to the receiving water.

The CTR promulgated now toxics criteria for California and, in addition, incorporated the previously adopted National Toxics Rule criteria that were applicable in the State. Priority pollutant water quality criteria in the CTR are applicable to San Diego Bay. The CTR contains both saltwater and freshwater criteria. Because a distinct separation generally does not exist between freshwater and saltwater aquatic communities, the following apply: In accordance with section 131.38(c)(3), freshwater criteria apply to areas where salinities are at or below at salinities of 1 part per thousand (ppt) and below at locations where this occurs 95 percent or more of the time. The Regional Water Board determined that because the discharge is within a bay, saltwater CTR criteria are applicable. The CTR criteria for saltwater or human health for consumption of organisms, whichever is more stringent, are used

to prescribe the effluent limitations in this Order to protect the beneficial uses of the San Diego Bay, a water of the United States in the vicinity of the discharge.

The CTR and NTR are only applicable to non-storm water discharges. The non-storm water discharges from the Facility to San Diego Bay include fire protection water, potable water leaks from hoses, steam condensate from hoses, and water weight test bag effluent. On March 26, 2002, the Discharger monitored fire protection water from Building 13 for priority pollutants. A priority pollutant scan (initial testing) was performed on this data. All pollutants, with the exception of antimony, arsenic, copper, selenium, and zinc were at non-detectable levels in the effluent. The Regional Water Board found that copper was at levels that necessitated additional monitoring. Monthly monitoring for copper, was established in Order No. R9-2002-0161 for fire protection water for a two year period (and for non-contact cooling water, which is no longer discharged). Annual monitoring was established for arsenic, cadmium, chromium, lead, mercury, nickel, silver, and zinc for non-storm water discharges.

A reasonable potential analysis was conducted for the non-storm water discharges to the San Diego Bay using all the available data (November 2002 through August 2007). The table below summarizes the applicable water quality criteria/objectives for priority pollutants reported in detectable concentrations in the effluent or receiving water. These criteria were used in conducting the RPAs for this Order.

**Table F-8. Applicable Water Quality Criteria**

Constituent	Selected Criteria μg/L	CTR/NTR Water Quality Criteria					
		Freshwater		Saltwater		Human Health for Consumption of:	
		Acute μg/L	Chronic μg/L	Acute μg/L	Chronic μg/L	Water & Organisms μg/L	Organisms Only μg/L
Arsenic, Total Recoverable	36.00	Not Applicable		69.00	36.00	Not Applicable	--
Cadmium, Total Recoverable	9.36			42.25	9.36		--
Chromium, Total Recoverable	50.35			1107.75	50.35		--
Copper, Total Recoverable	3.73			5.78	3.73		--
Lead, Total Recoverable	8.52			220.82	8.52		--
Mercury, Total Recoverable	0.051			--	--		0.051
Nickel, Total Recoverable	8.28			74.75	8.28		--
Silver, Total Recoverable	2.24			2.24	--		--
Zinc, Total Recoverable	85.62			95.14	85.62		--

### 3. Determining the Need for WQBELs

- a. Federal regulations require effluent limitations for all pollutants that are or may be discharged at a level that will cause or have the reasonable potential to cause, or contribute to an in-stream excursion above a narrative or numerical water quality standard. Based on information submitted as part of the application, in studies,

**ADMINISTRATIVE DRAFT**

and as directed by monitoring and reporting programs, the Regional Water Board finds that the discharges summarized below have reasonable potential to cause or contribute to an in-stream excursion above a water quality standard at one or more of the discharge locations for arsenic, copper, and lead. The Regional Water Board conducted the RPA in accordance with section 1.3 of the SIP. A summary of the results for the parameters which demonstrated reasonable potential, for each applicable discharge, is provided in the table below.

**Table F-9. Summary of RPA Results**

Discharge Location No.	Parameter	Maximum Effluent Concentration (MEC) (µg/L)	Background (B) (µg/L)	Criteria (C) (µg/L)	Reason <sup>1</sup>
FP-001, FP-002 (Fire Protection Water)	Arsenic, Total Recoverable	43	45	36	MEC & B > C
	Copper, Total Recoverable	151	31.8	3.73	MEC & B > C
SC-001, SC-002 (Steam Condensate)	Copper, Total Recoverable	77.3	31.8	3.73	MEC & B > C
	Lead, Total Recoverable	58	<5	8.52	MEC > C
WW-001, WW-002 (Water Weight Test Bags)	Arsenic, Total Recoverable	23	45	36	B > C & MEC is detectable <sup>2</sup>
	Copper, Total Recoverable	19.3	31.8	3.73	MEC & B > C

<sup>1</sup> MEC – Maximum Effluent Concentration

B – Background Concentration

C – Criteria (Water Quality)

<sup>2</sup> Step 6 of section 1.3 of the SIP states that if B is greater than C and the pollutant is detected in the effluent, an effluent limitation is required and the analysis for the subject pollutant is complete.

- b. Data for the potable water leaks from hoses (PW-001 and PW-002), and ballast water discharges (BW-001 and BW-002) were not available to conduct a RPA. Monitoring requirements for the CTR priority pollutants have been established in the MRP for potable water leaks from hoses at Discharge Point Nos. PW-001 and PW-002), and ballast water discharges (BW-001 and BW-002) to determine reasonable potential for these discharges during future permitting efforts. Pollutants of concern for ballast water include copper and arsenic, as background data indicates that they are present in the receiving water at levels that exceed water quality criteria and are likely to be present in the discharge of ballast water. However, the facility does not alter the floating drydock ballast tank water chemically or physically, so additional degradation of the receiving water during the monitoring period due to the discharge of ballast water is not expected. Data collected over this permit term may be used to determine if intakes credits may be appropriately applied to the discharge of ballast water at the Facility for various parameters. The Order may be reopened by the Regional Water Board for revisions as allowed in Provision VI.C.1.d (reopener), for the addition of effluent limitations, prohibitions, and additional monitoring requirements, based on the findings of the priority pollutant monitoring.

ADMINISTRATIVE DRAFT

**4. WQBEL Calculations**

- a. The WQBEL for pH is based on the water quality objective contained in the Basin Plan, which states, "In bays and estuaries the pH shall not be depressed below 7.0 nor raised above 9.0." The WQBEL for temperature is based on Part 4.B.(1) of the Thermal Plan.
- b. Effluent limitations for copper, arsenic, and lead were calculated in accordance with section 1.4 of the SIP. The following paragraphs describe the methodology used for calculating effluent limitations for these parameters.
- c. **Effluent Limitation Calculations.** In calculating maximum effluent limitations, the effluent concentration allowances were set equal to the criteria/standards/objectives.

$$ECA_{acute} = CMC$$

$$ECA_{chronic} = CCC$$

For the human health, agriculture, or other long-term criterion/objective, a dilution credit can be applied. The ECA is calculated as follows:

$$ECA_{HH} = HH + D(HH - B)$$

where:

$ECA_{acute}$  = effluent concentration allowance for acute (1-hour average) toxicity criterion

$ECA_{chronic}$  = effluent concentration allowance for chronic (4-day average) toxicity criterion

$ECA_{HH}$  = effluent concentration allowance for human health, agriculture, or other long-term criterion/objective

CMC = criteria maximum concentration (1-hour average)

CCC = criteria continuous concentration (4-day average, unless otherwise noted)

HH = human health, agriculture, or other long-term criterion/objective

D = dilution credit

B = maximum receiving water concentration

Acute and chronic toxicity ECAs were then converted to equivalent long-term averages (LTA) using statistical multipliers and the lowest is used. Additional statistical multipliers were then used to calculate the maximum daily effluent limitation (MDEL) and the average monthly effluent limitation (AMEL).

Human health ECAs are set equal to the AMEL and a statistical multiplier is used to calculate the MDEL.

LTA<sub>acute</sub>

ADMINISTRATIVE DRAFT

$$AMEL = mult_{AMEL} [\min(M_A ECA_{acute}, M_C ECA_{chronic})]$$

$$MDEL = mult_{MDEL} [\min(M_A ECA_{acute}, M_C ECA_{chronic})]$$

LTA<sub>chronic</sub>

$$MDEL_{HH} = \left( \frac{mult_{MDEL}}{mult_{AMEL}} \right) AMEL_{HH}$$

where:  $mult_{AMEL}$  = statistical multiplier converting minimum LTA to AMEL

$mult_{MDEL}$  = statistical multiplier converting minimum LTA to MDEL

$M_A$  = statistical multiplier converting CMC to LTA

$M_C$  = statistical multiplier converting CCC to LTA

WQBELs were calculated for cadmium, copper, mercury, nickel, and zinc as follows in Tables F-10 through F-12, below.

**Table F-10. WQBEL Calculations for Arsenic**

	Acute	Chronic
Criteria (µg/L) <sup>1</sup>	69	36
Dilution Credit	No Dilution	No Dilution
ECA	69	36
ECA Multiplier	0.32	0.53
LTA	22.15	18.99
AMEL Multiplier (95 <sup>th</sup> %)	<sup>2</sup>	1.55
<b>AMEL (µg/L)</b>	<sup>2</sup>	<b>29.48</b>
MDEL Multiplier (99 <sup>th</sup> %)	<sup>2</sup>	3.11
<b>MDEL (µg/L)</b>	<sup>2</sup>	<b>59.14</b>

<sup>1</sup> CTR Aquatic Life Criteria

<sup>2</sup> Limitations based on chronic LTA (Chronic LTA < Acute LTA)

**Table F-11. WQBEL Calculations for Copper**

	Acute	Chronic
Criteria (µg/L) <sup>1</sup>	5.78	9.36
Dilution Credit	No Dilution	No Dilution
ECA	5.78	9.36
ECA Multiplier	0.32	0.53
LTA	1.86	4.94
AMEL Multiplier (95 <sup>th</sup> %)	1.55	<sup>2</sup>
<b>AMEL (µg/L)</b>	<b>2.88</b>	<sup>2</sup>
MDEL Multiplier (99 <sup>th</sup> %)	3.11	<sup>2</sup>
<b>MDEL (µg/L)</b>	<b>5.78</b>	<sup>2</sup>

ADMINISTRATIVE DRAFT

<sup>1</sup> CTR Aquatic Life Criteria<sup>2</sup> Limitations based on acute LTA (Chronic LTA > Acute LTA)**Table F-12. WQBEL Calculations for Lead**

	Acute	Chronic
Criteria (µg/L) <sup>1</sup>	220.82	8.52
Dilution Credit	No Dilution	No Dilution
ECA	220.82	8.52
ECA Multiplier	0.32	0.53
LTA	70.9	4.49
AMEL Multiplier (95 <sup>th</sup> %)	<sup>2</sup>	1.55
<b>AMEL (µg/L)</b>	<sup>2</sup>	<b>6.98</b>
MDEL Multiplier (99 <sup>th</sup> %)	<sup>2</sup>	3.11
<b>MDEL (µg/L)</b>	<sup>2</sup>	<b>14.00</b>

<sup>1</sup> CTR Aquatic Life Criteria<sup>2</sup> Limitations based on chronic LTA (Chronic LTA < Acute LTA)

- d. A summary of the applicable WQBELs for the Discharger are summarized below:

**Table F-13. Summary of CTR Water Quality-based Effluent Limitations**

Discharge Location	Parameter	Units	Effluent Limitations	
			Average Monthly	Maximum Daily
FP-001, FP-002 (Fire Protection Water)	Arsenic, Total Recoverable	µg/L	29.48	59.14
	Copper, Total Recoverable	µg/L	2.88	5.78
SC-001, SC-002 (Steam Condensate)	Copper, Total Recoverable	µg/L	2.88	5.78
	Lead, Total Recoverable	µg/L	6.98	14.00
WW-001, WW-002 (Water Weight Test Bags)	Arsenic, Total Recoverable	µg/L	29.48	59.14
	Copper, Total Recoverable	µg/L	2.88	5.78

- 1) All discharges shall maintain a pH of between 7.0 standard units and 9.0 standard units at all times.
- 2) At no time shall any discharge be greater than 20°F over the natural temperature of the receiving water.

### 5. Whole Effluent Toxicity (WET)

Place Holder – To be completed pending review of US Navy toxicity evaluation report

#### D. Final Effluent Limitations

1. Applicable technology-based effluent limitations and WQBELs described in sections IV.B and IV.C have been applied in TENTATIVE ORDER NO. R9-2008-0048. Both WQBELs and technology-based effluent limitations were applicable the discharges (6.0 – 9.0 standard units and 7.0 – 9.0 standard units, respectively). To insure the protection of water quality, the more stringent lower and upper limitations for pH have been applied as

the final effluent limitations in TENTATIVE ORDER NO. R9-2008-0048.

2. Discharges from the Facility shall not exceed the effluent limitations summarized below:

**Table F-14. Effluent Limitations For All Discharges**

Parameter	Units	Effluent Limitations		
		Average Monthly	Weekly Average	Instantaneous Maximum
Oil and Grease	mg/L	25	40	75
Settleable Solids	ml/L	1.0	1.5	3.0
Turbidity	NTU	75	100	225
pH	pH units	--	--	<sup>1</sup>
Temperature	°F	--	--	<sup>2</sup>

<sup>1</sup> Within limits of 7.0 – 9.0 at all times.

<sup>2</sup> At no time shall any discharge be greater than 20°F over the natural temperature of the receiving water.

3. Discharges from Facility shall meet the location specific effluent limitations specified below:

**Table F-15. Summary of Final Effluent Limitations By Discharge Location**

Discharge Location	Parameter	Units	Effluent Limitations	
			Average Monthly	Maximum Daily
FP-001, FP-002 (Fire Protection Water)	Arsenic, Total Recoverable	µg/L	29.48	59.14
	Copper, Total Recoverable	µg/L	2.88	5.78
SC-001, SC-002 (Steam Condensate)	Copper, Total Recoverable	µg/L	2.88	5.78
	Lead, Total Recoverable	µg/L	6.98	14.00
WW-001, WW-002 (Water Weight Test Bags)	Arsenic, Total Recoverable	µg/L	29.48	59.14
	Copper, Total Recoverable	µg/L	2.88	5.78

- a. In addition to numeric technology-based limitations, the previous Order determined that numeric effluent limitations for many parameters are infeasible. To carry out the purpose and intent of the CWA, the previous Order required the Discharger to develop and implement a BMP plan, as authorized by CWA section 304(e) and section 402(p), for toxic pollutants and hazardous substances, and for the control of storm water discharges at Discharge Point Nos. SW-001 through SW-006.

#### 4. Satisfaction of Anti-Backsliding Requirements

All effluent limitations in this Order are at least as stringent as the effluent limitations in the previous Order and meet State and federal anti-backsliding requirements.

#### 5. Satisfaction of Antidegradation Policy

Waste Discharge Requirements for the Discharger must conform with federal and state antidegradation policies provided at 40 CFR 131.12 and in State Board

ADMINISTRATIVE DRAFT

Resolution No. 68-16, Statement of Policy with Respect to Maintaining High Quality of Waters in California. The antidegradation policies require that beneficial uses and the water quality necessary to maintain those beneficial uses in the receiving waters of the discharge shall be maintained and protected, and, if existing water quality is better than the quality required to maintain beneficial uses, the existing water quality shall be maintained and protected unless allowing a lowering of water quality is necessary to accommodate important economic and social development or consistent with maximum benefit to the people of California. When a significant lowering of water quality is allowed by the Regional Water Board, an antidegradation analysis is required in accordance with the State Water Board's Administrative Procedures Update (July 2, 1990), Antidegradation Policy Implementation for NPDES Permitting.

The limitations and requirements of TENTATIVE ORDER NO. R9-2008-0048 are more stringent than established in the previous Order. The permitted discharge is consistent with the antidegradation provisions of 40 CFR 131.12 and State Water Board Resolution No. 68-16. Compliance with these requirements will result in the use of best practicable treatment or control of the discharge. The impact on existing water quality will be insignificant.

## **6. Stringency of Requirements for Individual Pollutants**

This Order contains both technology-based and water quality-based effluent limitations for individual pollutants. The technology-based effluent limitations applied in the Order consist of restrictions on oil and grease, pH (upper limitation), settleable solids, turbidity, and a requirement to continue to implement a BMP plan for toxic pollutants, hazardous substances and storm water. Restrictions on oil and grease, pH (upper limitation), settleable solids, turbidity, and the BMP plan for toxic pollutants and hazardous substances are discussed in section IV.B.2. This Order's technology-based pollutant restrictions implement the minimum, applicable federal technology-based requirements. These limitations are not more stringent than required by the CWA.

Water quality-based effluent limitations have been scientifically derived to implement water quality objectives that protect beneficial uses. Both the beneficial uses and the water quality objectives have been approved pursuant to federal law and are the applicable federal water quality standards. To the extent that toxic pollutant WQBELs were derived from the CTR, the CTR is the applicable standard pursuant to section 131.38. The scientific procedures for calculating the individual WQBELs for priority pollutants are based on the CTR-SIP, which was approved by USEPA on May 18, 2000. All beneficial uses and water quality objectives contained in the Basin Plan were approved under state law and submitted to and approved by USEPA prior to May 30, 2000. Any water quality objectives and beneficial uses submitted to USEPA prior to May 30, 2000, but not approved by USEPA before that date, are nonetheless "applicable water quality standards for purposes of the CWA" pursuant to section 131.21(c)(1). Collectively, this Order's restrictions on individual pollutants are no more stringent than required to implement the requirements of the CWA.



## E. Interim Effluent Limitations

Based on effluent monitoring data submitted by the Discharger, a comparison between the MEC and calculated AMEL values shows that the Discharger may be unable to consistently comply with effluent limitations established in this Order for arsenic, copper, and lead. As a result, this Order contains interim limitations for these parameters and a compliance schedule that allows the Discharger until May 18, 2010 to comply with the final effluent limitations. Within 1 year after the effective date of this Order, the Discharger must prepare and submit a compliance plan that describes the steps that will be taken to ensure compliance with applicable limitations.

40 CFR section 131.38(e) provides conditions under which interim effluent limitations and compliance schedules may be issued. The SIP allows inclusion of an interim limitation with a specific compliance schedule included in an NPDES permit for priority pollutants if the limitation for the priority pollutant is based on CTR criteria and the Discharger demonstrates that it is infeasible to achieve immediate compliance with the effluent limitations. Based on existing data, it appears that it is infeasible for the Discharger to immediately comply with the CTR-based effluent limitations for arsenic, copper, and lead at various locations. Interim effluent limitations and a compliance schedule are included in the Order for parameters, at discharge locations, where data indicates it is infeasible for the Discharger to achieve immediate compliance with the final effluent limitations.

Pursuant to the SIP (section 2.2.1, Interim Requirements under a Compliance Schedule), when compliance schedules are established in an Order, interim limitations must be included based on current treatment facility performance or existing permit limitations, whichever is more stringent to maintain existing water quality. There are insufficient data to perform a meaningful statistical analysis to develop interim limitations and effluent limitations for arsenic, copper, and lead were not established in the previous Order. Thus, the individual MECs for each discharge location shall serve as the interim effluent limitation concentration for the constituents. However, in the event that the SIP calculated maximum daily effluent limitation is greater than the MEC for a parameter at a specific location, the maximum daily effluent limitation is applicable immediately, as the interim limitation (Fire Protection effluent limitation for arsenic).

Available data indicates that the Discharger is immediately capable of compliance with the water quality based-effluent limitations for arsenic at Discharge Point Nos. WW-001 and WW-002. Thus, no interim effluent limitation for arsenic is granted at Discharge Point Nos. WW-001 and WW-002.

It should be noted that the Regional Water Board might take appropriate enforcement actions if interim limitations and requirements are not met.

The SIP requires that the Regional Water Board establish other interim requirements such as requiring the Discharger to develop a pollutant minimization plan and/or source control measures and participate in the activities necessary to achieve the final effluent limitations. This Order requires the Discharger to prepare and implement a pollution

prevention plan for arsenic, copper, and lead in accordance with CWC section 13263.3(d)(2).

The following interim limitations shall be effective until May 18, 2010, after which, the Discharger shall demonstrate compliance with the final effluent limitations.

**Table F-16. Interim Effluent Limitations**

Discharge Location	Parameter	Units	Maximum Daily
FP-001, FP-002 (Fire Protection Water)	Arsenic, Total Recoverable	µg/L	59.14
	Copper, Total Recoverable	µg/L	5.78
SC-001, SC-002 (Steam Condensate)	Copper, Total Recoverable	µg/L	77.3
	Lead, Total Recoverable	µg/L	58
WW-001, WW-002 (Water Weight Bag Effluent)	Copper, Total Recoverable	µg/L	19.3

**F. Land Discharge Specifications – Not Applicable**

**G. Reclamation Specifications – Not Applicable**

**V. RATIONALE FOR RECEIVING WATER LIMITATIONS**

**A. Surface Water**

Receiving water limitations of TENTATIVE ORDER NO. R9-2008-0048 are derived from the water quality objectives for bays and estuaries established by the Basin Plan (1994), the Bays and Estuaries Policy (1974), the California Toxics Rule (2000), and the State Implementation Policy (2005).

**B. Groundwater – Not Applicable**

## VI. RATIONALE FOR MONITORING AND REPORTING REQUIREMENTS

40 CFR section 122.48 requires that all NPDES permits specify requirements for recording and reporting monitoring results. Water Code sections 13267 and 13383 authorizes the Regional Water Board to require technical and monitoring reports. The Monitoring and Reporting Program (MRP), Attachment E of this Order, establishes monitoring and reporting requirements to implement federal and state requirements. The following provides the rationale for the monitoring and reporting requirements contained in the MRP for this facility.

### A. Influent Monitoring

Influent monitoring is necessary for an assessment of the feasibility of complying with effluent limitations and to characterize the qualities of the influent into the Fire Protection System. Monthly influent monitoring of copper for the fire protection system (previous carried out as "Receiving Water Monitoring", section E of MRP No. R9-2002-0161) has been carried over to this Order.

Monthly monitoring of the fire protection system intake for arsenic has been included because the fire protection water data indicated there was reasonable potential in the final effluent to exceed water quality criteria.

Monthly monitoring for pH, and annual monitoring for total suspended solids and turbidity has been included for fire protection system intake to characterize the qualities of the influent. In addition, annual monitoring of CTR priority pollutants have been included to determine if additional pollutants contained in the influent are at levels that may contribute to the final effluent exceeding water quality criteria.

### B. Effluent Monitoring

Pursuant to the requirements of 40 CFR section 122.44(i)(2) effluent monitoring is required for all constituents with effluent limitations. Effluent monitoring is necessary to assess compliance with effluent limitations, assess the effectiveness of BMPs and pollution prevention plans, to assess the impacts of the discharge on the receiving water, and determine compliance with effluent limitations.

1. Based on the industrial types of activities that occur on-site, and the types of discharges from the Facility, annual effluent monitoring at all effluent monitoring locations for settleable solids, turbidity, total suspended solids, oil and grease, total petroleum hydrocarbons, polynuclear aromatic hydrocarbons, tributyltin, lead, and total residual chlorine have been carried over from MRP No. R9-2002-0161.

#### 2. Fire Protection System Water and Water Weight Bag Effluent Monitoring (Monitoring Locations FP-001, FP-002, WW-001, and WW-002)

a. Monthly effluent flow monitoring has been revised to daily to accurately determine the volume of effluent being discharged from the Facility into the San Diego Bay.

ADMINISTRATIVE DRAFT

- b. Annual effluent monitoring of pH and temperature has been revised to monthly in order to better characterize the discharge of fire protection system water from the Facility into the San Diego Bay.
- c. Annual monitoring for arsenic has been revised to monthly, and monthly monitoring for copper has been re-established because the discharge of fire protection water and water weight bag effluent has been determined to have reasonable potential to exceed water quality criteria for these parameters. Increased monitoring is necessary to better characterize the discharge of fire protection system water and water weight bag effluent from the Facility into the San Diego Bay, and to determine compliance with effluent limitations.
- d. Annual monitoring of the fire protection system water and water weight bag effluent for the remaining CTR priority pollutants has been included to determine if reasonable potential exists for the discharges to exceed water quality criteria, as specified in section 1.3 of the SIP. Annual monitoring for cadmium, chromium, lead, mercury, nickel, silver, and zinc are included in this annual CTR monitoring and are no longer specified individually in the MRP.

### **3. Ballast Water (Monitoring Locations BW-001 and BW-002)**

- a. Monthly effluent flow monitoring has been established to accurately determine the volume of effluent being discharged from the Facility into the San Diego Bay.
- b. Annual effluent monitoring of pH and temperature has been established to characterize the discharge ballast water and potable water leaks from hoses from the Facility into the San Diego Bay.
- c. Quarterly monitoring for arsenic and copper have been established because data indicates that these pollutants are present in the receiving water at levels that exceed water quality criteria for these parameters, and these pollutants may be present in the discharge of ballast water in levels that exceed water quality criteria. Further, sufficient monitoring data must be collected for use in determining if intake credits are appropriate.
- d. Annual monitoring of ballast water for the remaining CTR priority pollutants has been included to determine if reasonable potential exists for the discharges to exceed water quality criteria, as specified in section 1.3 of the SIP.

### **4. Potable Water Leaks From Hoses (Monitoring Location Nos. PW-001 and PW-002)**

- a. Monthly effluent flow monitoring has been established to accurately determine the volume of effluent being discharged from the Facility into the San Diego Bay.

- b. Annual effluent monitoring of pH and temperature has been established to characterize the discharge ballast water and potable water leaks from hoses from the Facility into the San Diego Bay.
- c. Annual monitoring of ballast water for the remaining CTR priority pollutants has been included to determine if reasonable potential exists for the discharges to exceed water quality criteria, as specified in section 1.3 of the SIP.

**5. Steam Condensate Leaks From Hoses (Monitoring Location Nos. SC-001 and SC-002, formally considered a miscellaneous low volume discharge)**

- a. Monthly effluent flow monitoring has been revised to daily to accurately determine the volume of effluent being discharged from the Facility into the San Diego Bay.
- b. Annual effluent monitoring of pH and temperature has been revised to monthly in order to better characterize the discharge of fire protection system water from the Facility into the San Diego Bay.
- c. Annual monitoring for copper and lead has been revised to monthly because discharges of steam condensate leaks from hoses have been determined to have reasonable potential to exceed water quality criteria for these parameters. Further, increased monitoring is necessary to determine compliance with effluent limitations, where applicable.
- d. Annual monitoring of these miscellaneous discharges for the remaining CTR priority pollutants has been included to determine if reasonable potential exists for the discharges to exceed water quality criteria, as specified in section 1.3 of the SIP. Annual monitoring for arsenic, cadmium, chromium, mercury, nickel, silver, and zinc are included in this annual CTR monitoring and are no longer specified individually in the MRP.

**C. Whole Effluent Toxicity Testing Requirements**

This subsection discusses the rationale for the required whole effluent toxicity testing requirements such as the selected test species, endpoint, frequency of testing, etc. The rationale for whole effluent toxicity limitations should be discussed above in section IV.B.6.

**D. Receiving Water Monitoring**

**1. Surface Water**

Monitoring of the receiving water is necessary to determine if the discharges from the Facility are impacting the San Diego Bay, applicable beneficial uses, and aquatic life.

The receiving water monitoring for the fire protection system intake water has been moved to the Influent Monitoring portion of the MRP and is discussed in section VI.A of this Fact Sheet.

Receiving water monitoring has been established outside the influence of all Facility discharges to provide an accurate representation of the background levels of pollutants. This data is necessary to perform future RPAs during permitting efforts, and further will be necessary for the consideration of intake credits for ballast water and fire protection water.

Quarterly monitoring for arsenic, copper, and lead has been included because the Facility has been determined to have reasonable potential to exceed water quality criteria for these parameters at various discharge locations.

Annual monitoring of the remaining CTR priority pollutants has been added to help determine reasonable potential, as specified in section 1.3 of the SIP, for future permitting efforts.

## **2. Groundwater – Not Applicable**

ADMINISTRATIVE DRAFT

## E. Other Monitoring Requirements

1. Monitoring requirements for Floating Drydock submergence/emergence water discharge, Floating Drydock ballast tank monitoring; floating boom cleaning; spill and illicit discharges, chemical utilization, and waste hauling have been carried over from MRP No. R9-2002-0161 to help determine the effectiveness of the BMP Plan and ensure that appropriate BMPs are properly implemented.
2. The discharge of contact storm water to the San Diego Bay through Discharge Point Nos. SW-001 through SW-006 may contain pollutants from the surrounding area which could contribute to the exceedance of the water quality criteria/objectives of the receiving water. Storm water monitoring requirements have been carried over from Order No. R9-2002-0161 to determine the effects of storm water discharges on the receiving water and monitor the effectiveness of the BMP Plan.
3. The General Shipyard Permit (Order No. 97-36; NPDES No. CAG039001) established a sediment monitoring program for the shipyards the required the facilities to collect annual surficial sediment samples. The sediment monitoring program also required sampling at three background reference stations in San Diego Bay. The monitoring included sediment sampling for grain size, trace metals including cadmium, chromium, copper, nickel, silver, mercury, arsenic, lead, zinc, TBT, TPH, PCBs/PCTs, and PAHs, and an analysis of paint chips entrained in the sediment. The purpose of the sampling was to monitor the levels of sediment contamination and to use the information for any future cleanups and implementation of waste load allocations for the TMDL program. Order No. R9-2002-0161 carried over these requirements, but did not require sediment monitoring until the sediment cleanup (discussed in section II.B.3 of this Fact Sheet) at BAE had been completed. The sediment cleanup was not completed during the term of the previous Order and no sediment sampling was required to be conducted by the Discharger. The Regional Water Board is currently working on a Cleanup and Abatement Order which is expected to require the Discharger to participate in the clean up of the Shipyard Sediment Site. The time frame for the adoption of the final Cleanup and Abatement Order is expected within the time frame of this Order.

Sediment monitoring requirements have been carried over from Order No. R9-2002-0161. The MRP requires that the first set of samples from NASSCO sampling stations and reference stations be taken concurrently with the last post-cleanup sampling. This will establish sediment data after the cleanup that can be used to compare the subsequent annual sediment monitoring data submitted thereafter. The sediment data conditions after the cleanup will be used to compare or analyze trends in the concentrations in the sediment.

## VII. RATIONALE FOR PROVISIONS

### A. Standard Provisions

Standard Provisions, which apply to all NPDES permits in accordance with 40 CFR section 122.41, and additional conditions applicable to specified categories of permits in accordance with 40 CFR section 122.42, are provided in Attachment D. The Discharger

must comply with all standard provisions and with those additional conditions that are applicable under 40 CFR section 122.42.

40 CFR section 122.41(a)(1) and (b) through (n) establish conditions that apply to all State-issued NPDES permits. These conditions must be incorporated into the permits either expressly or by reference. If incorporated by reference, a specific citation to the regulations must be included in the Order. Section 123.25(a)(12) allows the state to omit or modify conditions to impose more stringent requirements. In accordance with section 123.25, this Order omits federal conditions that address enforcement authority specified in sections 122.41(j)(5) and (k)(2) because the enforcement authority under the Water Code is more stringent. In lieu of these conditions, this Order incorporates by reference Water Code section 13387(e).

ADMINISTRATIVE DRAFT



## B. Special Provisions

### 1. Reopener Provisions

- a. The Order may be reopened and modified in accordance with NPDES regulations at 40 CFR Parts 122 and 124, as necessary, to include additional conditions or limitations based on newly available information or to implement any USEPA approved, new, State water quality objective.

This Order may be modified, revoked and reissued, or terminated for cause including, but not limited to, the following:

- i. Violations of any terms or conditions of this Order
  - ii. Obtaining this Order by misrepresentation or failure to disclose fully all relevant facts.
  - iii. A change in any condition that requires either a temporary or permanent reduction or elimination of the authorized discharge.
- b. This Order may be re-opened and modified, to incorporate in accordance with the provisions set forth in 40 CFR Parts 122 and 124, to include requirements for the implementation of the watershed management approach.
  - c. This Order may be re-opened and modified, revoked, and reissued or terminated in accordance with the provisions of 40 CFR sections 122.44, 122.62 to 122.64, 125.62, and 125.64. Causes for taking such actions include, but are not limited to, failure to comply with any condition of this Order and permit, and endangerment to human health or the environment resulting from the permitted activity.
  - d. This Order may be re-opened and modified, to incorporate additional limitations, prohibitions, and requirements, based on the results of additional monitoring required by the MRP.
  - e. The filing of a request by the Discharger for modifications, revocation and reissuance, or termination of this Order, or a notification of planned change in or anticipated noncompliance with this Order does not stay any condition of this Order.

### 2. Special Studies and Additional Monitoring Requirements

a. Toxicity will go here...

### 3. Best Management Practices and Pollution Prevention

- a. In addition to numeric technology-based limitations, the previous Order determined that numeric effluent limitations for many parameters are infeasible. To carry out the purpose and intent of the CWA, the previous Order required the

ADMINISTRATIVE DRAFT

Discharger to develop and implement a BMP plan, as authorized by CWA section 304(e) and section 402(p), for toxic pollutants and hazardous substances, and for the control of storm water discharges. This Order requires the Discharger to continue to implement and regularly update an adequate BMP Plan as specified in Attachment G.

- b. **CWC section 13263.3(d)(2) Pollution Prevention Plans.** Section 13263.3 of the California Water Code states that pollution prevention should be the first step in the hierarchy for reducing pollution and managing wastes. Further, section 13263.3 (d)(1) states that a Regional Water Board may require a Discharger to complete and implement a pollution prevention plan if that discharger significantly contributes, or has the potential to significantly contribute, to the creation of toxic hot spots. The results of a reasonable potential analysis detailed in section IV.C.3 of this Fact Sheet indicate the Discharger has potential to contribute to the creation of toxic hot spots for arsenic, copper, and lead. The Discharger shall develop and implement a Pollution Prevention Plan for arsenic, copper, and lead, which at a minimum, meets the requirements outlined in CWC section 13263.3(d)(2).

The minimum requirements for the pollution prevention plans include the following:

- i. An analysis of one or more of the pollutants, as directed by the state board, a regional board, or a POTW, that the facility discharges into water or introduces into POTWs, a description of the sources of the pollutants, and a comprehensive review of the processes used by the discharger that result in the generation and discharge of the pollutants.
- ii. An analysis of the potential for pollution prevention to reduce the generation of the pollutants, including the application of innovative and alternative technologies and any adverse environmental impacts resulting from the use of those methods.
- iii. A detailed description of the tasks and time schedules required to investigate and implement various elements of pollution prevention techniques.
- iv. A statement of the discharger's pollution prevention goals and strategies, including priorities for short-term and long-term action.
- v. A description of the discharger's existing pollution prevention methods.
- vi. A statement that the discharger's existing and planned pollution prevention strategies do not constitute cross media pollution transfers unless clear environmental benefits of such an approach are identified to the satisfaction of the state board, the regional board, or the POTW, and information that supports that statement.
- vii. Proof of compliance with the Hazardous Waste Source Reduction and Management Review Act of 1989 (Article 11.9 (commencing with section 25244.12) of

Chapter 6.5 of Division 20 of the Health and Safety Code) if the discharger is also subject to that act.

viii. An analysis, to the extent feasible, of the relative costs and benefits of the possible pollution prevention activities.

ix. A specification of, and rationale for, the technically feasible and economically practicable pollution prevention measures selected by the discharger for implementation.

**4. Construction, Operation, and Maintenance Specifications – Not Applicable**

**5. Special Provisions for Municipal Facilities (POTWs Only) – Not Applicable**

**6. Other Special Provisions – Not Applicable**

**7. Compliance Schedules**

**a. Compliance Schedules for Final Effluent Limitations for Arsenic, Copper, and Lead**

Section 2.2 of the SIP requires interim requirements to be included in an NPDES permit if a compliance schedule is granted in accordance with section 2.1 of the SIP. Data submitted by the Discharger over the term of Order No. R9-2002-0161 indicates that the Discharger can not immediately meet applicable water quality criteria. A compliance schedule for the Discharger to achieve compliance with final effluent limitations for arsenic, copper, and lead have been granted to the Discharger in accordance with section 2.1 of the SIP. By May 18, 2010, the Discharger shall comply with the final effluent limitations for arsenic, copper, and lead.

Because this compliance schedule is greater than 1 year, in accordance with the section 2.2.1 of the SIP, the Discharger shall submit semi-annual progress reports in accordance with the Monitoring and Reporting Program.

**b. Pollution Prevention Plan**

As part of the interim requirements required under section 2.2 of the SIP, the Discharger shall prepare and implement a pollution prevention plan for arsenic, copper, and lead, in accordance with CWC section 13263.3(d)(2) to help implement and track efforts by the Discharger to comply with the final effluent limitations for arsenic, copper, and lead. The minimum requirements for the pollution prevention plan are outlined in this Fact Sheet, Attachment F, section VII.B.3.b. The Discharger is required to submit a work plan and time schedule for preparation of the pollution prevention plan shall be completed and submitted to the Regional Water Board **within 3 months of the effective date of this**

**Order.** The Pollution Prevention Plan shall be completed and submitted to the Regional Water Board **within nine (9) months of the effective date of this Order**, and progress reports shall be submitted in accordance with the Monitoring and Reporting Program.

## VIII. PUBLIC PARTICIPATION

The Regional Water Board is considering the issuance of WDRs that will serve as a NPDES permit for BAE Systems. As a step in the WDR adoption process, the Regional Water Board staff has developed tentative WDRs. The Regional Water Board encourages public participation in the WDR adoption process.

### A. Notification of Interested Parties

The Regional Water Board has notified the Discharger and interested agencies and persons of its intent to prescribe waste discharge requirements for the discharge and has provided them with an opportunity to submit their written comments and recommendations. Notification was provided through the following **<Describe Notification Process (e.g., newspaper name and date)>**

### B. Written Comments

The staff determinations are tentative. Interested persons are invited to submit written comments concerning these tentative WDRs. Comments must be submitted either in person or by mail to the Executive Office at the Regional Water Board at the address above on the cover page of this Order.

To be fully responded to by staff and considered by the Regional Water Board, written comments must be received at the Regional Water Board offices by 5:00 p.m. on **<Date>**.

### C. Public Hearing

The Regional Water Board will hold a public hearing on the tentative WDRs during its regular Board meeting on the following date and time and at the following location:

Date: **<Public Hearing Date>**

Time: **<Public Hearing Time>**

Location: **Regional Water Quality Control Board, San Diego Region  
Board Meeting Room  
9174 Sky Park Court, Suite 100  
San Diego, CA 92123**

Interested persons are invited to attend. At the public hearing, the Regional Water Board will hear testimony, if any, pertinent to the discharge, WDRs, and permit. Oral testimony will be heard; however, for accuracy of the record, important testimony should be provided in writing.

ADMINISTRATIVE DRAFT

Please be aware that dates and venues may change. Our Web address is  
<<http://www.swrcb.ca.gov/rwqcb9/>> where you can access the current agenda for  
changes in dates and locations.

ADMINISTRATIVE DRAFT

**D. Waste Discharge Requirements Petitions**

Any aggrieved person may petition the State Water Resources Control Board to review the decision of the Regional Water Board regarding the final WDRs. The petition must be submitted within 30 days of the Regional Water Board's action to the following address:

State Water Resources Control Board  
Office of Chief Counsel  
P.O. Box 100, 1001 I Street  
Sacramento, CA 95812-0100

**E. Information and Copying**

The Report of Waste Discharge (RWD), related documents, tentative effluent limitations and special provisions, comments received, and other information are on file and may be inspected at the Regional Water Board's address above at any time between 8:30 a.m. and 4:45 p.m., Monday through Friday. Copying of documents may be arranged through the Regional Water Board by calling (858) 467-2952.

**F. Register of Interested Persons**

Any person interested in being placed on the mailing list for information regarding the WDRs and NPDES permit should contact the Regional Water Board, reference this facility, and provide a name, address, and phone number.

**G. Additional Information**

Requests for additional information or questions regarding this Order should be directed to Vicente Rodriquez at (858) 467-2952.

**ATTACHMENT G - BEST MANAGEMENT PRACTICES PLAN REQUIREMENTS****I. Objectives**

The Best Management Practices (BMP) Plan has two primary objectives:

- A. To identify and evaluate sources of wastes and pollutants associated with ship construction, modification, repair, and maintenance facilities and activities which may affect the quality of waters of the State and waters of the United States; and
- B. To identify and implement site-specific BMP to reduce or prevent the discharge of wastes and pollutants to waters of the State and waters of the United States.

**II. Best Management Practices Program Manual**

The Discharger's BMP Plan shall be set forth in a written BMP Plan Manual that contains descriptions of onsite activities, pollutant sources, and pollutants; descriptions of BMPs used at the site; drawings; maps; and copies of and/or references to parts of other relevant programs. The BMP Plan Manual shall be revised whenever appropriate. It shall be readily available for review by Facility employees, other onsite personnel, and Regional Water Board, U.S. Environmental Protection Agency (USEPA), SDUPD, and other authorized inspectors.

The BMP Plan Manual is considered a report that shall be available to the public from the Regional Water Board under section 308(b) of the Clean Water Act.

**III. Planning and Organization****A. Pollution Prevention and Control Personnel**

The BMP Plan Manual shall identify the positions and individuals responsible for development, implementation, and revision of the BMP Plan and for conducting all monitoring requirements specified in this Order. The BMP Plan Manual shall clearly identify the responsibilities, duties, and activities of all pollution prevention and control personnel.

**B. Related Regulatory Requirements**

The BMP Plan Manual shall contain or incorporate by reference the appropriate elements of programs implemented at the site in connection with other regulatory requirements. The Discharger shall review all local, State, and federal requirements that impact, complement, are related to, or are consistent with the requirements of this Order. The BMP Plan Manual shall identify any existing onsite programs that include water pollution prevention or control measures relating to the requirements of this Order.

**IV. Site Map**

ADMINISTRATIVE DRAFT

The BMP Plan Manual shall include a site map that includes notes, legends, and other data as appropriate to ensure that the site map is clear and understandable. The site map shall be on an 8-1/2 x 11 inch or larger sheet. If necessary, the required information may be shown on multiple site maps.

The following information shall be included on the site map:

- A. The site boundaries; the boundaries of all drainage areas on the site; portions of the site impacted by run-on from surrounding areas; direction of flow and outlet point of each drainage area; onsite and nearby waters of the United States; areas of soil erosion; and municipal and onsite storm drain inlets into which runoff from the site may flow.
- B. The location of the site runoff collection and conveyance system and associated points of discharge, direction of flow, and any structural control measures that affect site runoff and run-on. Examples of structural control measures are storm drain inlets, catch basins, berms, detention ponds, secondary containment, oil/water separators, diversion barriers, etc.
- C. The boundaries of all impervious areas of the site, including paved areas, buildings, covered storage areas, or other roofed structures and respective discharge points.
- D. Locations where materials are directly exposed to precipitation and the locations where significant spills or leaks, identified in accordance with section VI.A.4 below, have occurred.
- E. Areas of industrial activity; this shall include the locations of all storage areas and storage tanks, shipping and receiving areas, fueling areas, vehicle and equipment storage/maintenance areas, material handling and processing areas, waste treatment, storage, and disposal areas, dust or particulate generating areas, cleaning and rinsing areas, and other areas of industrial activity which are potential pollutant sources.

## **V. List of Significant Materials**

The BMP Plan Manual shall include a list of significant materials handled and stored at the site. For each material on the list, the locations where the material is stored, received, shipped, and handled, as well as the typical quantities and frequencies, shall be described. The materials list shall include raw materials, intermediate products, final or finished products, recycled materials and waste or disposed materials.

## **VI. Description of Potential Pollutant Sources**

- A. The BMP Plan Manual shall include a narrative description of the industrial activities at the site, as identified in accordance with section IV.E above, associated potential pollutant sources, and pollutants that could be discharged. At a minimum, the following items related to industrial activities and the site shall be addressed:

### **1. Industrial Processes**

Each industrial process; the type, characteristics, and quantity of significant materials used in or resulting from the process; and description of the manufacturing, cleaning, rinsing,

ADMINISTRATIVE DRAFT



recycling, disposal, or other activities related to the process shall be described. Where applicable, areas protected by containment structures and the corresponding containment capacity shall be described.

## 2. Material Handling and Storage Areas

Each handling and storage area; the type, characteristics, and quantity of significant materials handled or stored; shipping, receiving, and loading procedures; and spill and leak prevention and response procedures shall be described. Where applicable, areas protected by containment structures and the corresponding containment capacity shall be described.

## 3. Dust and Particulate Generating Activities

All activities that generate dust or particulates and their discharge locations, the characteristics of dust and particulate pollutants, the approximate quantity of dust and particulate pollutants generated, and the primary locations where dust and particulate pollutants would settle shall be identified.

## 4. Significant Spills and Leaks

Materials that have spilled or leaked in significant quantities since April 17, 1994, including toxic chemicals (listed in 40 CFR 302) that have been discharged, as reported on USEPA Form R, and oil and hazardous substances in excess of reportable quantities (see 40 CFR 110, 117, and 302) shall be described.

The description shall include the type, characteristics, and approximate quantity of the materials spilled or leaked, the cleanup or remedial actions that have occurred or are planned, the approximate remaining quantity of materials that could be discharged, and the preventive measures taken to ensure spills and leaks do not recur. This list shall be updated continuously during the term of this Order.

## 5. Discharges

The Discharger shall investigate its site to identify all discharges and their sources. As part of this investigation, all drains (inlets and outlets) shall be evaluated to identify whether they connect to an onsite or municipal storm drain system or otherwise empty into waters of the United States.

All discharges shall be described. This shall include the source, quantity, frequency, and characteristics of the discharges and associated drainage area.

The BMP Plan Manual shall include BMPs to prevent, or minimize, the potential for contact of water discharged from the site, with significant materials and equipment.

## 6. Soil Erosion

ADMINISTRATIVE DRAFT

The site locations where soil erosion could occur shall be identified.

- B. The BMP Plan Manual shall include a summary of all areas of industrial activities, potential pollutant sources, and pollutants that could be discharged. This information shall be summarized in a form similar to Table G-1. The last column of Table G-1 "Best Management Practices," shall be completed in accordance with section VIII below.

ADMINISTRATIVE DRAFT

## EXAMPLE

**Table G-1. Assessment of Potential Pollution Sources and Corresponding Best Management Practices**

Area	Activity	Pollutant Source	Pollutant	Best Management Practices
Vehicle & Equipment Fueling	Fueling	Spills and leaks during delivery	Fuel oil	- Use spill and overflow protection
		Spills caused by topping off fuel tanks	Fuel oil	- Minimize run-on of storm water into the fueling area
		Hosing or washing down fuel area	Fuel oil	- Cover fueling area
		Leaking storage tanks	Fuel oil	- Use dry cleanup methods rather than hosing down area
		Rainfall running off fueling area, and rainfall running onto and off fueling area	Fuel oil	- Implement proper spill prevention control program - Implement adequate preventive maintenance program to prevent tank and line leaks - Inspect fueling areas regularly to detect problems before they occur - Train employees on proper fueling, cleanup, and spill response techniques

ADMINISTRATIVE DRAFT

**VII. Assessment of Potential Pollutant Sources**

A. The BMP Plan Manual shall include a narrative assessment of all industrial activities and potential pollutant sources as described in accordance with section VI above to determine:

1. Which areas of the site and activities at the site are likely sources of pollutants, and
2. Which pollutants are likely to be discharged. When performing this assessment, the Discharger shall consider and evaluate various factors, including current BMPs; quantities of significant materials handled, produced, stored, or disposed of; locations of potential pollutant sources; form of pollutants; likelihood of exposure of pollutants to wind and site runoff; history of spills and leaks; run-on from offsite sources; and other factors as appropriate for each potential pollutant source and each pollutant.

- B. The BMP Plan Manual shall identify the areas of and activities at the site that are likely sources of pollutants and the corresponding pollutants that are likely to be discharged.

The Discharger shall develop and implement BMPs as appropriate and necessary to prevent, or minimize the potential for, the discharge of pollutants associated with each potential pollutant source. The BMPs shall be described in accordance with section VIII below.

### **VIII. Best Management Practices**

- A. The BMP Plan shall include a narrative description of the BMPs to be implemented at the site for each pollutant and its potential source(s) identified in accordance with sections VI and VII above. The BMPs shall be developed and implemented to prevent, or minimize the potential for, the discharge of pollutants. Each pollutant and its potential source(s) may require one or more BMPs. Some BMPs may be appropriate for multiple pollutants and/or multiple potential sources, while other BMPs may be appropriate for only a single pollutant and/or only a single potential source.

The description of the BMPs shall identify the BMPs as (1) existing BMPs, (2) existing BMPs to be revised and implemented, or (3) new BMPs to be implemented. The description shall also include a discussion of the effectiveness of each BMP to prevent, or minimize the potential for, the discharge of pollutants. The BMP Plan Manual shall include a summary of the BMPs implemented for each potential pollutant source. This information shall be summarized in a form similar to Table G-1.

- B. The Discharger shall give highest priority to development and implementation of "Preventive BMPs," i.e., measures to reduce or eliminate the generation of pollutants and waste, such as waste minimization and Pollution Prevention (P2).

In addition, the Discharger shall develop and implement "Control BMPs," i.e. measures to control or manage pollutants and waste after they are generated and before they come into contact with water, including measures to prevent leaks, spills, and other releases.

The Discharger shall also develop and implement "Treatment BMPs," i.e., measures to remove pollutants and waste from water released to San Diego Bay.

As a contingency, the Discharger shall also develop and, as necessary, implement "Response BMPs," i.e., measures to respond to leaks, spills, and other releases with containment, control, and cleanup to prevent, or minimize the potential for, the discharge of pollutants and to minimize the adverse effects of such discharges.

- C. The BMP Plan shall include BMPs which adequately address the following:

1. Control of large solid materials

2. Abrasive blasting
3. Oil, grease, and fuel transfers
4. Paint and solvent use
5. Dust and overspray
6. Over water activities
7. Storm drain inlet protection
8. Hose, piping, and fitting use and maintenance
9. Segregation of water not containing pollutants from pollutants and from water containing pollutants
10. Segregation of water from debris
11. Hydroblasting
12. Material (including waste) storage
13. Sewage (black water) disposal
14. Gray water disposal
15. Oily bilge and ballast water disposal
16. Floating dry dock, graving dock, shipbuilding ways, and marine railway cleanup
17. Sally port protection
18. Discharges resulting from wind, tidal action, and site runoff (including rainfall runoff and other miscellaneous water flows)
19. Leaks and spills
20. Waste (including sludge) disposal
21. Recovery of ship launch grease/wax
22. Other activities with potential to result in discharges of wastes or pollutants to waters of the United States.

D. The BMP Plan Manual shall include non-structural and structural BMPs as appropriate.

1. Non-structural BMPs include but are not limited to:

a. Good Housekeeping

This consists of practical procedures to maintain a clean and orderly site, to separate water from pollutants, and to separate pollutants from water.

b. Preventive Maintenance

This includes the regular inspection and maintenance, including testing, of structural controls (catch basins, oil/water separators, etc.) as well as other site equipment and systems.

c. Material Handling and Storage

This includes procedures to minimize the potential for spills and leaks and to minimize exposure of significant materials to water.

d. Spill and Leak Response

This includes containment, control, and cleanup procedures.

e. Onsite Personnel Training

This includes training of all onsite personnel whose actions or lack thereof could result in the discharge of pollutants. Such personnel include employees of the Discharger as well as other onsite personnel, such as personnel associated with subcontractors, customers (e.g. U.S. Navy), and others. This also includes training of personnel who are responsible for (1) implementing the BMP Plan, (2) conducting inspections, sampling, and visual observations, and (3) managing the site drainage system. Training should address topics such as good housekeeping, material handling and storage, spill response, and actions necessary to implement all BMPs identified in the BMP Plan Manual. The BMP Plan Manual shall identify periodic dates for such training. Records shall be maintained of all training sessions held.

f. Waste Handling/Recycling

This includes procedures and processes to handle, store, recycle, and dispose of waste materials.

g. Recordkeeping and Internal Reporting

This includes procedures to ensure that all records of inspections, spills, maintenance activities, corrective actions, visual observations, etc., are developed, retained, and provided, as necessary, to the appropriate personnel.

h. Erosion Control and Site Stabilization

This includes all sediment and erosion control activities. This may include the planting and maintenance of vegetation, diversion of run-on and runoff, placement of sandbags, silt screens, or other sediment and erosion control devices, etc.

i. Inspections

This includes, in addition to the preventive maintenance inspections identified above, an inspection schedule of all potential pollutant sources. Tracking and follow-up procedures shall be implemented to ensure adequate corrective actions are taken and adequate BMPs are developed and implemented.

j. Quality Assurance

This includes procedures to ensure that the BMP Plan is adequate and that all elements of the BMP Plan are completely implemented.

2. Structural BMPs include but are not limited to:

a. Overhead Coverage

This includes structures that provide coverage over or enclosure of materials, work areas, and potential pollutant sources.

b. Retention Ponds

This includes basins, ponds, surface impoundments, bermed areas, etc., that prevent pollutants from being discharged from the site.

c. Control Devices

This includes berms or other devices that channel or route water away from potential pollutant sources.

d. Secondary Containment Structures

This includes structures around storage tanks and other areas for the purpose of containing leaks and spills.

e. Treatment

This includes inlet controls, infiltration devices, oil/water separators, detention ponds, vegetative swales, etc., which remove pollutants from water before they are discharged.

**IX. Annual Comprehensive Site Compliance Evaluation**

The Discharger shall conduct at least one comprehensive site compliance evaluation (evaluation) annually. The evaluation shall be conducted not less than 8 or more than 16 months apart. The BMP Plan shall be revised, as appropriate, and the revisions implemented within 90 days of the evaluation. Evaluations shall include the following:

- A. A review of all visual observation records, inspection records, and sampling and analysis results.
- B. A visual inspection of all potential pollutant sources for evidence of, or the potential for, the discharge of pollutants.
- C. A review and evaluation of all BMPs (both structural and non-structural) to determine whether the BMPs are adequate, properly implemented and maintained or whether additional BMPs are needed. A visual inspection of equipment needed to implement the BMP Plan, such as spill response equipment, shall be included.
- D. An evaluation report that includes, (1) identification of personnel performing the evaluation, (2) the date(s) of the evaluation, (3) necessary BMP Plan revisions, (4) schedule for implementing BMP Plan revisions, (5) any incidents of non-compliance and the corrective actions taken, and (6) a certification that the Discharger is in compliance with this Order. If the above certification cannot be provided, the evaluation report shall include an explanation of why the Discharger is not in

compliance with this Order. The evaluation report shall be submitted as part of the annual effluent report (see Monitoring and Reporting Program), retained for at least 5 years, and signed and certified in accordance with the requirements of this Order.

ADMINISTRATIVE DRAFT